

**COMPLETION REPORT FOR PROBE HOLE C3830 (TX-105)
TX TANK FARM 200 WEST AREA**

K. D. Reynolds

Duratek Federal Services, Inc., Northwest Operations

March 2003

Prepared for the Office of River Protection, CH2M HILL Hanford Group, Inc.
Richland, Washington

CONTENTS

1.0 INTRODUCTION	1
2.0 SUMMARY OF ACTIVITIES.....	5
3.0 DRILLING AND SAMPLING DETAILS	6
3.1 DRILLING	6
3.1.1 Casing Driving.....	7
3.1.2 Split-Spoon Sampler.....	9
3.2 SAMPLING	9
3.2.1 Soil Sampling	9
3.3 GEOPHYSICAL LOGGING	11
4.0 PROBE HOLE DECOMMISSIONING	12
5.0 ENVIRONMENTAL, SAFETY, AND HEALTH	13
6.0 REFERENCES	13

APPENDICES

A Field Activity Reports.....	A-i
B Geologic/Sample Logs.....	B-i
C Geophysical Logs.....	C-i
D Chain of Custody/Sample Analysis Requests.....	D-i
E Field Documentation.....	E-i
F Field Logbook Entries.....	F-i
G Equipment Cleaning Forms	G-i
H Washington State Department of Ecology Documentation	H-i
I Vadose Zone Tensiometer Placement.....	I-i
J Noise Monitoring	J-i

LIST OF FIGURES AND PLATE

Figure 1. Location of 241-TX Tank Farm.	3
Figure 2. C3830 and Other Wells, Probe Locations, and Tanks.....	4
Figure 3. C3830 Blow Counts—Depth vs. Blow.	8
Plate 1. TX-105 Probe Hole C3830	following page 14

LIST OF TABLES

Table 1. Sample Depths.	10
Table 2. Dry Wells Utilized for Cross-Section Correlation.....	11

TERMS

BGS	below ground surface
cm	centimeter
cps	counts per second
DOE	U.S. Department of Energy
ft	foot
ft•lb	foot-pound
in.	inch
MDL	minimum detection limit
pCi/g	picocuries per gram
vf%	volume fraction percent moisture

COMPLETION REPORT FOR PROBE HOLE C3830 (TX-105) TX TANK FARM 200 WEST AREA

1.0 INTRODUCTION

The U.S. Department of Energy (DOE) assigned the River Protection Project Single-Shell Tank Program the tasks of transferring waste from the single-shell tanks to double-shell tanks and developing and implementing a strategy to retrieve single-shell tank and miscellaneous underground storage tank waste. In support of the eventual retrieval of this waste, the Single-Shell Tank Program Vadose Zone Project was given responsibility for collecting and providing subsurface data from the single-shell tank farm facilities. This data is intended to provide an understanding of the distribution and movement of contaminants in the vadose zone under and adjacent to the tank farms. Subsequently, a work plan was prepared to collect field characterization data in and near Waste Management Area TX. This planned activity is intended to support decision-making relative to DOE/RL-99-36, *Phase 1 RCRA Facility Investigation/Corrective Measures Study Work Plan for Single-Shell Tank Waste Management Areas*. The document, RPP-7578, *Site-Specific SST Phase 1 RFI/CMS Work Plan Addendum for WMAs T and TX-TY*, was necessary to identify and plan characterization efforts as part of DOE/RL-99-36.

The data requirement goals identified through a data quality objective process are documented in RPP-7578. The outlined goals include the tasks, project responsibilities, and schedules for the characterization efforts. One of the identified field characterization efforts is the collection of vadose zone data from the installation of up to four closed-end probe holes in the TX tank farm.

Utilizing RPP-7578 as guidance, DFSNW-DOW-006, *Description of Work: Drilling and Sampling* was prepared defining the methodology and actions for drilling and sampling a series of probe holes in the TX tank farm. This report provides information for the planned series of probe driving activities. DFSNW-DOW-006 included selected sampling depths, borehole construction and sampling methodologies, geophysical logging requirements, decommissioning directions, environmental health and safety program directions and quality control drivers. This borehole completion report is a summary of activities and sampling efforts of probe hole C3830 adjacent to tank TX-105 and near tank TX-101. This is the final probe hole of the series planned under DFSNW-DOW-006. See Figure 1 for a location map of the 241-TX tank farm and Figure 2 for a detailed location map of C3830 and other wells, probe locations, and tanks in the project area. Appendices to this completion report contain copies of the following documentation generated during performance of the outlined work:

- Field Activity Reports (Appendix A)
- Geologic/Sample Logs (Appendix B)

- Geophysical Logs (Appendix C)
 - High-Purity Germanium (HPGe) and moisture logs from probe hole C3830
- Chain of Custody/Sample Analysis Requests (Appendix D [includes summary sheets])
- Blow Count Forms (Appendix E)
 - Casing driving
- Field Logbook Entries (Appendix F)
- Equipment Cleaning Form (Appendix G)
- Washington State Department of Ecology (Ecology) documentation (Appendix H)
 - Start and decommissioning cards
 - Completion report
- Vadose Zone Tensiometer Placement (Appendix I)
 - Instrument detail diagram
 - Percolation test graphs
 - As-Built Diagram
 - Memo detailing instrument placement
- Noise Monitoring (Appendix J)

Figure 1. Location of 241-TX Tank Farm.





Figure 2. C3830 and Other Wells, Probe Locations, and Tanks.



2.0 SUMMARY OF ACTIVITIES

Duratek Federal Services, Inc., Northwest Operations (DFSNW) began preliminary design and procurement planning for samplers, casing jacks and wrenches in support of the TX scope of work in late January 2002. This was followed by procurement of the necessary field equipment and support (drill pipe, casing, casing tips and shoes, samplers, casing and drill pipe wrenches, casing jacks and contracting for drilling support) in February and March. Fifteen dry wells in the vicinity of the planned probes were selected for moisture logging and were logged and analyzed by late February 2002. Concurrent with equipment procurement and moisture logging and analysis, DFSNW-DOW-006 was prepared and submitted. The purpose of DFSNW-DOW-006 was to guide field activities, call out selected sample depths and provide documentation of planned activities to tank farm operations. The first probe hole of the series (C3832) adjacent to single shell tank TX-104 was completed during May and June of 2002, the second (C3831) was completed during July and the first two weeks of August.

Field activities relating to C3830 (the third and last of the three planned probes) commenced with mobilization of the probe driving platform and support equipment from C3831 (TX-107) to the C3830 (TX-105) probe site on August 15, 2002. Field Activity Reports were generated by DFSNW field oversight personnel for each day of the deployment and copies are included in Appendix A. Excluding weekends and holidays there were 25 field days associated with mobilization, drilling, sampling, logging, decommissioning, and de-mobilization related to probe hole C3830. The total days on location included one and one-half days of rig-up activities, four days for borehole decommissioning and vadose tensiometer placement, five days of geophysical logging, and 11 days of driving casing and sampling. At the conclusion of the decommissioning and tensiometer placements three and one-half days were required to demobilize the drilling platform and support equipment from the TX Tank Farm. During field operations for this probe hole no full days were lost as down time from rig failures, weather delays or other operational problems. A total of 18 hours was lost for the listed causes during C3830 activities over the 25 days of field operations. The total depth of 116.75 ft below ground surface (BGS), as measured by steel line tape, was reached on September 5, 2002. At this depth the probe tip was approximately 2.95 ft into the highly cemented portion of the calcium carbonates of the Cold Creek sediments. Blow counts exceeded manufacture's recommended numbers per advance depth at this point. Prior to decommissioning, geophysical logging was completed to total depth with moisture and HPGe spectral gamma detectors. During the decommissioning process two small scale percolation tests were conducted and four (4) sets of in situ tensiometers were placed at depths of 96.25 ft, 49.95 ft, 7.45 ft and 2.9 ft BGS. See Appendix H for the Washington-State-required Water Well Report documenting the borehole construction details and Appendix I for graphed details of the percolation tests, tensiometer instruments and an As-Built diagram of the instrument placements.

Eighteen (18) split-spoon samples, 1.25 ft long x 2.5 in. in diameter, were collected at specified depths for potential chemical and radiological analysis during the drilling/driving of this probe. (See Appendix D for information regarding sample depth, Chain of Custody, etc. and Appendix B for geologic descriptions of the samples retrieved).

The position of this boring was initially located by CH2M HILL Hanford Group, Inc. DFSNW personnel subsequently documented the location at Easting 566795.41 m, Northing 136166.88 m at an elevation above sea level of 206.005 m (675.869 ft) by use of Global Positioning Satellite instrumentation.

3.0 DRILLING AND SAMPLING DETAILS

3.1 DRILLING

Per the referenced description of work (DFSNW-DOW-006), the casing utilized was a design configuration proven at the SX-108 Slant Borehole Project; e.g., P-110 carbon steel, 18 cm (7-in.) OD x 13 cm (5-13/16-in.) ID with a pin pile thread. Details of the design configuration and methodology are discussed in RPP-6917, *SX-108 Slant Borehole Completion Report*. The majority of the casing string was composed of 5-ft joints with several 2-, 3- and 4-ft joints for positioning the probe end at proposed sampling intervals. Based on engineering calculations, prior testing and previous success at SX-108, the thread pattern was selected to withstand the expected driving force as well as the maximum pull back capacity of the casing jacks. The drilling rig was equipped with an ICE-40 pile driver, which delivers approximately 40,000 ft•lb of force in the vertical position. The rig, pile driver and remote handling arm configuration were successfully utilized previously for the SX-108 Slant Borehole project. The pile driver provided adequate force to drive the casing to a total depth of 116.75 ft BGS. At approximately 113.8 ft BGS the first occurrence of the highly cemented facies of the Cold Creek sediments were encountered and only another 2.95 ft of further casing advance was possible. At this point the blow counts exceeded the manufacture's recommendations and the casing was determined to be at refusal. Because of lessons learned from C3832 (TX-104) and the success of the C3831 (TX-107) effort, the designed base plate with attachment points for the jacks was again utilized to control the jack position and aid in casing alignment.


No problems with handling or making up the casing were encountered. Minor problems with operation and maintenance of the wrench breakout and jack system continued during the activities for this probe hole. Approximately six hours of operational time were expended adjusting, cleaning and realigning the jacks, wrenches and driving apparatus during the 11 days of driving activities. Modifications and improvement of the system are still ongoing. Improvements in the system and increasing crew efficiencies have resulted in shorter job duration when compared to the previous probe holes in TX. The initial driving activities at C3832 required 18 days, C3831 required 15 days and C3830 required 11 days to collect roughly the same number of samples and reach depths equivalent to the first two probe holes. The changes in pipe handling methodologies and improved crew work efficiencies have contributed to an approximate 35% reduction in the time required to complete the field activities.

3.1.1 Casing Driving

To accomplish the objectives of acquiring samples the casing was driven in a closed configuration (e.g., removable tip in place) to the planned sample depths, and the tip and inner rod were then removed. A sampler was placed on the rods, inserted through the casing to total depth and the pile driver was utilized to drive the sampler ahead. The manufacturer of the pile driver has recommended an operational limit for determining refusal. That limit is reached when less than one inch of casing advance is gained for 10 full stroke blows of the pile driver.

Blow counts vs. advancement of the casing were recorded and, as expected, varied over depth. Field records (blow counts recorded during driving of the casing to total depth) are provided in Appendix E. Tracking and comparison of blow counts when utilizing this type of pile driver for engineering purposes is complicated by the fact that the hammer reacts to the resistance of the probe to advance. When little resistance is encountered, the hammer does not stroke to its full length and less than the maximum 40,000 ft•lb is applied to advance the casing. When resistance to the advance of the probe increases, full hammer strokes occur and the full potential force of the hammer is used to advance the casing. Figure 3 is a graphic representation of the blow count vs. depth for C3830. At a depth of 112 ft BGS the blow count increased from an average of 20 to 35 blows per foot to 70+ blows per foot. This increased resistance to driving was interpreted as increased resistance to casing advance caused by the caliche-rich silt facies of the Cold Creek. The contact of the Cold Creek with overlying Hanford sand and silts is observed to have occurred at 99.5 ft BGS (as described in sample 14 taken from 98.97 ft to 100.36 ft BGS). Casing refusal (blow counts in excess of 10 blows per inch) occurred between 113.8 ft. and 116.75 ft. BGS. Between these depths, blow counts exceeded 70 blows per 6 inches (i.e., less than one inch per 10 blows-refusal). The contact between the carbonate rich sands and silts and the highly cemented zones was observed to have occurred at 113.8 ft BGS in a sample collected from 113.55 ft to 115.0 ft BGS. Casing was driven to a total depth of 116.75 ft (1.75 ft past the last sample interval).

Figure 3. C3830 Blow Counts—Depth vs. Blow.



3.1.2 Split-Spoon Sampler

A split-spoon sampler with an additional inner steel liner for increased structural strength was specially designed for collecting sediment samples ahead of the driven casing. This sampler collects a 2.5-in. x 1-ft driven sample in two 6-in. long stainless steel liners. Additional material is retrieved in the .25-ft (3-in.) long drive shoe (nose cone) of the sampler body. The sampler body is designed to house the split liner and the sample liners. For this scope of work a sampler utilized in the SX-108 Project was redesigned to accommodate larger liners (2.5-in. vs. 2-in.) through removal of the lead shielding utilized for the previous deployment. Removing the shielding and increasing sample size were undertaken because of the lower expected contamination levels when compared to the previous deployment. This lower expected level of radioactive contamination allowed larger volumes of soil with less shielding to be safely handled at the surface in the field and at the laboratory. The sampler is deployed and advanced by use of an inner string of 4½-in. drill pipe.

Sample handling and any potential contaminate spread, as well as potential exposure of onsite personnel were minimized by capping the bottom of the split-spoon sampler, placing it in a transport container and using the remote-handling arm. The complete split-spoon assembly was placed in a transport drum and transported to Pacific Northwest National Laboratory with the sample intact in the split spoon. The laboratory performed the breakout of the samples from the split spoon and extruded the soil from the liners. No onsite breakdown of the samples was performed.

3.2 SAMPLING

3.2.1 Soil Sampling

During advancement of the borehole, sampling was attempted 18 times using a split-spoon sampler. The split spoon was driven utilizing the diesel pile drive hammer a minimum of 1.25 ft into the bottom of the borehole at each selected sample location. Overdriving of the sampler on the C3832 (TX-104) probe hole had resulted in problems in the laboratory when attempting to remove the samples from the stainless steel inner liners. No sample over compaction problems were reported by the laboratory for removal of the samples retrieved from C 3830.

Projected target depths for sample collection were first outlined in the referenced RFI/CMS documentation (RPP-7578) prepared by CH2M HILL. Further refinement of the preferred sample depths was derived by performing moisture logging in 14 dry wells surrounding all of the proposed probe locations in the TX Farm. To accomplish the target refinement, cross section correlations of observable and identifiable geologic features were prepared from the logging data. These features were compared to the sample depths identified in the RFI/CMS (RPP-7578) and with the approval of the CH2M HILL Project Lead, sampling targets based on projected geologic features (e.g., facies contacts, grain size changes, features such as tank excavation compaction zones) were selected and documented in DFSNW-DOW-006. Table 1 below provides information on targeted sample depths, actual sample depths, generalized geophysical log detections and sediment types for the interval.

Table 1. Sample Depths.

DOW Target (C3830)	TX-105 (3830)	Log Detections/sediment
15-16	14.96-16.31	no remarks/backfill sand
28-29	27.91-29.25	moisture (m) inc/backfill sand-gravel
41-42	40.93-42.49	slight m inc/backfill gravelly sand
46-47	46.05-47.5	no remarks/backfill gravel-sand
47-48	47.5-49.0	m inc/backfill gravel-sand
53-54	52.98-54.36	m-gamma inc/backfill contact -Hanford bdd slt-and
57-58	56.99-58.37	m-inc/fine-med snd
59-60	58.29-59.7	m-peak/snd-slt interbds
66-67	66.06-67.46	incr m-slight gamma inc/ H. med sand
72-73	71.95-73.3	H. med-fine sand
77-78	76.98-78.35	slty fine sand, interbdd med sand
81-82	80.91-82.21	m increase/fine-med sand
86-87	86.11-87.41	m-peak/ med sand change to 86.6 slt-snd interbds
99-100	98.97-100.36	m peak, gamm inc/H-Cold Creek contact, snd w lam silt-snd
100-101	100.32-101.72	m peak, gamm peak/lam fine-med snd w silt
103-104	102.99-104.44	low m, gamma high/compacted silt lam
108-109	107.89-109.19	decrease m-gamma/silt to fine sand
Unplanned Refusal	113.55-115.00	decrease m-gamma/silt with contact caliche 113.8
119-120		
124-125		
134-135		
146-147		

Of the 18 samples collected, 34 of the 36 six-inch liners recovered were 100% full. Two liners from samples taken at 102.99 ft BGS and 107.89 ft BGS (one liner in each of the two sample areas) were only 90% full on recovery. At the time of this report no detailed information relating to laboratory-derived soil moisture content, sample radiochemistry or chemical contamination is available. As noted above several samples were taken in zones that had characteristics that correlate to the geophysical responses observed on the log plots in Appendix C. Descriptions of

the sediments retrieved in the 18 samples are found in Appendix B and Plate 1 (a graphic depiction of the geophysics, expected lithologies and retrieved samples with sample descriptions and formation contact depths).

3.3 GEOPHYSICAL LOGGING

Prior to the initiation of probe driving activities, open dry wells in the vicinity of the probe locations were reviewed for accessibility. Fifteen wells were selected for potential logging. See Figure 2 for the location of the wells selected (marked with tank farm well numbers, for example 51-04-05). Fourteen of the wells were subsequently logged by DFSNW with neutron-moisture instrumentation developed specifically for use at Hanford by DFSNW and analyzed for percent volume moisture content. Results of this logging scope (log plots, log data reports and analysis reports) were reported in Appendix C of RPP-12017, *Completion Report for Probe Hole C3832 (TX-104) TX Tank Farm 200 West Area*. Correlation cross-sections utilizing these logs were generated to select sample depths for the probe locations. Table 2 below lists the dry wells utilized for cross section correlation.

Table 2. Dry Wells Utilized for Cross-Section Correlation.

1. 51-00-07	8. 51-03-01
2. 51-04-06	9. 51-03-02
3. 51-04-05	10. 51-00-06
4. 51-03-09	11. 51-02-02
5. 51-04-02	12. 51-05-07
6. 51-03-11	13. 51-05-05
7. 51-03-12	14. 51-00-03

When the C3830 probe reached refusal (total depth) the inner drill string and tip were removed and geophysical logging was conducted utilizing DFSNW equipment and personnel prior to decommissioning of the probe hole. Appendix C contains copies of the log plots, log data reports, analysis results, and interpretations generated from the probe hole (See log plots for C3830 in Appendix C). The following logging suites were utilized:

1. Gross gamma
2. Spectral (HPgE) gamma logging
3. Neutron-Moisture.

The total gamma logs for the probe hole show several areas of marked changes in the background count rates. The first high count area (approximately 310–320 counts per second) at 1 ft BGS corresponds to the highest Cs-137 contamination observed in the borehole. Cesium was detected from surface to approximately 11 ft BGS with the peak level of 7.5 pCi/g at 1 ft BGS. No other Cesium detections above the minimum detection levels (MDL) of the instrumentation (0.1 pCi/g) were encountered in the probe hole. An additional change in total gamma count rate occurs where an increase from an average 150 cps to approximately 200 cps is

observable at approximately 52 ft. BGS. This change corresponds to the depth where the probe crossed from tank excavation backfill into undisturbed Hanford sediments and is reflected in an approximate 5 pCi/g increase in natural potassium ratio. The volume percent moisture log also reflects this material (formation) change by demonstrating an increase from an average of 5 to 7 vf % in the back fill to 7 to 9 vf % in the undisturbed Hanford sediments. The total gamma count rate also increases from approximately 200 counts to 250 to 300 counts in the 98 ft to 110 ft BGS zone. This depth corresponds with the transition from Hanford sands and silts into the Cold Creek facies of silts- and carbonate-rich sediments. The total count increase is reflected in a marked thorium concentration change, as it relates to the natural potassium/uranium/thorium ratios of spectral response measured by the HPGe detector. Indications of uranium at levels below the statistically valid detection level (10 pCi/g) were observed in the 50 ft to 68 ft BGS interval, as shown on the log plots contained in Appendix C.

4.0 PROBE HOLE DECOMMISSIONING

Decommissioning of probe hole and construction of the borehole tensiometer placement for C3830 commenced on September 16, 2002, and the installation and decommissioning was completed on September 19, 2002. Decommissioning activities met all applicable sections of WAC 173-160, "Minimum Standards for Construction and Maintenance of Wells," requirements. As the casing was extracted, dry bentonite materials were added to fill the annular space. Approximately 40 cubic feet of material (39.8 ft³ in 56 sacks) was placed into the probe hole as the casing was extracted. This volume slightly exceeds the minimal calculated volume (35.4 ft³) for filling the void space created by casing extraction. The probe hole was filled within approximately one ft of grade and covered with gravel to conform to tank farm requirements.

Two percolation tests were conducted to provide baseline information relating to formation conductivity at 103.54 ft to 105.87 ft BGS and at 57.01 ft to 59.05 ft BGS. Appendix I contains the graphs of the falling head test data and an As-Built diagram of the final construction.

As the borehole was backfilled with bentonite the percolation test zones were isolated from the bentonite filled sections by placement of a sand pad approximately 1 ft in thickness. A measured volume of water was then added to the borehole and the infiltration rate (increase in depth to water as the fluid penetrated the borehole wall) was monitored. To avoid having the testing influence the instrument readings after placement, the test zones were filled with an additional ± 4 ft of bentonite, and the instruments were placed in the borehole surrounded by sand. After the instruments were encased in the sand, bentonite was added to fill the borehole to the next instrument placement zone. The details of the construction are depicted on the As-Built diagram in Appendix I.

5.0 ENVIRONMENTAL, SAFETY, AND HEALTH

During the field operations, the job site was surveyed by both DFSNW Operations Safety and CH2M HILL Hanford Group, Inc., Tank Farm Industrial Hygiene and Safety personnel for safety and health compliance. To ensure compliance with hearing protection guidelines, noise levels were monitored during the first set of probe driving operations. The results of this monitoring are provided in Appendix J for reference. There were no lost time, reportable *Occupational Safety and Health Act of 1970* injuries, or first aid cases during performance of the work activities relating to this scope of work.

6.0 REFERENCES

DFSNW-DOW-006, 2002, *Description of Work: Drilling and Sampling*, Rev. 0, Duratek Federal Services, Inc., Northwest Operations, Richland, Washington.

DOE/RL-99-36, 1999, *Phase 1 RCRA Facility Investigation/Corrective Measures Study Work Plan for Single-Shell Tank Waste Management Areas*, U.S. Department of Energy, Richland Operations Office, Richland, Washington.

Occupational Safety and Health Act of 1970, 29 USC 651 et seq.

RPP-6917, 2000, *SX-108 Slant Borehole Completion Report*, Rev. 0, prepared by Waste Management Technical Services for CH2M HILL Hanford Group, Inc., Single Shell Tank Farms Vadose Zone Program, Richland, Washington.

RPP-7578, 2001, *Site-Specific SST Phase 1 RFI/CMS Work Plan Addendum for WMAs T and TX-TY*, Rev. 0, CH2M HILL Hanford Group, Inc., Richland, Washington.




RPP-12017, 2002, *Completion Report for Probe Hole C3832 (TX-104) TX Tank Farm 200 West Area*, Rev. 0, prepared by Duratek Federal Services, Inc., Northwest Operations, for CH2M Hill Hanford Group, Inc., Richland, Washington.

WAC 173-160, "Minimum Standards for Construction and Maintenance of Wells," *Washington Administrative Code*, as amended.


This page intentionally left blank.

APPENDIX A
FIELD ACTIVITY REPORTS

This page intentionally left blank.

		Duratek Federal Services, Inc., Northwest Operations				
DRILLING AND SAMPLING (PERCUSSION) DAILY WORK RECORD						Page 1 of 1
WELL I.D.: C3830		WELL NUMBER: N/A		REPORT NUMBER: 71		DATE: August 15, 2002 Thursday
CONTRACT NUMBER: 8248-55			START CARD NO: S00631		RIG MODEL/NO: SIMCO 5000 (Rig 106)	
PURPOSE: Daily safety meeting. Remove shoe, prepare rig for moving to next site.				REFERENCE: DFSNW-DOW-006, Rev. 0		LOCATION: TX Tank Farm, 200 West
REFERENCE MEASURING POINT: Steel Plate plus 0.25 ft (ground level)				TOTAL SHIFT FOOTAGE: 0.0 ft.		
CONSTRUCTION DESCRIPTION: N/A				BORING DEPTH: START: 0 ft END: 0 ft		START TIME: 07:00 END TIME: 16:30 CONTRACTOR TIME: 0.5 TOTAL TIME: 9.5
CASING SIZE 7.0 " OD	SET-AT DEPTH NA	TYPE CASING CS	DRIVE POINT DIMENSION Shoe, 7.5 " OD	START DEPTH 0 ft	END DEPTH 0 ft.	
DOCUMENTED DOWNTIME N/A WEATHER CONDITIONS (373-2716 or 373-2710) 8:30 81F, wind NW 8-12 mph, WBGT 70F, 25% humidity, 29.16 barometric pressure			CASING SUMMARY Bottom of 7 " OD casing (start of shift) = 0 ft. Bottom of 7" OD casing (end of shift) = 0 ft. Casing (7 in OD) stick up (end of shift) = 0 ft. Total casing = 0 ft.		PERSONNEL: OPERATOR: K. Olson D Morris/D Curry WA LICENSE #: 1217 OTHER: S.H. Worley R. Sharp (Opr) K. Johnson (PIC) K. Harteilius (HPT)	
TIME		DESCRIPTION OF OPERATIONS/REMARKS				
FROM	TO					
07:30	8:00	Conduct daily safety meeting. During the daily safety meeting crew discussed anticipated activities: Removal of shoe, Lay down mast and have rig prepared for moving to next site.				
8:05	9:30	In Farm. Equipment inspection completed with no deficiencies noted. Removed shoe, moved casings, started the addition of the revised ""ring"" for the casing slips. Required tap to clean threads came out of farm to collect tools and take a break.				
9:45	11:30	Back in the farm attach "Ring". 10:30 Layed Mast down. Secured Rig.				
11:30	12:00	Lunch				
12:00	1:00	More prep. Work for moving rig. Secured the Casing Jacks.				
1:00	1:30	Pre-Job meeting! New Package has arrived! Reviewed JHA, Route map and rig placement				
1:30	1:45	Waiting for Truck/Teamsters				
1:45	2:30	Teamster/truck here signed in and in the Farm! Rig has been moved off site and staged away from tanks to be placed in position on Monday morning! Surveyed out of farm.				
REPORT BY: S. H. Worley TITLE: Field Team Lead SIGNATURE: 				REVIEWED BY: MG Gardner TITLE: Project Manager DATE: 10-8-02 SIGNATURE: 		

		Duratek Federal Services, Inc., Northwest Operations				
DRILLING AND SAMPLING (PERCUSSION) DAILY WORK RECORD						Page 1 of 1
WELL I.D.: C3830		WELL NUMBER: N/A		REPORT NUMBER: 72		DATE: August 19, 2002 Monday
CONTRACT NUMBER: 8248-55			START CARD NO: S00631		RIG MODEL/NO: SIMCO 5000 (Rig 106)	
PURPOSE: Daily safety meeting. Set-up drill unit and support equipment.				REFERENCE: DFSNW-DOW-006, Rev. 0		LOCATION: TX Tank Farm, 200 West
REFERENCE MEASURING POINT: Steel Plate plus 0.25 ft (ground level)				TOTAL SHIFT FOOTAGE: 0.0 ft.		
CONSTRUCTION DESCRIPTION: N/A				BORING DEPTH:		START TIME: 07:00 END TIME: 16:30 CONTRACTOR TIME: 0.5 TOTAL TIME: 9.5
CASING SIZE	SET-AT DEPTH	TYPE CASING	DRIVE POINT DIMENSION	START DEPTH	END DEPTH	
7.0 " OD	NA	CS	Shoe, 7.5 " OD	0 ft	0 ft.	
DOCUMENTED DOWNTIME				CASING SUMMARY		PERSONNEL: OPERATOR: K. Olson D Morris/D Curry WA LICENSE #: 1217 OTHER: S.H. Worley R. Sharp (Opr) K. Johnson (PIC) K. Hartilius (HPT)
N/A				Bottom of 7 " OD casing (start of shift) = 0 ft.		
WEATHER CONDITIONS (373-2716 or 373-2710)				Bottom of 7 " OD casing (end of shift) = 0 ft.		
9:30 75F, wind N 3 mph, WBGT 70F, 32% humidity, 29.06 barometric pressure				Casing (7 in OD) stick up (end of shift) = 0 ft.		
				Total casing = 0 ft.		
				SAMPLE SUMMARY		
				N/A		
TIME		DESCRIPTION OF OPERATIONS/REMARKS				
FROM	TO					
07:20		Arrive on site, Blue water Crew, Ricky and Clint only folks on site. Waiting for truck drivers to move rig and Steel plate. Conduct daily safety meeting. During the daily safety meeting crew discussed anticipated activities. Tire low on Rig, tried calling shop (busy) Kenny arrives he has compressor and will retrieve more hose to reach tire from outside fence.(7:45) Unlocked gate to get the plate moved,				
7:50		Truck drivers arrive, sent to ACE in. Opened Farm Gate Crew in to move steel plate and oil pad.				
9:30		Rig in transport to next hole.				
10:30		Rig set, truck out of the farm, Out of farm for break.				
10:45	12:00	In Farm to set up rig.				
12:00	12:30	Lunch				
12:30	16:30	Rig Set-up, Casing set up over the hole, ready to drill tomorrow AM. (10.23' of 7" casing including shoe)				
		Will need height of deck from ground-surface and other relevant base measurements.				
REPORT BY: S.H. Worley				REVIEWED BY: MG Gardner		
TITLE: Field Team Lead				TITLE: Project Manager		
SIGNATURE: 				DATE: 10-8-02		
				SIGNATURE: 		

		Duratek Federal Services, Inc., Northwest Operations				
DRILLING AND SAMPLING (PERCUSSION) DAILY WORK RECORD						Page 1 of 3
WELL I.D.: C3830		WELL NUMBER: N/A		REPORT NUMBER: 73	DATE: August 20, 2002 Tuesday	
CONTRACT NUMBER: 8248-55		START CARD NO: S00631		RIG MODEL/NO: SIMCO 5000 (Rig 106)		
PURPOSE: Daily safety meeting. Drive casing to a depth of 27.91 ft. Obtain samples S02083-01 (equip blank), S02083-02 and S02083-03.				REFERENCE: DFSNW-DOW-006, Rev. 0		LOCATION: TX Tank Farm, 200 West
REFERENCE MEASURING POINT: Steel Plate plus 0.25 ft (ground level)				TOTAL SHIFT FOOTAGE: 29.25 ft.		
CONSTRUCTION DESCRIPTION: N/A				BORING DEPTH:		START TIME: 07:00 END TIME: 16:30 CONTRACTOR TIME: 0.5 TOTAL TIME: 9.5
CASING SIZE	SET-AT DEPTH	TYPE CASING	DRIVE POINT DIMENSION	START DEPTH	END DEPTH	
7.0 " OD	NA	CS	Shoe, 7.5 " OD	0 ft	27.91 ft	
DOCUMENTED DOWNTIME			CASING SUMMARY			PERSONNEL: OPERATOR: K. Olson D Morris/D Curry WA LICENSE #: 1217 OTHER: D.E. Skoglie R. Sharp (Opr) K. Johnson (PIC) K. Hartelius (HPT)
N/A			Bottom of 7 " OD casing (start of shift) = 0 ft.			
WEATHER CONDITIONS (373-2716 or 373-2710)			Bottom of 7 " OD casing (end of shift) = 27.91 ft			
9:30 75F, wind N 3 mph, WBGT 70F, 32% humidity, 29.06 barometric pressure			Casing (7 in OD) stick up (end of shift) = 1.0 ft			
			Total casing = 26.09 ft			
			SAMPLE SUMMARY			
			Equipment Blank: S02083-01			
			Sample: S02083-02 (#1) 14.96 – 16.31 (1.35 ft)			
			Sample: S02083-03 (#2) 27.91 – 29.25 ft (1.34 ft)			
TIME		DESCRIPTION OF OPERATIONS/REMARKS				
FROM	TO					
07:00	08:09	Daily safety meeting conducted. Discussed anticipated activities (07:20). Reroute hydraulic lines for rotary head latching mechanism. Adjust head and obtain measurements for constant (3.35 ft ground level to top of work deck). Reset drive head and align/level drill unit.				
08:09	09:15	Hammer will not pump up (fuel). Bleed system (08:20). Drive casing to 6.19 ft bgs. 10.44 – (3.35 + .9). Blows 3/2/2/2/3/3. Tab on operator side came off. Level hydraulic jacks.				
09:15	09:40	Add casing 5.0 ft (total 15.44 ft) and Dp 5.0 ft (total 16.06 ft). Set up hammer.				
09:40		Drive casing to 11.19 ft bgs. 15.94 – (3.35 + 1.4). Blows 8/14/12/10/9. Secure hammer/disassemble drive head.				
10:00	10:08	Add casing 4.0 ft (total 19.44 ft) and Dp 4.0 ft (total 20.06). Set up hammer.				
10:08	10:09	Drive casing to 14.96 ft bgs. 19.44 – (3.35 + 1.13). Blows 12/10/8/6. Secure hammer/disassemble drive head.				
10:09	10:57	Back pull casing .25 ft. Trip Dp out of bore –hole. Run sampler in boring. Set-up hammer/drive head.				
10:57	11:20	Drive sample S02083-02 (#1) 14.96 – 16.31 ft (1.35 ft). Blows 1/1/1 (10:58). Sample in drum @ 11:20.				
11:20	11:57	Back-pull and remove casing 4 ft. Trip into the boring with Dp. Add casing 5.0 (total 20.44 ft) and Dp 5.0 (total 21.06 ft).				
11:57	12:50	Lunch (11:57 – 12:35) Set-up hammer				
12:50	12:59	Drive casing to 16.02 ft bgs. 20.44 – (3.35 + 1.07). Blows 8/4. Secure hammer/disassemble drive head.				
12:59	13:13	Add casing 5.0 ft (total 25.44 ft) and Dp 5.01 ft (total 26.07) @ 13:08. Set up hammer.				
13:13	13:15	Drive casing to 20.94 ft bgs. 25.44 – (3.35 + 1.15). Blows 10/10/10/12/13. Secure hammer/disassemble head.				
12:59	13:35	Add casing 5.0 ft (total 30.44 ft) and Dp 5.0 ft (total 31.07) @ 13:30. Set up hammer.				
13:35	13:40	Drive casing to 26.02 ft bgs. 30.44 – (3.35 + 1.07). Blows 14/14/14/14/15. Secure hammer/disassemble head.				
13:40	13:52	Add casing 2.0 ft (total 32.44 ft) and Dp 2.0 ft (total 33.07) @ 13:48. Set up hammer.				
13:52	14:15	Drive casing to 27.91 ft bgs. 32.44 – (3.35 + 1.18). Blows 20/11. Secure hammer/disassemble head. Trip out.				
14:15	14:48	Trip in sampler @ 14:26. Drive sample S02083-03 (27.91 – 29.25). Trip out in drum @ 14:48.				
14:48	16:30	Back-pull 2 ft casing. Trip in Dp. Conduct maintenance and documentation. Secure site.				
REPORT BY: D.E. Skoglie				REVIEWED BY: MG Gardner		
TITLE: Field Team Lead				TITLE: Project Manager		
SIGNATURE: <i>David E. Skoglie</i>				SIGNATURE: <i>MG Gardner</i> DATE: 10-8-02		



Duratek Federal Services, Inc., Northwest Operations

C3830 SAMPLE FORM

FAR No. 73

Page 2 of 3

Sample No. 502083 - 02 Sample Tracking No. 1

Target Depth 15 to 16

(1) 3.35 top of rig floor above ground

(2) 4.48 casing stickup above ground

Csg Total (3) 19.44 - Stickup (2) 4.48 = TD (4) 14.96

Does not include drive head

Backpull stickup (2+5) .25

Sample depth (4) 14.96 to (4+6) 16.31


Blow Count			
	.5 ft	1 ft	1.35 ft
Start Time	1	1	1
End Time			
1057			
1058			

Estimated Recovery: 100%

Remarks:

- (1) Sample in drum @ 11:20 hrs.
 (2) Sample moist on tip (bottom)

- 1 = Top of rig floor above ground
 2 = Stickup of csg above ground 1 + measure from floor to top csg = SU
 3 = Total csg length
 4 = Depth of csg = Total Depth (TD)
 Total csg - SU⁽²⁾ = TD
 5 = Casing back pull
 6 = Sampler drive distance
 7 = Total depth of driven sample = 4 + 6



PREPARED BY (Please print): D.E. SKOGGIE

TITLE: FTL DATE: 08 20 02

SIGNATURE: *D.E. Skoggie*

REVIEWED BY (Please print): MG GARDNER

TITLE: *Mgr*

DATE:

SIGNATURE: *MG Gardner*

10-8-02



Duratek Federal Services, Inc., Northwest Operations

C3830

SAMPLE FORM

FAR No. 73Page 3 of 3Sample No. 502083-03 Sample Tracking No. 2Target Depth 28 to 29(1) 3.35 top of rig floor above ground(2) 4.53 casing stickup above groundCsg Total (3) 32.44 - Stickup (2) 4.53 = TD (4) 27.91

Does not include drive head

Backpull stickup (2+5) .25Sample depth (4) 27.91 to (4+6) 29.25


	Blow Count		
			<u>1.34</u>
	.5 ft	1 ft	<u>1.5 ft</u>
Start Time			
<u>1428</u>	<u>2</u>	<u>2</u>	<u>1</u>
End Time			
<u>1429</u>			

Estimated Recovery: 100%

Remarks:

(1) Sample in drum @ 14:48 hrs.


- 1 = Top of rig floor above ground
 2 = Stickup of csg above ground 1 + measure from floor to top csg = SU
 3 = Total csg length
 4 = Depth of csg = Total Depth (TD)
 Total csg - SU⁽²⁾ = TD
 5 = Casing back pull
 6 = Sampler drive distance
 7 = Total depth of driven sample = 4 + 6



PREPARED BY (Please print): D.E. SIOGLIE
 TITLE: FTL DATE: 8/20/02
 SIGNATURE: David E. Sioglie

REVIEWED BY (Please print): MG GARDNER
 TITLE: MR DATE: 10-8-02
 SIGNATURE: MG Gardner

DFSNW-WS-00

		Duratek Federal Services, Inc., Northwest Operations					
DRILLING AND SAMPLING (PERCUSSION) DAILY WORK RECORD						Page 1 of 3	
WELL I.D.: C3830		WELL NUMBER: N/A		REPORT NUMBER: 74		DATE: August 21, 2002 Wednesday	
CONTRACT NUMBER: 8248-55		START CARD NO: S00631		RIG MODEL/NO: SIMCO 5000 (Rig 106)			
PURPOSE: Daily safety meeting. Drive casing to a depth of 46.05 ft. Obtain samples S02083-04 and S02083-05.				REFERENCE: DFSNW-DOW-006, Rev. 0		LOCATION: TX Tank Farm, 200 West	
REFERENCE MEASURING POINT: Steel Plate plus 0.25 ft (ground level)				TOTAL SHIFT FOOTAGE: 18.25 ft.			
CONSTRUCTION DESCRIPTION: N/A							
CASING SIZE 7.0" OD	SET-AT DEPTH NA	TYPE CASING CS	DRIVE POINT DIMENSION Shoe, 7.5" OD	START DEPTH 27.91 ft	END DEPTH 46.05 ft	BORING DEPTH: START: 29.25 ft END: 47.5 ft.	START TIME: 07:00 END TIME: 16:30 CONTRACTOR TIME: 0.5 TOTAL TIME: 9.5
DOCUMENTED DOWNTIME 2 hr – health physics			CASING SUMMARY Bottom of 7" OD casing (start of shift) = 27.91 ft. Bottom of 7" OD casing (end of shift) = 46.05 ft. Casing (7 in OD) stick up (include bkpull) = 1.3 ft. Total casing = 50.45 ft.			PERSONNEL: OPERATOR: K. Olson D Morris/D Curry WA LICENSE #: 1217 OTHER: D.E. Skoglie/S. Worley Snook (Opr) K. Johnson (PIC) K. Hartelius (HPT)	
WEATHER CONDITIONS (373-2716 or 373-2710) 9:30 62F, wind W 3 -6 mph, 58% humidity, 29.269 barometric pressure			SAMPLE SUMMARY Sample: S02083-04 (#3) 40.93–42.49 (1.35 ft) 100% Sample: S02083-05 (#4) 46.05 –47.5 ft (1.45 ft) 100%				
TIME FROM TO		DESCRIPTION OF OPERATIONS/REMARKS					
07:00	07:18	Daily safety meeting conducted. Discussed anticipated activities. Complete equip inspection.					
07:18	07:42	Add casing 5.01 (total 35.45 ft) and Dp 5.01 (36.08 ft). Set hammer.					
07:42	07:43	Drive casing to 30.95 ft bgs. 35.45 – (3.35 + .1.15). Blows 8/10/10/2. Secure hammer/disassemble drive head.					
07:43	08:00	Add casing 5.0 ft (total 40.45 ft) and Dp 5.0 ft (total 41.08). Set up hammer.					
08:00	08:11	Drive casing to 36.1 ft bgs. 40.45 – (3.35 + 1.0). Blows 10/10/13/15/16. Secure hammer/disassemble dr/head.					
08:11	08:26	Add casing 5.0 ft (total 45.45 ft) and Dp 5.01 ft (total 46.09). Set up hammer.					
08:26	08:30	Drive casing to 40.93 ft bgs. 45.45 – (3.35 + 1.17). Blows 13/15/14/14/10. Secure hammer/remove dr/head.					
08:30	09:17	Back pull casing .25 ft. (08:34) Trip Dp out of bore –hole. Run sampler in boring. Set-up hammer/drive head.					
09:17	09:40	Drive sample S02083-04 (#3) 40.93 – 42.49 ft (1.56 ft). Blows 1/2/1 (09:18). Sample in drum @ 09:40 hrs.					
09:40	10:37	Trip into the boring with Dp. Break 10:00 – 10:22. Add casing 5.0 (total 50.45 ft) and Dp 5.0 (total 51.09 ft).					
10:37	10:44	Set-up hammer (10:42). Drive casing to 46.05ft bgs. 50.45 – (3.35 + 1.05). Blows 6/9/8/9/12.					
10:44	11:08	Secure hammer/disassemble drive head. Back-pull casing .25 ft. Trip Dp out of boring.					
11:08	11:30	Run sampler to bottom.					
11:30	12:00	Lunch					
12:00	1:30	Back in the farm, drive sample S02083-05 (#4) 46.05- 47.5' (1.45) Blows 2 (12:30) sample in drum (12:45) Tagged Bottom 47.45 ft. bgs. Ran sampler back in hole. HPT had to leave, shut down drilling					
1:30	2:15	Lay mast down and conduct mast and component inspection. No deficiencies noted. The mast was set back up and out of farm.					
2:15	3:00	Fill out reports leave site.					
3:00	4:30	BSE crew discusses daily operations and equipment maintenance.					
REPORT BY: D.E. Skoglie/S. Worley TITLE: Field Team Lead SIGNATURE: <i>D.E. Skoglie</i>				REVIEWED BY: MG Gardner TITLE: Project Manager SIGNATURE: <i>MG Gardner</i>		DATE: 10-8-02	



Duratek Federal Services, Inc., Northwest Operations

C 3830

SAMPLE FORM

FAR No. 74Page 2 of 3Sample No. 5020 83-04 Sample Tracking No. 3Target Depth 41 to 42(1) 3.35 top of rig floor above ground(2) 4.52 casing stickup above groundCsg Total (3) 45.45 - Stickup (2) 4.52 = TD (4) 40.93

Does not include drive head

Backpull stickup (2+5) .25Sample depth (4) 40.93 to (4+6) 42.49


	Blow Count			<u>1.56</u>
	.5 ft	1 ft	<u>1.5 ft</u>	
Start Time				
<u>0917</u>	<u>1</u>	<u>2</u>	<u>1</u>	
End Time				
<u>0918</u>				

Estimated Recovery: 100%

Remarks:

(1) Sample in drum @ 09:40 hrs.

- 1 = Top of rig floor above ground
 2 = Stickup of csg above ground 1 + measure from floor to top csg = SU
 3 = Total csg length
 4 = Depth of csg = Total Depth (TD)
 Total csg - SU⁽²⁾ = TD
 5 = Casing back pull
 6 = Sampler drive distance
 7 = Total depth of driven sample = 4 + 6



PREPARED BY (Please print): D.E. SKOGLIE
 TITLE: FTL DATE: 08 21 02
 SIGNATURE: David E. Skoglie


REVIEWED BY (Please print): MG GARDNER
 TITLE: MGR DATE: 10 08 02
 SIGNATURE: MG Gardner





Duratek Federal Services, Inc., Northwest Operations

<p>C3830 SAMPLE FORM</p> <p>Sample No. <u>502083-05</u> Sample Tracking No. <u>4</u></p> <p>Target Depth <u>46</u> to <u>47</u></p> <p>(1) <u>3.35</u> top of rig floor above ground</p> <p>(2) <u>4.4</u> casing stickup above ground</p> <p>Csg Total (3) <u>50.45</u> - Stickup (2) <u>4.4</u> = TD (4) <u>46.05</u></p> <p>Does not include drive head</p> <p>Backpull stickup (2+5) <u>.25</u></p> <p>Sample depth (4) <u>46.05</u> to (4+6) <u>47.5</u></p> <div style="text-align: right; margin-right: 50px;">Blow Count <u>1.45</u></div> <table border="1" style="width: 100%; border-collapse: collapse; margin-top: 10px;"> <thead> <tr> <th></th> <th>.5 ft</th> <th>1 ft</th> <th><u>1.5</u> ft</th> </tr> </thead> <tbody> <tr> <td>Start Time <u>1229</u></td> <td style="text-align: center;">1</td> <td style="text-align: center;">1</td> <td style="text-align: center;">1</td> </tr> <tr> <td>End Time <u>1230</u></td> <td></td> <td></td> <td></td> </tr> </tbody> </table> <p>Estimated Recovery: <u>100%</u></p> <p>Remarks:</p> <p style="margin-left: 40px;">(1) Sample in drum @ 12:50 hrs.</p> <p>1 = Top of rig floor above ground 2 = Stickup of csg above ground 1 + measure from floor to top csg = SU 3 = Total csg length 4 = Depth of csg = Total Depth (TD) Total csg - SU⁽²⁾ = TD 5 = Casing back pull 6 = Sampler drive distance 7 = Total depth of driven sample = 4 + 6</p>		.5 ft	1 ft	<u>1.5</u> ft	Start Time <u>1229</u>	1	1	1	End Time <u>1230</u>				<p>FAR No. <u>74</u> Page <u>3</u> of <u>3</u></p> <div style="text-align: center;"> </div>
	.5 ft	1 ft	<u>1.5</u> ft										
Start Time <u>1229</u>	1	1	1										
End Time <u>1230</u>													
<p>PREPARED BY (Please print): <u>D.E. SKOGLIE</u></p> <p>TITLE: <u>FTL</u> DATE: <u>082102</u></p> <p>SIGNATURE: <u>David E. Skoglie</u></p>	<p>REVIEWED BY (Please print): <u>MG GARDNER</u></p> <p>TITLE: <u>MBR</u> DATE: <u>10-08-02</u></p> <p>SIGNATURE: <u>MG Gardner</u></p>												

DFSNW-WS-00

		Duratek Federal Services, Inc., Northwest Operations				
DRILLING AND SAMPLING (PERCUSSION) DAILY WORK RECORD						Page 1 of 1
WELL I.D.: C3830		WELL NUMBER: N/A		REPORT NUMBER: 75		DATE: August 22, 2002 Thursday
CONTRACT NUMBER: 8248-55			START CARD NO: S00631		RIG MODEL/NO: SIMCO 5000 (Rig 106)	
PURPOSE: Daily safety meeting. Drive casing to a depth of 56.99 ft bgs. Obtain samples S02083-06, S02083-07 and S02083-08.				REFERENCE: DFSNW-DOW-006, Rev. 0		LOCATION: TX Tank Farm, 200 West
REFERENCE MEASURING POINT: Steel Plate				TOTAL SHIFT FOOTAGE: 10.87 ft.		
CONSTRUCTION DESCRIPTION: N/A				BORING DEPTH: START: 47.5 ft END: 58.37 ft		START TIME: 07:00 END TIME: 16:30 CONTRACTOR TIME: 0.5 TOTAL TIME: 9.5
CASING SIZE 7.0" OD	SET-AT DEPTH NA	TYPE CASING CS	DRIVE POINT DIMENSION Shoe, 7.5" OD	START DEPTH 46.05 ft	END DEPTH 56.99ft	
DOCUMENTED DOWNTIME N/A WEATHER CONDITIONS (373-2716 or 373-2710) 15:25: Temperature 88 F, Humidity 26%, Barometric pressure 26.62, Wind SW 6 mph			CASING SUMMARY Bottom of 7" OD casing (start of shift) = 46.05 ft. Bottom of 7" OD casing (end of shift) = 56.99 Casing (7 in OD) stick up (end of shift) = 1.11 ft SAMPLE SUMMARY Sample: S02083-06 (#5) 47.5 – 49.0 (1.5 ft) 100% Sample: S02083-07 (#6) 52.98 – 54.36 (1.38 ft) 100% Sample: S02083-08 (#7) 56.99 – 58.37 (1.38 ft) 100%		PERSONNEL: OPERATOR: K. Olson D Morris/D Curry WA LICENSE #: 1217 OTHER: D.E. Skoglie R. Sharp/ S. Snook (Opr) K. Johnson (PIC) K. Harteilius (HPT)	
TIME FROM TO		DESCRIPTION OF OPERATIONS/REMARKS				
07:00 07:18		Daily safety meeting conducted. Discussed anticipated activities (07:23). Complete equip main/inspection.				
07:18 07:42		Add casing that was removed for mast inspection. Set hammer.				
07:43 08:18		Drive sample S02083-06 (#5) 47.5 – 49.0 ft (1.5 ft). Blows 1/2/1 (07:44). Sleeve sample and place cap (1 o-ring and a swipe of well-guard). Sample in drum @ 08:18 hrs. Set-up next sampler.				
08:18 08:50		Add casing 5.0 ft (total 55.45 ft) and Dp 5.01 ft (total 56.1 ft). Set up hammer.				
08:50 08:11		Drive casing to 50.87 ft bgs. 55.45 – (3.35 + 1.23). Blows 7/11/13/20/15. Secure hammer/disassemble dr/head.				
08:11 08:26		Add casing 2.0 ft (total 57.45 ft) and Dp 2.0 ft (total 58.1). Set up hammer.				
08:26 09:20		Drive casing to 52.98 ft bgs. 57.45 – (3.35 + 1.12). Blows 15/16. Secure hammer/remove dr/head.				
09:20 10:52		Tip is stuck. Break 09:45 – 10:00. Fuel truck in RBA fueling support generator. Repair hydraulic hose (tighten connection). Remove tip with hydraulic jacks. Trip Dp out of boring @ 10:52.				
10:52 11:09		Run the sampler in and set-up the drive head.				
11:11 12:00		Drive sample S02083-07 (52.98 – 54.36) 1.38 ft. Blows 3/3/2. Sample at the surface @ 11:37. No radiological contamination noted. Sample in drum @ 11:42.				
12:00 12:45		Lunch. Mr. Flower fabricated slips for the 7 inch. A welding and cutting permit was prepared and approved. Kutrite was attempted to be installed on the vertical slip bars. The Kutrite will need to be placed in a horizontal access at a later date. A tab was welded on the hammer as a back-up to the cable securement system.				
12:45 13:24		Add casing 4.0 ft (total 61.45 ft) and Dp 4.0 ft (total 62.1 ft). Set up hammer.				
13:24 13:37		Drive casing to 56.99 ft bgs @13:28. 61.45 – (3.35 + 1.11). Blows 11/28/34/31. Secure hammer/disassemble dr/head. Back pull casing .25				
13:37 14:53		Trip out Dp (14:03). Trip in with sampler and set up drive head (14:25). Drive sample S02083-08 (56.99 – 58.37) 1.38 ft. Blows 3/4/2. Trip sampler out on surface @ 14:50 and in drum @ 14:53 hrs.				
14:53 16:30		Tag @ 58.29 ft bgs. Run sampler to bottom. Secure site. Pickup Dp from pipeyard.				
REPORT BY: D.E. Skoglie TITLE: Field Team Lead SIGNATURE: <i>David E. Skoglie</i>				REVIEWED BY: MG Gardner TITLE: Project Manager DATE: 10-08-02 SIGNATURE: <i>MG Gardner</i>		

	Duratek Federal Services, Inc., Northwest Operations		
C3830 SAMPLE FORM	FAR No. <u>75</u> Page <u>2</u> of <u>4</u>		
Sample No. <u>502083-06</u> Sample Tracking No. <u>5</u>			
Target Depth <u>48</u> to <u>49</u>			
(1) <u>3.35</u> top of rig floor above ground			
(2) <u>3.0</u> casing stickup above ground			
Csg Total (3) <u>50.45</u> - Stickup (2) <u>3.0</u> = TD (4) <u>47.45</u>			
Does not include drive head			
Backpull stickup (2+5) <u>.25</u>			
Sample depth (4) <u>47.45</u> to (4+6) <u>49.0</u>			
Blow Count			
	.5 ft	1 ft	1.5 ft
Start Time	<u>1</u>	<u>2</u>	<u>1</u>
End Time			
Estimated Recovery: <u>100%</u>			
Remarks:			
(1) DTB TAG recorded @ <u>47.45</u> (back to back sample).			
(2) Sample in Drum @ <u>0818 hrs</u>			
1 = Top of rig floor above ground 2 = Stickup of csg above ground 1 + measure from floor to top csg = SU 3 = Total csg length 4 = Depth of csg = Total Depth (TD) Total csg - SU ⁽²⁾ = TD 5 = Casing back pull 6 = Sampler drive distance 7 = Total depth of driven sample = 4 + 6			
PREPARED BY (Please print): <u>D.E. Skoglie</u> TITLE: <u>FTL</u> DATE: <u>08/22/02</u> SIGNATURE: <u>David E. Skoglie</u>		REVIEWED BY (Please print): <u>MG GARDNER</u> TITLE: <u>MR</u> DATE: <u>10-8-02</u> SIGNATURE: <u>MG Gardner</u>	



DFS NW-WS-00



Duratek Federal Services, Inc., Northwest Operations

<p>C3830 SAMPLE FORM</p> <p>Sample No. <u>5020 83-07</u> Sample Tracking No. <u>6</u></p> <p>Target Depth <u>53</u> to <u>54</u></p> <p>(1) <u>3.35</u> top of rig floor above ground</p> <p>(2) <u>4.47</u> casing stickup above ground</p> <p>Csg Total (3) <u>57.45</u> - Stickup (2) <u>4.47</u> = TD (4)</p> <p>Does not include drive head <u>52.98</u></p> <p>Backpull stickup (2+5) <u>.25</u></p> <p>Sample depth (4) <u>52.98</u> to (4+6) <u>54.36</u></p> <table border="1" style="margin-left: auto; margin-right: auto;"> <thead> <tr> <th></th> <th colspan="3">Blow Count <u>1.38</u></th> </tr> <tr> <th></th> <th>.5 ft</th> <th>1 ft</th> <th><u>1.5 ft</u></th> </tr> </thead> <tbody> <tr> <td>Start Time <u>11 11</u></td> <td><u>3</u></td> <td><u>3</u></td> <td><u>2</u></td> </tr> <tr> <td>End Time <u>11 12</u></td> <td></td> <td></td> <td></td> </tr> </tbody> </table> <p>Estimated Recovery: <u>100%</u></p> <p>Remarks: <u>(1) Sample in drum @ 11:42 hrs</u></p> <p>1 = Top of rig floor above ground 2 = Stickup of csg above ground 1 + measure from floor to top csg = SU 3 = Total csg length 4 = Depth of csg = Total Depth (TD) Total csg - SU⁽²⁾ = TD 5 = Casing back pull 6 = Sampler drive distance 7 = Total depth of driven sample = 4 + 6</p> <p>PREPARED BY (Please print): <u>D.E. SKOGHIE</u> TITLE: <u>FTL</u> DATE: <u>08 22 02</u> SIGNATURE: <u>Dave Skoghie</u></p>		Blow Count <u>1.38</u>				.5 ft	1 ft	<u>1.5 ft</u>	Start Time <u>11 11</u>	<u>3</u>	<u>3</u>	<u>2</u>	End Time <u>11 12</u>				<p>FAR No. <u>75</u> Page <u>3</u> of <u>4</u></p> <p>REVIEWED BY (Please print): <u>MB BARNER</u> TITLE: <u>MBR</u> DATE: <u>10-08-02</u> SIGNATURE: <u>MBB</u></p>
	Blow Count <u>1.38</u>																
	.5 ft	1 ft	<u>1.5 ft</u>														
Start Time <u>11 11</u>	<u>3</u>	<u>3</u>	<u>2</u>														
End Time <u>11 12</u>																	

DFSNW-WS-00



Duratek Federal Services, Inc., Northwest Operations

C3830 SAMPLE FORM

FAR No. 75

Page 4 of 4

Sample No. 502083-08 Sample Tracking No. 7

Target Depth 57 to 58

(1) 3.35 top of rig floor above ground

(2) 4.46 casing stickup above ground

Csg Total (3) 61.45 - Stickup (2) 4.46 = TD (4)
Does not include drive head 56.99

Backpull stickup (2+5) .25

Sample depth (4) 56.99 to (4+6) 58.37


Blow Count 1.38			
	.5 ft	1 ft	1.5 ft
Start Time 1425	3	4	2
End Time 1426			

Estimated Recovery: 100%

Remarks:


① Sample in down @ 14:53 hrs.

- 1 = Top of rig floor above ground
 2 = Stickup of csg above ground 1 + measure from floor to top csg = SU
 3 = Total csg length
 4 = Depth of csg = Total Depth (TD)
 Total csg - SU⁽²⁾ = TD
 5 = Casing back pull
 6 = Sampler drive distance
 7 = Total depth of driven sample = 4 + 6



PREPARED BY (Please print): D.E. SKOGLIE
 TITLE: FTL DATE: 08 22 02
 SIGNATURE: David E. Skoglie

REVIEWED BY (Please print): MG GARDNER
 TITLE: MGR DATE: 10-8-02
 SIGNATURE: MG Gardner

		Duratek Federal Services, Inc., Northwest Operations				
DRILLING AND SAMPLING (PERCUSSION) DAILY WORK RECORD						Page 1 of 2
WELL I.D.: C3830		WELL NUMBER: N/A		REPORT NUMBER: 76	DATE: August 23, 2002 Friday	
CONTRACT NUMBER: 8248-55		START CARD NO: S00631		RIG MODEL/NO: SIMCO 5000 (Rig 106)		
PURPOSE: Daily and weekly safety meeting. Drive casing depth is 56.99 ft bgs. Obtain samples S02083-09.				REFERENCE: DFSNW-DOW-006, Rev. 0		LOCATION: TX Tank Farm, 200 West
REFERENCE MEASURING POINT: Steel Plate plus 0.25 ft (ground level)				TOTAL SHIFT FOOTAGE: 1.33 ft.		
CONSTRUCTION DESCRIPTION: N/A				BORING DEPTH:		START TIME: 07:00 END TIME: 15:30 CONTRACTOR TIME: 0.5 TOTAL TIME: 8.5
CASING SIZE	SET-AT DEPTH	TYPE CASING	DRIVE POINT DIMENSION	START DEPTH	END DEPTH	
7.0" OD	NA	CS	Shoe, 7.5" OD	56.99 ft	56.99 ft	END: 59.7 ft
DOCUMENTED DOWNTIME			CASING SUMMARY			PERSONNEL: OPERATOR: K. Olson D Morris/D Curry WA LICENSE #: 1217 OTHER: D.E. Skoglie R. Sharp/ S. Snook (Opr) K. Johnson (PIC) K. Hartelius (HPT)
N/A			Bottom of 7" OD casing (start of shift) = 56.99 ft.			
WEATHER CONDITIONS (373-2716 or 373-2710)			Bottom of 7" OD casing (end of shift) = 56.99 ft.			
08:07: Temperature 66 F, Humidity 74%, Barometric pressure 29.33, Wind NW 3 mph			Casing (7 in OD) stick up (include bkpull) = 56.99 ft			
			Total casing = 60.45 ft.			
			SAMPLE SUMMARY			
			Sample: S02083-09 (#8) 58.29 – 59.7 (1.41 ft) 100%			
TIME		DESCRIPTION OF OPERATIONS/REMARKS				
FROM	TO					
07:00	08:49	Daily and weekly safety meeting conducted. Discussed anticipated activities. Complete equipment maintenance and inspection, no deficiencies noted. Also, inspect lower chain drive due to hearing the chain travel around the sprockets. A loose set screw was tightened. Alternate HPT arrives with instruments.				
08:49	09:25	Set-up the hammer. Drive sample S02083-09 (#8) 58.29 – 59.7 ft. (1.41 ft) 08:53. Blows 2/2/2 (07:44). Sleeve sample and place cap (1 O-ring and a swipe of Well Guard lubricant). Sample in drum @ 09:25 hrs.				
09:25	10:22	Back-pull casing (4 and 2 ft sections from string). Run Dp to bottom of casing.				
10:22	11:45	Add casing 5.0 ft (total 60.45 ft.) and Dp (total 61.1 ft.). Casing will not push down with head (6 ft open hole). Lower hammer onto casing. The casing lowered ~ 1 ft. Dry fire the hammer. The casing went to bottom. A stop tab was knocked off the lower hammer with the rotary head frame.				
11:45		Two people stayed in the zone to repair the tab while the others ate lunch. Once lunch was over, the third BSE ate lunch while the other two conducted a rig inspection due to the tab being knocked off.				
		The hammer was lifted, however it would not lower into the secured position. A brace was used to lift the hammer from one side. The hammer was lowered. Further inspection revealed the hammer bracing in good shape. The square corner of the mast bracing was ground down to allow the hammer arms to slide past the end of the mast bracing.				
		The upper and lower mast components were inspected. Set screws in the upper sprocket were tightened.				
	15:30	Area secured. Documentation completed. Fuel obtained.				
REPORT BY: D.E. Skoglie				REVIEWED BY: MG Gardner		
TITLE: Field Team Lead				TITLE: Project Manager		
SIGNATURE: <i>David E. Skoglie</i>				DATE: 10-08-02		
				SIGNATURE: <i>MG Gardner</i>		



Duratek Federal Services, Inc., Northwest Operations

C3830

SAMPLE FORM

FAR No. 76

Page 2 of 2

Sample No. 502083-09 Sample Tracking No. 8

Target Depth 59 to 60

(1) 3.35 top of rig floor above ground

(2) 4.46 casing stickup above ground

Csg Total (3) 61.45 - Stickup (2) 4.46 = TD (4)

Does not include drive head 56.99

Backpull stickup (2+5) .25

Sample depth (4) 58.29 to (4+6) 59.7

Blow Count

1.41


	.5 ft	1 ft	1.5 ft
Start Time 0853	2	2	2
End Time 0853			

Estimated Recovery: 100%

Remarks:




- (1) sample in drum @ 0925 hrs.
 (2) DTB TAG 58.29 (BACK TO BACK sample)

- 1 = Top of rig floor above ground
 2 = Stickup of csg above ground 1 + measure from floor to top csg = SU
 3 = Total csg length
 4 = Depth of csg = Total Depth (TD)
 Total csg - SU⁽²⁾ = TD
 5 = Casing back pull
 6 = Sampler drive distance
 7 = Total depth of driven sample = 4 + 6



PREPARED BY (Please print): D.E. SKOGLIE
 TITLE: FTL DATE: 08-23-02
 SIGNATURE: David E. Skoglie

REVIEWED BY (Please print): M.G. GARDNER
 TITLE: MGR DATE: 10-08-02
 SIGNATURE: M.G. Gardner

		Duratek Federal Services, Inc., Northwest Operations					
DRILLING AND SAMPLING (PERCUSSION) DAILY WORK RECORD							Page 1 of 2
WELL I.D.: C3830		WELL NUMBER: N/A		REPORT NUMBER: 77		DATE: August 26, 2002 Monday	
CONTRACT NUMBER: 8248-55			START CARD NO: S00631		RIG MODEL/NO: SIMCO 5000 (Rig 106)		
PURPOSE: Daily safety meeting. Casing is drove to a depth of 71.95 ft bgs. Obtain sample S02083-10.				REFERENCE: DFSNW-DOW-006, Rev. 0		LOCATION: TX Tank Farm, 200 West	
REFERENCE MEASURING POINT: Steel Plate plus 0.25 ft (ground level)				TOTAL SHIFT FOOTAGE: 12.25 ft.			
CONSTRUCTION DESCRIPTION: N/A				BORING DEPTH:		START TIME: 07:00	
CASING SIZE		SET-AT DEPTH	TYPE CASING	DRIVE POINT DIMENSION	START DEPTH	END DEPTH	END TIME: 16:30
7.0 " OD		NA	CS	Shoe, 7.5 " OD	56.99 ft	71.95ft	CONTRACTOR TIME: 0.5
				END: 71.95 ft		TOTAL TIME: 9.5	
DOCUMENTED DOWNTIME				CASING SUMMARY		PERSONNEL:	
N/A				Bottom of 7 " OD casing (start of shift) = 56.99 ft.		OPERATOR: K. Olson	
WEATHER CONDITIONS (373-2716 or 373-2710)				Bottom of 7 " OD casing (end of shift) = 71.95 ft		D Morris/D Curry	
08:46: Temperature 74F, Humidity 48%, Barometric pressure 29.41, Wind NW 9 with gusts to 16 mph				Casing (7 in OD) stick up (include bkpull) = 1.14 ft		WA LICENSE #: 1217	
				Total casing = 76.45 ft		OTHER: D.E. Skoglie/K. Flower	
				SAMPLE SUMMARY		S. Snook (Opr)	
				Sample: S02083-10 (#9) 66.06 – 67.46 (1.4 ft) 100%		K. Johnson (PIC)	
						K. Harteilius (HPT)	
TIME		DESCRIPTION OF OPERATIONS/REMARKS					
FROM	TO						
07:00	10:00	Daily safety meeting conducted (07:17). Discussed anticipated activities. Complete equipment maintenance and inspection, no deficiencies noted. Cut out the center of the lower stop (installed last Friday) with the port-a-band. Welding/cutting permit in place. Weld hammer stop arm (upper mast), spacer on rotary head (alignment) and lower mast chain guard.					
10:00	10:28	Add 2 ft casing and back-pull casing to place casing joint in the wrenches. Add casing 5.0 ft (65.45) and Dp 5.01 (66.11). Set-up hammer.					
10:28	10:34	Drive casing to 61.08 ft bgs. 65.45 – (3.35 + 1.02). Blows 13/15/12/19. Secure hammer and disassemble drive head assembly.					
10:34	10:48	Add casing 5.0 ft (70.45) and Dp 5.0 (71.11). Set-up hammer.					
10:48	11:04	Drive casing to 66.06 ft bgs. 70.45 – (3.35 + 1.04) 10:52. Blows 21/30/39/38/38. Secure hammer and disassemble drive head assembly.					
11:04	11:40	Back-pull casing .25 ft (11:10). Trip Dp out of boring 11:40hrs.					
11:40	12:16	Lunch					
12:16	13:18	Trip sampler in boring. Set-up drive head and hammer. Drive sample (66.06 – 67.46) @ 12:50 – 12:51. Blows 2/2/2. The sampler was pulled from the boring and landed on the deck @ 13:12. The sample was placed in the drum @ 13:18.					
13:18	13:42	The Dp was tripped into the boring.					
13:42	13:56	Add casing 6.0 ft (76.45) and Dp 6.0 (77.11). A 4 ft and 2 ft casing were added together. Set-up hammer.					
13:56	13:59	Drive casing to 71.95 ft bgs. 76.45 – (3.35 + 1.15). Blows 8/27/22/23/25/43. Casing driving was stopped after 2 ft to tighten a casing section (due to adding two sections).					
13:59	14:14	Back-pull casing .25 ft. Secure hammer and disassemble drive head.					
14:14	14:29	Break					
14:29	15:38	Trip Dp out of boring. Pick-up a sampler and run to bottom of the boring.					
15:38	16:30	Fuel equipment. Secure site. Complete documentation.					
REPORT BY: D.E. Skoglie				REVIEWED BY: MG Gardner			
TITLE: Field Team Lead				TITLE: Project Manager			
SIGNATURE: 				DATE: 10-08-02			
				SIGNATURE: 			



Duratek Federal Services, Inc., Northwest Operations

C3830 SAMPLE FORM

FAR No. 77

Page 2 of 2

Sample No. 502083-10 Sample Tracking No. 9

Target Depth 66 to 67

(1) 3.35 top of rig floor above ground

(2) 4.39 casing stickup above ground

Csg Total (3) 70.45 - Stickup (2) 4.39 = TD (4) 66.06
Does not include drive head

Backpull stickup (2+5) .25

Sample depth (4) 66.06 to (4+6) 67.46


	Blow Count		
	.5 ft	1 ft	1.5 ft
Start Time 12 50	2	2	2
End Time 12 51			

Estimated Recovery: 100%

Remarks:




(1) Sample in drum @ 13 18 hrs.


- 1 = Top of rig floor above ground
 2 = Stickup of csg above ground 1 + measure from floor to top csg = SU
 3 = Total csg length
 4 = Depth of csg = Total Depth (TD)
 Total csg - SU⁽²⁾ = TD
 5 = Casing back pull
 6 = Sampler drive distance
 7 = Total depth of driven sample = 4 + 6




PREPARED BY (Please print): D.E. SKOGLIE
 TITLE: FTL DATE: 082602
 SIGNATURE: David Skoglie

REVIEWED BY (Please print): MG GARDNER
 TITLE: MGR DATE:
 SIGNATURE: M. Gardner 10-08-02

		Duratek Federal Services, Inc., Northwest Operations						
DRILLING AND SAMPLING (PERCUSSION) DAILY WORK RECORD								Page 1 of 3
WELL I.D.: C3830		WELL NUMBER: N/A		REPORT NUMBER: 78		DATE: August 27, 2002 Tuesday		
CONTRACT NUMBER: 8248-55		START CARD NO: S00631		RIG MODEL/NO: SIMCO 5000 (Rig 106)				
PURPOSE: Daily safety meeting. Casing is drove to a depth of 80.91 ft bgs. Obtain sample S02083-11 and S02083-12.				REFERENCE: DFSNW-DOW-006, Rev. 0		LOCATION: TX Tank Farm, 200 West		
REFERENCE MEASURING POINT: Steel Plate plus 0.25 ft (ground level)				TOTAL SHIFT FOOTAGE: 8.96 ft.				
CONSTRUCTION DESCRIPTION: N/A				BORING DEPTH:		START TIME: 07:00		
CASING SIZE		SET-AT DEPTH	TYPE CASING	DRIVE POINT DIMENSION	START DEPTH	END DEPTH	END TIME: 16:30	
7.0" OD	NA	CS	Shoe, 7.5" OD	71.95 ft	80.91 ft		CONTRACTOR TIME: 0.5	
				END: 80.91 ft		TOTAL TIME: 9.5		
DOCUMENTED DOWNTIME				CASING SUMMARY		PERSONNEL:		
N/A				Bottom of 7" OD casing (start of shift) = 71.95 ft.		OPERATOR: K. Olson		
WEATHER CONDITIONS (373-2716 or 373-2710)				Bottom of 7" OD casing (end of shift) = 80.91 ft		D Morris/D Curry		
10:00: Temperature 77F, Humidity 47%, Barometric pressure 29.39, Wind N5 with gusts to 11				Casing (7 in OD) stick up (include bkpull) = 1.45 ft		WA LICENSE #: 1217		
				Total casing = 85.46 ft.		OTHER: D.E. Skoglie/K. Flower		
				SAMPLE SUMMARY		S. Snook/R. Sharp (Opr)		
				Sample: S02083-11 (#10) 71.95 – 73.3 (1.35 ft) 100%		K. Johnson (PIC)		
				Sample: S02083-12 (#11) 76.98 – 78.35 (1.37 ft) 100%		K. Hartelius (HPT)		
TIME		DESCRIPTION OF OPERATIONS/REMARKS						
FROM	TO							
07:00	07:37	Daily safety meeting conducted (07:17). Discussed anticipated activities. Complete equipment maintenance and inspection, no deficiencies noted.						
07:37	08:35	Sampler sitting on bottom. Set-up drive head and hammer. Drive sample S02083-11 (71.95 – 73.3) @ 07:37 – 07:38. Blows 3/3/2. The sampler was pulled from the boring and landed on the deck @ 08:08. The sample was placed in the drum @ 08:10 hrs. Trip Dp/tip into casing.						
08:35	08:46	Add casing 5.01 (total 81.46 ft) and Dp 5.01 (total 82.12 ft). Set-up hammer.						
08:46	09:00	Drive casing to 76.98 ft bgs. 81.46 – (3.35 + 1.13). Blows 8/31/35/36/38. Secure hammer and disassemble drive head assembly.						
09:00	10:18	Back-pull casing .25 ft (09:07). Tip is stuck, release by jacking out (09:25). Trip Dp out of boring. The fuel line to hammer is leaking (hammer tank is full). Shut down supply pump. No fuel to ground, absorbed with pads (on the drill deck) 10:02 hrs. Break (10:02 – 10:18).						
10:18	11:45	Trip sampler in boring. Set-up drive head and hammer. Drive sample S02083-12 (76.98 – 78.35) @ 11:00 – 11:01. Blows 3/4/3. The sampler was pulled from the boring and landed on the deck @ 11:30. The sample was placed in the drum @ 11:35.						
11:45	12:20	Lunch						
12:20	12:54	The Dp/tip was tripped into the boring.						
12:54	13:14	Add casing 4.0 ft (total 85.46) and Dp 4.0 (86.12). Set-up the hammer.						
13:14	14:15	Drive casing to 80.91 ft bgs. 85.46 – (3.35 + 1.2). Blows 12/22/36/38. Back-pull casing .25 ft. Trip out inner string.						
14:15	14:45	Break (14:45). Run sampler in boring. Crew exits TX Tank Farm (15:48).						
15:48	16:30	Secure site and complete documentation.						
REPORT BY: DE Skoglie				REVIEWED BY: MG Gardner				
TITLE: Field Team Lead				TITLE: Project Manager				
SIGNATURE: 				DATE: 10-08-02				
				SIGNATURE: 				

	Duratek Federal Services, Inc., Northwest Operations		
C3830 SAMPLE FORM	FAR No. <u>78</u>	Page <u>2</u> of <u>3</u>	
Sample No. <u>502083-11</u> Sample Tracking No. <u>10</u>			
Target Depth <u>72</u> to <u>73</u>			
(1) <u>3.35</u> top of rig floor above ground			
(2) <u>4.5</u> casing stickup above ground			
Csg Total (3) <u>76.45</u> - Stickup (2) <u>4.5</u> = TD (4) <u>71.95</u>			
Does not include drive head			
Backpull stickup (2+5) <u>.25</u>			
Sample depth (4) <u>71.95</u> to (4+6) <u>73.3</u>			
Blow Count <u>1.35</u>			
	.5 ft	1 ft	<u>1.5</u> ft
Start Time	<u>3</u>	<u>3</u>	<u>2</u>
End Time			
<u>0737</u>			
<u>0738</u>			
Estimated Recovery: <u>100%</u>			
Remarks:			
<u>(1) Sample in drum @ 0810 hrs.</u>			
1 = Top of rig floor above ground 2 = Stickup of csg above ground 1 + measure from floor to top csg = SU 3 = Total csg length 4 = Depth of csg = Total Depth (TD) Total csg - SU ⁽²⁾ = TD 5 = Casing back pull 6 = Sampler drive distance 7 = Total depth of driven sample = 4 + 6			
PREPARED BY (Please print): <u>D.E. SKOGLIE</u> TITLE: <u>FTL</u> DATE: <u>08/27/02</u> SIGNATURE: <u>David E. Skogle</u>		REVIEWED BY (Please print): <u>MG GARDNER</u> TITLE: <u>MR</u> DATE: <u>10-08-02</u> SIGNATURE: <u>MG Gardner</u>	



The diagram illustrates the wellbore structure and measurements. Key features include:

- Rig Floor** at the top.
- Ground Level** indicated by a horizontal line.
- Measurements (in feet):**
 - (1) 3.35: From Rig Floor to top of casing.
 - (2) 4.5: Casing stickup above ground.
 - (3) 76.45: Total casing length.
 - (4) 71.95: Depth of casing (Total Depth).
 - (5) .25: Backpull stickup.
 - (6) 1.35: Sampler drive distance.
 - (7) 73.3: Total depth of driven sample (4 + 6).
 - (8) 1.35: Distance from ground level to the bottom of the casing.



Duratek Federal Services, Inc., Northwest Operations

C3830

SAMPLE FORM

FAR No. 78

Page 3 of 3

Sample No. 5020 83-12 Sample Tracking No. 11

Target Depth 77 to 78

(1) 3.35 top of rig floor above ground

(2) 4.48 casing stickup above ground

Csg Total (3) 81.46 - Stickup (2) 4.48 = TD (4)

Does not include drive head 76.98

Backpull stickup (2+5) .25

Sample depth (4) 76.98 to (4+6) 78.35

Blow Count 1.37

	.5 ft	1 ft	1.5 ft
Start Time	3	4	3
End Time			
1100			
1101			

Estimated Recovery: 100%

Remarks:

(1) Sample in drum @ 11:35 hrs.

- 1 = Top of rig floor above ground
 2 = Stickup of csg above ground 1 + measure from floor to top csg = SU
 3 = Total csg length
 4 = Depth of csg = Total Depth (TD)
 Total csg - SU⁽²⁾ = TD
 5 = Casing back pull
 6 = Sampler drive distance
 7 = Total depth of driven sample = 4 + 6


PREPARED BY (Please print): D.E. SKOGLIE


TITLE: FTL DATE: 08 27 02



SIGNATURE: *David E. Skoglie*

REVIEWED BY (Please print): MG GARDNER

TITLE: MGR DATE:

SIGNATURE: *MG Gardner* 10-08-02

		Duratek Federal Services, Inc., Northwest Operations						
DRILLING AND SAMPLING (PERCUSSION) DAILY WORK RECORD								Page 1 of 3
WELL I.D.: C3830		WELL NUMBER: N/A		REPORT NUMBER: 79		DATE: August 28, 2002 Wednesday		
CONTRACT NUMBER: 8248-55			START CARD NO: S00631			RIG MODEL/NO: SIMCO 5000 (Rig 106)		
PURPOSE: Daily safety meeting. Casing is drove to a depth of 86.11 ft bgs. Obtain sample S02083-13 and S02083-14.				REFERENCE: DFSNW-DOW-006, Rev. 0		LOCATION: TX Tank Farm, 200 West		
REFERENCE MEASURING POINT: Steel Plate plus 0.25 ft (ground surface)				TOTAL SHIFT FOOTAGE: 6.5 ft.				
CONSTRUCTION DESCRIPTION: N/A				BORING DEPTH:		START TIME: 07:00		
CASING SIZE	SET-AT DEPTH	TYPE CASING	DRIVE POINT DIMENSION	START DEPTH	END DEPTH	START: 80.91 ft	END TIME: 16:30	
7.0 " OD	NA	CS	Shoe, 7.5 " OD	80.91 ft	86.11 ft	END: 87.41 ft	CONTRACTOR TIME: 0.5	
DOCUMENTED DOWNTIME HPT – 1.25 hrs.				CASING SUMMARY		PERSONNEL:		
WEATHER CONDITIONS (373-2716 or 373-2710) 10:00: Temperature 74F, Humidity 51%, Barometric pressure 29.25, Wind N @ 6 mph				Bottom of 7 " OD casing (start of shift) = 71.95 ft.		OPERATOR: K. Olson		
				Bottom of 7 " OD casing (end of shift) = 80.91 ft		D Morris/D Curry		
				Casing (7 in OD) stick up (include bkpull) = 1.25 ft		WA LICENSE #: 1217		
				Total casing = 86.11 ft		OTHER: DE Gostovich		
				SAMPLE SUMMARY		S. Snook/R. Sharp (Opr)		
				Sample: S02083-13 (#12) 80.91 – 82.21(1.3 ft) 90%		K. Johnson (PIC)		
				Sample: S02083-14 (#13) 86.11 – 87.41(1.3 ft) 100%		?? (HPT)		
						K. Flower		
TIME		DESCRIPTION OF OPERATIONS/REMARKS						
FROM	TO							
07:00	08:15	Daily safety meeting conducted (07:17). Discussed anticipated activities. Complete equipment maintenance and inspection, no deficiencies noted. HPT (alternate) arrives 08:15.						
08:15	09:00	Sampler sitting on bottom. Set-up drive head and hammer. Drive sample S02083-13 (80.91 – 82.21) @ 08:20 – 08:21. Blows 4/4/3. The sampler was pulled from the boring and landed on the deck @ 08:46. The sample was placed in the drum @ 08:55 hrs.						
09:00		Remove 4 ft section of casing. Trip Dp/tip into boring (11:15).						
		Add casing 5.0 (total 86.46 ft) and Dp 5.0 (total 87.12 ft). Set-up hammer.						
08:46		Drive casing to 81.91 ft bgs. 86.46 – (3.35 + 1.2). Blows (not recorded). Secure hammer and disassemble drive head assembly.						
		Add casing 4.0 (total 90.46 ft) and Dp 4.0 (total 91.12 ft). Set-up hammer.						
	10:30	Drive casing to 86.11 ft bgs. 90.46 – (3.35 + 1.0). Blows (not recorded). Secure hammer and disassemble drive head assembly (10:30 hrs.). Back-pull casing .25 ft.						
11:15	11:45	Lunch						
11:45	13:30	HPT arrives @ 12:45. Remove Dp from boring.						
13:30	14:40	Trip sampler in boring. Set-up drive head and hammer. Drive sample S02083-14 (86.11 – 87.41). Blows 4/3/3. The sampler was pulled from the boring and landed on the deck @ 14:28. The sample was placed in the drum @ 14:40.						
14:40	16:30	Secure site. Complete documentation.						
REPORT BY: DE Gostovich				REVIEWED BY: MG Gardner				
TITLE: Field Team Lead				TITLE: Project Manager				
SIGNATURE: <i>DE. Skoglie for</i>				DATE: 11-27-02				
				SIGNATURE: <i>MG Gardner</i>				

	Duratek Federal Services, Inc., Northwest Operations		
C3830 SAMPLE FORM		FAR No. <u>79</u>	Page <u>2</u> of <u>3</u>
Sample No. <u>502083-13</u> Sample Tracking No. <u>12</u>			
Target Depth <u>81</u> to <u>82</u>			
(1) <u>3.35</u> top of rig floor above ground			
(2) <u>4.55</u> casing stickup above ground			
Csg Total (3) <u>85.46</u> - Stickup (2) <u>4.55</u> = TD (4)			
Does not include drive head <u>80.91</u>			
Backpull stickup (2+5) <u>.25</u>			
Sample depth (4) <u>80.91</u> to (4+6) <u>82.21</u>			
Blow Count <u>1.3</u>			
	.5 ft	1 ft	<u>1.3</u> ft
Start Time <u>0820</u>	<u>4</u>	<u>4</u>	<u>3</u>
End Time <u>0822</u>			
Estimated Recovery: <u>90%</u>			
Remarks: <u>(1) sample in down @ 0855 hrs.</u>			
<div style="display: flex; justify-content: space-between;"> <div style="width: 45%;"> <p>1 = Top of rig floor above ground</p> <p>2 = Stickup of csg above ground 1 + measure from floor to top csg = SU</p> <p>3 = Total csg length</p> <p>4 = Depth of csg = Total Depth (TD) Total csg - SU⁽²⁾ = TD</p> <p>5 = Casing back pull</p> <p>6 = Sampler drive distance</p> <p>7 = Total depth of driven sample = 4 + 6</p> </div> <div style="width: 50%;">  </div> </div>			
PREPARED BY (Please print): <u>D.E. SKOGLIE</u>		REVIEWED BY (Please print): <u>MG GARDNER</u>	
TITLE: <u>FTL</u> DATE: <u>08 28 02</u>		TITLE: <u>MR</u> DATE:	
SIGNATURE: <u>David E Skogle</u>		SIGNATURE: <u>MG Gardner</u> <u>11-27-02</u>	

DFSNN-WS-00



Duratek Federal Services, Inc., Northwest Operations

C3830

SAMPLE FORM

FAR No. 79

Page 3 of 3

Sample No. 502083-14 Sample Tracking No. 13

Target Depth 86 to 87

(1) 3.35 top of rig floor above ground

(2) 4.35 casing stickup above ground

Csg Total (3) 90.46 - Stickup (2) 4.35 = TD (4) 86.11

Does not include drive head

Backpull stickup (2+5) .25

Sample depth (4) 86.11 to (4+6) 87.41

Blow Count

1.3

	.5 ft	1 ft	1.5 ft
Start Time	4	3	3
End Time			

Estimated Recovery: 100%

Remarks:

(1) Sample in drum @ 14:40 hrs.

1 = Top of rig floor above ground

2 = Stickup of csg above ground 1 + measure from floor to top csg = SU

3 = Total csg length


4 = Depth of csg = Total Depth (TD)

Total csg - SU⁽²⁾ = TD

5 = Casing back pull


6 = Sampler drive distance




7 = Total depth of driven sample = 4 + 6



PREPARED BY (Please print): D.E. Shoglie
 TITLE: FTL DATE: 08/28/02
 SIGNATURE: David E. Shoglie

REVIEWED BY (Please print): M.G. GARNER
 TITLE: MGR DATE:
 SIGNATURE: M.G. Garner 11-27-02

		Duratek Federal Services, Inc., Northwest Operations						
DRILLING AND SAMPLING (PERCUSSION) DAILY WORK RECORD								Page 1 of 1
WELL I.D.: C3830		WELL NUMBER: N/A		REPORT NUMBER: 80		DATE: August 29, 2002 Thursday		
CONTRACT NUMBER: 8248-55			START CARD NO: S00631			RIG MODEL/NO: SIMCO 5000 (Rig 106)		
PURPOSE: Daily and weekly safety meeting. Casing is drove to a depth of 98.97 ft bgs.				REFERENCE: DFSNW-DOW-006, Rev. 0		LOCATION: TX Tank Farm, 200 West		
REFERENCE MEASURING POINT: Steel Plate				TOTAL SHIFT FOOTAGE: 11.56 ft.				
CONSTRUCTION DESCRIPTION: N/A				BORING DEPTH: START: 87.41 ft END: 98.97 ft		START TIME: 07:00 END TIME: 16:30 CONTRACTOR TIME: 0.5 TOTAL TIME: 9.5		
CASING SIZE 7.0 " OD	SET-AT DEPTH NA	TYPE CASING CS	DRIVE POINT DIMENSION Shoe, 7.5 " OD	START DEPTH 86.11 ft	END DEPTH 98.97 ft			
DOCUMENTED DOWNTIME HPT – 4.5 hrs.			CASING SUMMARY Bottom of 7 " OD casing (start of shift) = 86.11 ft. Bottom of 7 " OD casing (end of shift) = 98.97 ft Casing (7 in OD) stick up (end of shift) = 1.14 ft			PERSONNEL: OPERATOR: K. Olson D Morris/D Curry WA LICENSE #: 1217 OTHER: DE Skoglie S. Snook/R. Sharp (Opr) K. Johnson (PIC) K. Hartelius (HPT) K. Flower		
WEATHER CONDITIONS (373-2716 or 373-2710) 10:00: Temperature 74F, Humidity 51%, Barometric pressure 29.25, Wind N @ 6 mph			SAMPLE SUMMARY N/A					
TIME FROM TO		DESCRIPTION OF OPERATIONS/REMARKS						
07:00	07:45	Daily and weekly safety meeting conducted. Discussed anticipated activities. Complete equipment maintenance and inspection, no deficiencies noted.						
07:45	08:50	Remove 4 ft section of casing. Trip Dp/tip into boring.						
08:50	08:58	Add casing 5.0 (total 91.46 ft) and Dp 5.01 (total 96.13 ft). Set-up hammer.						
08:58	08:59	Drive casing to 87.06 ft bgs. 91.46 – (3.35 + 1.05). Blows 26. Secure hammer and disassemble drive head assembly.						
08:59	09:22	Add casing 5.0 (total 96.46 ft) and Dp 5.0 (total 97.13 ft). Set-up hammer.						
09:22	09:30	Drive casing to 92.04 ft bgs. 96.46 – (3.35 + 1.07). Blows 22/21/20/19/20. Secure hammer and disassemble drive head assembly.						
09:30	09:45	Add casing 5.0 (total 101.46 ft) and Dp 5.01 (total 102.14 ft). Set-up hammer.						
09:45	09:47	Drive casing to 97.07 ft bgs. 101.46 – (3.35 + 1.04). Blows 24/23/25/26/21. Secure hammer and disassemble drive head assembly.						
09:47	10:03	Add casing 2.0 (total 103.46 ft) and Dp 2.0 (total 104.14 ft). Set-up hammer.						
10:03	10:30	Drive casing to 98.97 ft bgs. 103.46 – (3.35 + 1.14). Blows 24/5. Secure hammer and disassemble drive head assembly (10:15 hrs). Break 10:15 – 10:30.						
10:30	11:20	Trip Dp out of bore-hole (11:20). Disassemble sample shoe/liner assembly.						
11:20	11:35	Secure site. Complete documentation.						
11:35	12:05	Lunch						
12:05	16:30	No alternate HPT this pm. Conduct discussion regarding completion. Complete documentation.						
REPORT BY: DE Skoglie TITLE: Field Team Lead SIGNATURE: <u>D.E. Skoglie</u>				REVIEWED BY: MG Gardner TITLE: Project Manager DATE: 10-08-02 SIGNATURE: <u>MG Gardner</u>				

		Duratek Federal Services, Inc., Northwest Operations						
DRILLING AND SAMPLING (PERCUSSION) DAILY WORK RECORD								Page 1 of 3
WELL I.D.: C3830		WELL NUMBER: N/A		REPORT NUMBER: 81		DATE: September 03, 2002 Tuesday		
CONTRACT NUMBER: 8248-55			START CARD NO: S00631			RIG MODEL/NO: SIMCO 5000 (Rig 106)		
PURPOSE: Daily safety meeting. Casing is drove to a depth of 102.99 ft bgs. Obtain samples S02083-15 and S02083-16.				REFERENCE: DFSNW-DOW-006, Rev. 0		LOCATION: TX Tank Farm, 200 West		
REFERENCE MEASURING POINT: Steel Plate plus 0.25 ft (ground level)				TOTAL SHIFT FOOTAGE: 4.02 ft.				
CONSTRUCTION DESCRIPTION: N/A				BORING DEPTH:		START TIME: 07:00		
CASING SIZE		SET-AT DEPTH	TYPE CASING	DRIVE POINT DIMENSION	START DEPTH	END DEPTH	END TIME: 16:30	
7.0 " OD		NA	CS	Shoe, 7.5 " OD	98.97 ft	102.99 ft	CONTRACTOR TIME: 0.5	
						TOTAL TIME: 9.5		
DOCUMENTED DOWNTIME Wind 2 hrs.				CASING SUMMARY		PERSONNEL:		
WEATHER CONDITIONS (373-2716 or 373-2710) 07:04: Temperature 62F, Humidity 47%, Barometric pressure 29.063, Wind NW @ 11 mph, gusts to 20				Bottom of 7 " OD casing (start of shift) = 98.97 ft.		OPERATOR: K. Olson		
				Bottom of 7 " OD casing (end of shift) = 102.99 ft		D Morris/D Curry		
				Casing (7 in OD) stick up (end of shift) = 1.37 ft		WA LICENSE #: 1217		
				Total casing = 107.46 ft		OTHER: DE Skoglie		
				SAMPLE SUMMARY		S. Snook (Opr)		
				Sample: S02083-15 (98.97 – 100.36) 1.39 ft. 100%		R. Sharp (PIC)		
				Sample: S02083-16 (100.32 – 101.72) 1.4 ft. 100%		K. Hartelius (HPT)		
TIME		DESCRIPTION OF OPERATIONS/REMARKS						
FROM	TO							
07:00	07:45	Daily and weekly safety meeting conducted. Discussed anticipated activities. Complete equipment maintenance and inspection, no deficiencies noted.						
07:45	08:44	Tag bottom @ 98.97 ft bgs. Trip Dp/sampler into bore-hole.						
08:44	09:25	Drive sample S02083- 15 (#14) (98.97 - 100.36) 08:44 – 08:45. Blows 3/3/2. Sample on deck @ 09:18 and in drum @ 09:25.						
09:25	09:30	Tag bottom @ 100.32 ft bgs.						
09:30	11:30	Shut down due to wind (18 mph with gusts to 26).						
11:00	11:30	Lunch						
11:30	12:13	Trip in with sampler.						
12:13	13:15	Drive sample S02083- 16 (#15) (100.32 - 101.72). Blows 2/2/1. Sample on deck @ 12:52 and in drum @ 13:00 hrs.						
13:15	14:02	Trip in Dp.						
14:02	14:07	Add casing 4.0 (total 107.46 ft) and Dp 4.0 (total 108.14 ft). Set-up hammer.						
14:07	14:10	Drive casing to 102.99 ft bgs. 107.46 – (3.35 + 1.12). Blows 9/18/17/20. Secure hammer and disassemble drive head assembly. Backpull casing 0.25 ft.						
14:10		Trip Dp out of boring.						
	15:30	Run a sampler into boring (land on bottom).						
15:30	16:30	Secure site complete documentation.						
REPORT BY: DE Skoglie		REVIEWED BY: MG Gardner						
TITLE: Field Team Lead		TITLE: Project Manager						
SIGNATURE: 		DATE: 10-08-02						
		SIGNATURE: 						



Duratek Federal Services, Inc., Northwest Operations

C3830 SAMPLE FORM

FAR No. 81

Page 2 of 3

Sample No. 502083-15 Sample Tracking No. 14

Target Depth 99 to 100

(1) 3.35 top of rig floor above ground

(2) 4.49 casing stickup above ground

Csg Total (3) 103.46 - Stickup (2) 4.49 = TD (4) 98.97

Does not include drive head

Backpull stickup (2+5) .25

Sample depth (4) 98.97 to (4+6) 100.36

Blow Count 1.39

	.5 ft	1 ft	1.5 ft
Start Time	3	3	2
End Time			

Estimated Recovery: 100%

Remarks:

① Sample in drum @ 09:25 hrs.

1 = Top of rig floor above ground

2 = Stickup of csg above ground 1 + measure from floor to top csg = SU

3 = Total csg length


4 = Depth of csg = Total Depth (TD)

Total csg - SU⁽²⁾ = TD

5 = Casing back pull

6 = Sampler drive distance

7 = Total depth of driven sample = 4 + 6



PREPARED BY (Please print): D.E. SKOGLIE
 TITLE: FTL DATE: 09 03 02
 SIGNATURE: *D.E. Skoglie*

REVIEWED BY (Please print): MG GARDNER
 TITLE: MGR DATE: 10-8-02
 SIGNATURE: *MG Gardner*

DFS NW-WS-00



Duratek Federal Services, Inc., Northwest Operations

C3830 SAMPLE FORM

FAR No. 81

Page 3 of 3

Sample No. 5020 83-116 Sample Tracking No. 15

Target Depth 100 to 101

(1) 3.35 top of rig floor above ground

(2) 4.49 casing stickup above ground

Csg Total (3) 103.46 - Stickup (2) 4.49 = TD (4)

Does not include drive head 100.32

Backpull stickup (2+5) 25

Sample depth (4) 100.32 to (4+6) 101.72

Blow Count 1.3

	.5 ft	1 ft	1.5 ft
Start Time 1213	2	2	1
End Time 1214			

Estimated Recovery: 100%

Remarks:

(1) Sample in drum @ 1300 hrs.

(2) DTB YAG 100.32 FT BGS.

1 = Top of rig floor above ground

2 = Stickup of csg above ground 1 + measure from floor to top csg = SU

3 = Total csg length


4 = Depth of csg = Total Depth (TD)

Total csg - SU⁽²⁾ = TD

5 = Casing back pull

6 = Sampler drive distance

7 = Total depth of driven sample = 4 + 6



PREPARED BY (Please print): D.E. SKOGLIE

TITLE: FTL DATE: 09 03 02


SIGNATURE: David E. Skoglie

REVIEWED BY (Please print): MG GARNER

TITLE: MGR DATE: 10-08-02

SIGNATURE: MG Garner

DFSNW-WS-00

		Duratek Federal Services, Inc., Northwest Operations				
DRILLING AND SAMPLING (PERCUSSION) DAILY WORK RECORD						Page 1 of 3
WELL I.D.: C3830		WELL NUMBER: N/A		REPORT NUMBER: 82		DATE: September 04, 2002 Wednesday
CONTRACT NUMBER: 8248-55			START CARD NO: S00631		RIG MODEL/NO: SIMCO 5000 (Rig 106)	
PURPOSE: Daily safety meeting. Casing is drove to a depth 113.6 ft bgs. Obtain samples S02083-17 and S02083-18 .				REFERENCE: DFSNW-DOW-006, Rev. 0		LOCATION: TX Tank Farm, 200 West
REFERENCE MEASURING POINT: Steel Plate				TOTAL SHIFT FOOTAGE: 10.6 ft.		
CONSTRUCTION DESCRIPTION: N/A						BORING DEPTH: START: 102.99 ft END: 113.6 ft
CASING SIZE 7.0 " OD	SET-AT DEPTH NA	TYPE CASING CS	DRIVE POINT DIMENSION Shoe, 7.5 " OD	START DEPTH 102.99 ft	END DEPTH 113.6 ft	
DOCUMENTED DOWNTIME N/A			CASING SUMMARY Bottom of 7 " OD casing (start of shift) = 102.99 ft. Bottom of 7" OD casing (end of shift) = 113.6 ft Casing (7 in OD) stick up (end of shift) = 4.5 ft Total casing = 121.45 ft			PERSONNEL: OPERATOR: K. Olson D Morris/D Curry WA LICENSE #: 1217 OTHER: DE Skoglie S. Snook (Opr) R. Sharp (PIC) K. Hartelius (HPT)
WEATHER CONDITIONS (373-2716 or 373-2710) 07:28: Temperature 46F, Humidity 55%, Barometric pressure 29.21, Wind @ 2 mph			SAMPLE SUMMARY Sample: S02083-17 (102.99 – 104.44) Rec ukn Sample: S02083-18 () 100%			
TIME FROM TO		DESCRIPTION OF OPERATIONS/REMARKS				
07:00	07:55	Daily and weekly safety meeting conducted. Discussed anticipated activities. Complete equipment maintenance and inspection, no deficiencies noted.				
07:58	08:40	Drive sample S02083- 17 (#16) 102.99 – 104.44 (1.45 ft) 07:58 – 07:59. Blows 2/3/2. Sample on deck @ 08:30 and in drum @ 08:40.				
08:40	09:33	Trip Dp into boring. Add casing 5.0 (total 112.46 ft) and Dp 5.0 (total 113.14 ft). Set-up hammer.				
09:33	09:45	Drive casing to 107.89 ft bgs. 112.46 – (3.35 + 1.22). Blows 7/15/17/20/22. Secure hammer and disassemble drive head assembly.				
09:45	10:15	Back-pull casing .25 ft. Break (10:06 – 10:15)				
10:15	11:30	Trip Dp/tip from boring (10:55 hrs). Run sampler to bottom of boring.				
11:30	12:00	Lunch				
12:00	14:19	Drive sample S02083- 18 (#17) 107.89 – 109.19 (1.3 ft) 12:28 – 12:29. Blows 2/2/2. Secure hammer and disassemble drive head. Sample on deck @ 13:00 and in drum @ 13:11 hrs. Trip Dp/tip into boring.				
14:19	14:42	Add casing 4.99 (total 117.45 ft) and Dp 5.01 (total 118.15 ft). Set-up hammer.				
14:42	14:45	Drive casing to 113.0 ft bgs. 117.45 – (3.35 + 1.1). Blows 12/30/34/24/25. Secure hammer and disassemble drive head assembly. Blow counts dropped.				
14:19	14:42	Add casing 4.0 (total 121.45 ft) and Dp 4.0 (total 122.15 ft). Set-up hammer.				
14:42	14:45	Drive casing to 113.6 ft bgs. 121.45 – (3.35 + 4.5). Blows 36. Secure hammer and disassemble drive head assembly. Blow counts have came up significantly. A sample will be taken at this depth.				
14:45	15:40	Secure hammer and disassemble drive head. Initiate Dp trip out.				
15:40	16:30	Secure site.				
REPORT BY: DE Skoglie TITLE: Field Team Lead SIGNATURE: <i>D.E. Skoglie</i>			REVIEWED BY: MG Gardner TITLE: Project Manager SIGNATURE: <i>MG Gardner</i>			DATE: 10-9-02



Duratek Federal Services, Inc., Northwest Operations

C3830 SAMPLE FORM

FAR No. 82

Page 2 of 3

Sample No. 502083-17 Sample Tracking No. 16

Target Depth 103 to 104

(1) 3.35 top of rig floor above ground

(2) 4.47 casing stickup above ground

Csg Total (3) 107.46 - Stickup (2) 4.47 = TD (4)

Does not include drive head 102.99

Backpull stickup (2+5) .25

Sample depth (4) 102.99 to (4+6) 104.44

Blow Count 1.45


	.5 ft	1 ft	1.5 ft
Start Time	2	3	2
End Time			
0758			
0759			

Estimated Recovery: 90%

Remarks:

(1) sample in drum @ 0840 hrs.

- 1 = Top of rig floor above ground
 2 = Stickup of csg above ground 1 + measure from floor to top csg = SU
 3 = Total csg length
 4 = Depth of csg = Total Depth (TD)
 Total csg - SU⁽²⁾ = TD
 5 = Casing back pull
 6 = Sampler drive distance
 7 = Total depth of driven sample = 4 + 6



PREPARED BY (Please print): D.E. SKOGLIE
 TITLE: FTL DATE: 090402
 SIGNATURE: *David E Skoglie*

REVIEWED BY (Please print): MG GARDNER
 TITLE: MGR DATE: 10-9-02
 SIGNATURE: *MG Gardner*

DFSNW-WS-00



Duratek Federal Services, Inc., Northwest Operations

C3830 SAMPLE FORM

FAR No. 82

Page 3 of 3

Sample No. 502083-18 Sample Tracking No. 17

Target Depth 108 to 109

(1) 3.35 top of rig floor above ground

(2) 4.57 casing stickup above ground

Csg Total (3) 112.46 - Stickup (2) 4.57 = TD (4)

Does not include drive head 107.89

Backpull stickup (2+5) .25

Sample depth (4) 107.89 to (4+6) 109.19

Blow Count 1.3

	.5 ft	1 ft	1.5 ft
Start Time 1228	2	2	2
End Time 1229			

Estimated Recovery: 90%

Remarks:

(1) Sample in drum C 1311 hrs.

1 = Top of rig floor above ground

2 = Stickup of csg above ground 1 + measure from floor to top csg = SU

3 = Total csg length


4 = Depth of csg = Total Depth (TD)

Total csg - SU⁽²⁾ = TD

5 = Casing back pull

6 = Sampler drive distance

7 = Total depth of driven sample = 4 + 6



PREPARED BY (Please print): D.E. SKOGLIE

TITLE: FTL DATE: 090402

SIGNATURE: David E Skoglie

REVIEWED BY (Please print): MG GARNER

TITLE: MGR DATE:

SIGNATURE: [Signature] 10-9-02



Duratek Federal Services, Inc., Northwest Operations

DRILLING AND SAMPLING (PERCUSSION) DAILY WORK RECORD

Page 1 of 2

WELL I.D.: C3830

WELL NUMBER: N/A

REPORT NUMBER: 83

DATE: September 05, 2002
Thursday

CONTRACT NUMBER: 8248-55

START CARD NO: S00631

RIG MODEL/NO: SIMCO 5000 (Rig 106)

PURPOSE: Daily safety meeting. Casing is drove to a depth 116.75 ft bgs. Obtain samples S02083-19.

REFERENCE: DFSNW-DOW-006,
Rev. 0

LOCATION: TX Tank Farm, 200 West

REFERENCE MEASURING POINT: Steel Plate

TOTAL SHIFT FOOTAGE: 3.85 ft.

CONSTRUCTION DESCRIPTION: N/A

BORING DEPTH:

START: 113.6 ft

END: 117.45 ft

START TIME: 07:00

END TIME: 16:30

CONTRACTOR TIME: 0.5
TOTAL TIME: 2.5

TOTAL TIME: 9.5

CASING SIZE	SET-AT DEPTH	TYPE CASING	DRIVE POINT DIMENSION	START DEPTH	END DEPTH
7.0 " OD	NA	CS	Shoe, 7.5 " OD	113.6 ft	117.45 ft

DOCUMENTED DOWNTIME
N/A

CASING SUMMARY

Bottom of 7 " OD casing (start of shift) = 113.6 ft

Bottom of 7" OD casing (end of shift) = 117.45 ft

Casing (7 in OD) stick up (end of shift) = 4.0 ft

Total casing = 121.45 ft

SAMPLE SUMMARY

Sample: S02083-19 (113.55 – 115.0)

PERSONNEL:

OPERATOR: K. Olson

D Morris/D Curry

WA LICENSE #: 1217

OTHER: DE Skoglie



R. Sharp (Opr)

K. Johnson (PIC)

R. Ancelet (HPT)

WEATHER CONDITIONS (373-2716 or 373-2710)

07:28: Temperature 46F, Humidity 55%,
Barometric pressure 29.21, Wind @ 2 mph

TIME		DESCRIPTION OF OPERATIONS/REMARKS
FROM	TO	
07:00	07:58	Daily safety meeting conducted. Discussed anticipated activities. Complete equipment maintenance and inspection, no deficiencies noted.
07:58	09:02	Trip Dp/tip from boring. Tag depth to bottom @ 113.55 ft bgs. Run sampler to bottom of boring.
09:02	09:12	Set-up drive head and hammer.
07:58	10:00	Drive sample S02083- 19 (#18) 113.55 – 115.0 (1.45 ft) 09:12 – 09:13. Blows 5/7/6. Secure hammer and disassemble drive head. Sample on deck @ 09:56 and in drum @ 10:00 hrs.
10:00	11:40	Trip Dp into boring. Break 10:05 – 10:20. Fuel equipment.
11:40	12:15	Lunch
12:15	12:30	Add casing 4.0 (total 121.45 ft) and Dp 4.0 (total 122.15 ft). Set-up hammer.
12:30	12:47	Drive casing to 116.75 ft bgs. 122.15 – (3.35 + 1.35). Blows 113.6 – 114.0 = 13; 114.0 – 115.0 = 60; 115.0 – 116.0 = 78; 116.0 – 116.42 = 40; and 116.42 – 116.75 = 54; 116.75 – 117.45 refusal. Secure hammer and disassemble drive head assembly. Bore-hole has reached total depth of 117.45 ft bgs.
12:47	15:30	Disassemble Dp coming out of the boring.
15:30	16:30	Secure Site. Complete documentation.
REPORT BY: DE Skogle		REVIEWED BY: KD Reynolds
TITLE: Field Team Lead		TITLE: Project Manager
SIGNATURE: 		DATE: 11-20-02
		SIGNATURE: 



Duratek Federal Services, Inc., Northwest Operations

C3830

SAMPLE FORM

FAR No. 83Page 2 of 3Sample No. S 02083-19 Sample Tracking No. 17 BTarget Depth TBD to TBD(1) 3.35 top of rig floor above ground(2) 7.9 casing stickup above groundCsg Total (3) 121.45 - Stickup (2) 7.9 = TD (4) 113.55

Does not include drive head

Backpull stickup (2+5) ,5Sample depth (4) 113.55 to (4+6) 115.0Blow Count 1.45

	.5 ft	1 ft	1.5 ft
Start Time 0912	5	7	6
End Time 0913			

Estimated Recovery: 100%

Remarks:

(1) Sample in drum @ 10:00 hrs.

1 = Top of rig floor above ground

2 = Stickup of csg above ground 1 + measure from floor to top csg = SU


3 = Total csg length

4 = Depth of csg = Total Depth (TD)
Total csg - SU⁽²⁾ = TD

5 = Casing back pull

6 = Sampler drive distance

7 = Total depth of driven sample = 4 + 6

PREPARED BY (Please print): D.E. SkoglieTITLE: FTLDATE: 09/05/02SIGNATURE: David E. SkoglieREVIEWED BY (Please print): Kent ReynoldsTITLE: Proj. m.

DATE:

SIGNATURE: Kent Reynolds11-20-02

DFSNW-WS-00

Duratek Federal Services, Inc., Northwest Operations

TUBULAR GOODS DUAL STRING TALLY SHEET

Page 3 of 3

DATE: 08/20/02
09/05/02

WELL NUMBER: C3830

CONTINUATION OF REPORT NUMBER: 83

CASING		INNER STRING		CASING		INNER STRING	
JT. NO.	LENGTH (in feet)	JT. NO.	LENGTH (in feet)	JT. NO.	LENGTH (in feet)	JT. NO.	LENGTH (in feet)
1A	1.45 (SHOE)	1B	0.82 (TIP)	19A	5.0 65.45	19B	5.0 71.11
2A	1.99	2B	4.99 (C)	20A	5.0 70.45	20B	2.0 73.11
3A	2.0 5.44	3B	5.25 11.06	21A *	2.0 72.45	21B *	4.0 77.11
4A	5.0 10.44	4B	5.0 (C) 16.06	22A *	4.0 76.45	22B	5.01 82.12
5A	5.0 15.44	5B	4.0 20.06	23A	5.01 81.46	23B	4.0 86.12
OFF 6A	4.0 19.44	6B	5.0 21.06	OFF 24A	4.0 85.46	24B	5.0 87.12
7A	5.0 20.44	7B	5.01 26.07	25A	5.0 86.46	25B	4.0 91.12
8A	5.0 25.44	8B	5.0 31.07	OFF 26A	4.0 90.46	26B	5.01 92.13
9A	5.0 30.44	OFF 9B	2.0 33.07	27A	5.0 91.46	27B	5.0 97.13
OFF 10A	2.0 32.44	10B	5.01 36.08	28A	5.0 96.46	28B	5.01 102.14
11A	5.01 35.45	11B	5.0 41.08	29A	5.0 101.46	29B	2.0 104.14
12A	5.0 40.45	12B	5.01 46.09	30A *	2.0 103.46	30B *	4.0 108.14
13A	5.0 45.45	13B	5.0 51.09	31A *	4.0 107.46	31B	5.0 113.14
14A	5.0 50.45	14B	5.01 56.10	32A	5.0 112.46	32B	5.01 118.15
15A	5.0 55.45	OFF 15B	2.0 58.10	33A	4.99 117.45	33B	4.0 122.15
OFF 16A	2.0 57.45	OFF 16B	4.0 62.10	34A	4.0 121.45	34B	
OFF 17A	4.0 61.45	5 17B	5.0 61.10	35A		35B	
18A	5.0 60.45	18B	5.01 66.11	36A		36B	

TOTAL for Page:

FT

TOTAL for Page:

FT

TOTAL for Page:

FT

TOTAL for Page:

FT

TOTAL (ALL):

FT

TOTAL (ALL):

FT

REPORT BY: DE Skoglie

REVIEWED BY: MG Gardner KD Reynolds

TITLE: Field Team Lead

DATE: 09/05/02

TITLE: Project Manager

DATE: 11-20-02

SIGNATURE: David E. Skoglie


SIGNATURE: KD Reynolds

DRTK-WS-003


* CASING WAS LEFT IN STRING


NOTE 1: SAMPLER + STINGER = 5.67 FT.




NOTE 2: DRIVE HEAD = 3.2 FT.




		Duratek Federal Services, Inc., Northwest Operations						
DRILLING AND SAMPLING (PERCUSSION) DAILY WORK RECORD								Page 1 of 1
WELL I.D.: C3830		WELL NUMBER: N/A		REPORT NUMBER: 84		DATE: September 06, 2002 Friday		
CONTRACT NUMBER: 8248-55			START CARD NO: S00630			RIG MODEL/NO: SIMCO 5000 (Rig 106)		
PURPOSE: Daily Safety meeting. Gyroscope survey and equipment survey and release.				REFERENCE: DFSNW-DOW-006, Rev. 0		LOCATION: TX Tank Farm, 200 West		
REFERENCE MEASURING POINT: Steel Plate				TOTAL SHIFT FOOTAGE: 0.0 ft.				
CONSTRUCTION DESCRIPTION: N/A				BORING DEPTH: START: 117.45 ft END: 117.45 ft		START TIME: 0700 END TIME: 1530 CONTRACTOR TIME: 0.5 TOTAL TIME: 8.5		
CASING SIZE	SET-AT DEPTH	TYPE CASING	DRIVE POINT DIMENSION	START DEPTH	END DEPTH			
7.0 " OD	NA	CS	Shoe, 7.5 " OD	117.45 ft	117.45 ft.			
DOCUMENTED DOWNTIME			CASING SUMMARY			PERSONNEL:		
N/A			Bottom of 7 " OD casing (start of shift) = 117.45 ft.			OPERATOR: KC Olson		
			Bottom of 7" OD casing (end of shift) = 117.45 ft.			DL Curry/DE Morris		
			Casing (7 in OD) stick up (end of shift) = 4.0 ft.			WA LICENSE #: 1217		
WEATHER CONDITIONS (373-2716)			Total Casing = 121.45 ft.			OTHER: D Skoglie		
N/A			SAMPLE SUMMARY			K Johnson (Optr/PIC)		
			N/A			K Hartelius (HPT)		
						K. Flower/R. Sharpe		
						K. Young/F. Hall		
TIME		DESCRIPTION OF OPERATIONS/REMARKS						
FROM	TO							
07:00	07:45	Conduct daily safety meeting.						
07:45		A gyroscope survey was completed.						
		Equipment was surveyed and released (the drill pipe was transported to the Duratek pipe yard and pressure washed.						
	15:30	Documentation was completed. Area secured.						
REPORT BY: DE Skoglie				REVIEWED BY: KD Reynolds				
TITLE: Field Team Lead				TITLE: Project Manager				
SIGNATURE: <u>David E. Skoglie</u>				SIGNATURE: <u>Kent Reynolds</u> DATE: 11-20-02				


		Duratek Federal Services, Inc., Northwest Operations						
DRILLING AND SAMPLING (PERCUSSION) DAILY WORK RECORD								Page 1 of 1
WELL I.D.: C3830		WELL NUMBER: N/A		REPORT NUMBER: 85		DATE: September 09, 2002 Monday		
CONTRACT NUMBER: 8248-55		START CARD NO: S00630		RIG MODEL/NO: SIMCO 5000 (Rig 106)				
PURPOSE: Daily Safety meeting. Geophysical logging of borehole was initiated and equipment survey and release.				REFERENCE: DFSNW-DOW-006, Rev. 0		LOCATION: TX Tank Farm, 200 West		
REFERENCE MEASURING POINT: Steel Plate				TOTAL SHIFT FOOTAGE: 0.0 ft.				
CONSTRUCTION DESCRIPTION: N/A				BORING DEPTH:		START TIME: 0700		
CASING SIZE		SET-AT DEPTH	TYPE CASING	DRIVE POINT DIMENSION	START DEPTH	END DEPTH	END TIME: 1630	
7.0" OD		NA	CS	Shoe, 7.5" OD	117.45 ft	117.45 ft	CONTRACTOR TIME: 0.5	
							TOTAL TIME: 9.5	
DOCUMENTED DOWNTIME				CASING SUMMARY		PERSONNEL:		
N/A				Bottom of 7" OD casing (start of shift) = 117.45 ft.		OPERATOR: KC Olson		
				Bottom of 7" OD casing (end of shift) = 117.45 ft.		DL Curry/DE Morris		
WEATHER CONDITIONS (373-2716)				Casing (7 in OD) stick up (end of shift) = 4.0 ft.		WA LICENSE #: 1217		
N/A				Total Casing = 121.45 ft.		OTHER: D Skoglie		
				SAMPLE SUMMARY		K Johnson (Opt/PIC)		
				N/A		K Hartelius (HPT)		
						K. Flower/R. Sharpe		
						K. Young/F. Hall		
TIME		DESCRIPTION OF OPERATIONS/REMARKS						
FROM	TO							
07:00	07:35	Conduct daily safety meeting.						
07:35		Geophysical logging was conducted. Moisture logging was completed and germanium logging initiated (10 ft).						
		Equipment was surveyed and released. Prepare for moisture sensor installation.						
	16:30	Documentation was completed. Area secured.						
REPORT BY: DE Skoglie				REVIEWED BY: KD Reynolds				
TITLE: Field Team Lead				TITLE: Project Manager				
SIGNATURE: 				DATE: 11-20-02				
				SIGNATURE: 				




		Duratek Federal Services, Inc., Northwest Operations				
DRILLING AND SAMPLING (PERCUSSION) DAILY WORK RECORD						Page 1 of 1
WELL I.D.: C3830		WELL NUMBER: N/A		REPORT NUMBER: 86		DATE: September 10, 2002 Tuesday
CONTRACT NUMBER: 8248-55			START CARD NO: S00630		RIG MODEL/NO: SIMCO 5000 (Rig 106)	
PURPOSE: Daily Safety meeting. Geophysical logging of borehole was initiated and equipment survey and release.				REFERENCE: DFSNW-DOW-006, Rev. 0		LOCATION: TX Tank Farm, 200 West
REFERENCE MEASURING POINT: Steel Plate				TOTAL SHIFT FOOTAGE: 0.0 ft.		
CONSTRUCTION DESCRIPTION: N/A				BORING DEPTH:		START TIME: 0700 END TIME: 1630 CONTRACTOR TIME: 0.5 TOTAL TIME: 9.5
CASING SIZE	SET-AT DEPTH	TYPE CASING	DRIVE POINT DIMENSION	START DEPTH	END DEPTH	
7.0 " OD	NA	CS	Shoe, 7.5 " OD	117.45 ft	117.45 ft.	
DOCUMENTED DOWNTIME			CASING SUMMARY			PERSONNEL: OPERATOR: KC Olson DL Curry/DE Morris WA LICENSE #: 1217 OTHER: D Skoglie K Johnson (Optr/PIC) K Hartelius (HPT) K. Flower/R. Sharpe K. Young/F. Hall
Health Physics - 1.5 hrs.			Bottom of 7 " OD casing (start of shift) = 117.45 ft.			
WEATHER CONDITIONS (373-2716)			Bottom of 7" OD casing (end of shift) = 117.45 ft.			
N/A			Casing (7 in OD) stick up (end of shift) = 4.0 ft.			
			Total Casing = 121.45 ft.			
			SAMPLE SUMMARY			
			N/A			
TIME		DESCRIPTION OF OPERATIONS/REMARKS				
FROM	TO					
07:00	07:35	Conduct daily safety meeting.				
07:35		Geophysical logging was conducted. Germanium logging conducted to 52.0 ft.				
		Equipment was surveyed and released. Prepare for moisture sensor installation.				
	16:30	Documentation was completed. Area secured.				
REPORT BY: DE Skoglie				REVIEWED BY: KD Reynolds		
TITLE: Field Team Lead				TITLE: Project Manager		
SIGNATURE: <i>David E. Skoglie</i>				DATE: 11-10-02		
				SIGNATURE: <i>Kurt Reynolds</i>		




		Duratek Federal Services, Inc., Northwest Operations						
DRILLING AND SAMPLING (PERCUSSION) DAILY WORK RECORD								Page 1 of 1
WELL I.D.: C3830		WELL NUMBER: N/A		REPORT NUMBER: 87		DATE: September 11, 2002 Wednesday		
CONTRACT NUMBER: 8248-55			START CARD NO: S00630			RIG MODEL/NO: SIMCO 5000 (Rig 106)		
PURPOSE: Daily Safety meeting. Geophysical logging of borehole and equipment survey and release.				REFERENCE: DFSNW-DOW-006, Rev. 0		LOCATION: TX Tank Farm, 200 West		
REFERENCE MEASURING POINT: Steel Plate				TOTAL SHIFT FOOTAGE: 0.0 ft.				
CONSTRUCTION DESCRIPTION: N/A				BORING DEPTH:		START TIME: 0700		
CASING SIZE		SET-AT DEPTH	TYPE CASING	DRIVE POINT DIMENSION	START DEPTH	END DEPTH	END TIME: 1630	
7.0 " OD		NA	CS	Shoe, 7.5 " OD	117.45 ft	117.45 ft.	CONTRACTOR TIME: 0.5	
DOCUMENTED DOWNTIME				CASING SUMMARY		PERSONNEL:		
Logging tool - 3 hrs.				Bottom of 7 " OD casing (start of shift) = 117.45 ft.		OPERATOR: KC Olson		
WEATHER CONDITIONS (373-2716)				Bottom of 7" OD casing (end of shift) = 117.45 ft.		DL Curry/DE Morris		
Temperature – 76 F; Wind – N @5 mph;				Casing (7 in OD) stick up (end of shift) = 4.0 ft.		WA LICENSE #: 1217		
Barometric pressure – 29.24; Humidity – 28%.				Total Casing = 121.45 ft.		OTHER: D Skoglie		
				SAMPLE SUMMARY		K Johnson (Optr/PIC)		
				N/A		K Hartelius (HPT)		
						K. Flower/R. Sharpe		
						K. Young/F. Hall		
TIME		DESCRIPTION OF OPERATIONS/REMARKS						
FROM	TO							
07:00	07:30	Conduct daily safety meeting.						
07:30		The logging tool did not remain cooled down. Initiated cool-down @ 10:30 tool is cooled-down. Geophysical logging was conducted. Germanium logging conducted.						
	15:00	Equipment was surveyed and released. Prepare for moisture sensor installation.						
15:00	16:30	Documentation was completed. Area secured.						
REPORT BY: DE Skoglie				REVIEWED BY: KD Reynolds				
TITLE: Field Team Lead				TITLE: Project Manager				
SIGNATURE: <i>David F. Skoglie</i>				SIGNATURE: <i>Kurt Reynolds</i> DATE: 11-20-02				


		Duratek Federal Services, Inc., Northwest Operations						
DRILLING AND SAMPLING (PERCUSSION) DAILY WORK RECORD								Page 1 of 1
WELL I.D.: C3830		WELL NUMBER: N/A		REPORT NUMBER: 88		DATE: September 12, 2002 Thursday		
CONTRACT NUMBER: 8248-55			START CARD NO: S00630			RIG MODEL/NO: SIMCO 5000 (Rig 106)		
PURPOSE: Daily Safety meeting. Geophysical logging completed.				REFERENCE: DFSNW-DOW-006, Rev. 0		LOCATION: TX Tank Farm, 200 West		
REFERENCE MEASURING POINT: Steel Plate				TOTAL SHIFT FOOTAGE: 0.0 ft.				
CONSTRUCTION DESCRIPTION: N/A				BORING DEPTH: START: 117.45 ft END: 117.45 ft		START TIME: 0700 END TIME: 1630 CONTRACTOR TIME: 0.5 TOTAL TIME: 9.5		
CASING SIZE	SET- AT DEPTH	TYPE CASING	DRIVE POINT DIMENSION	START DEPTH	END DEPTH			
7.0 " OD	NA	CS	Shoe, 7.5 " OD	117.45 ft	117.45 ft.			
DOCUMENTED DOWNTIME Health physics – 1.5 hrs. WEATHER CONDITIONS (373-2716) N/A			CASING SUMMARY			PERSONNEL: OPERATOR: KC Olson DL Curry/DE Morris WA LICENSE #: 1217 OTHER: D Skoglie K Johnson (Optr/PIC) K Hartelius (HPT) K. Flower/R. Sharpe K. Young/F. Hall		
			Bottom of 7 " OD casing (start of shift) = 117.45 ft.					
			Bottom of 7" OD casing (end of shift) = 117.45 ft.					
			Casing (7 in OD) stick up (end of shift) = 4.0 ft.					
			Total Casing = 121.45 ft.					
			SAMPLE SUMMARY					
			N/A					
TIME		DESCRIPTION OF OPERATIONS/REMARKS						
FROM	TO							
07:00	07:30	Conduct daily safety meeting.						
07:30	14:00	Geophysical logging was completed. Germanium logging conducted to final depth.						
14:00	15:00	Equipment was surveyed and released. Prepare for moisture sensor installation. Install hydraulic hose on drill unit. Casing slips cleaned. No air samplers on location, therefore back-pulling operations cannot be started.						
15:00	16:30	Documentation was completed. Area secured.						
REPORT BY: DE Skoglie				REVIEWED BY: KD Reynolds				
TITLE: Field Team Lead				TITLE: Project Manager				
SIGNATURE: 				SIGNATURE:  DATE: 11-20-02				


		Duratek Federal Services, Inc., Northwest Operations																																																																																		
DRILLING AND SAMPLING (PERCUSSION) DAILY WORK RECORD						Page 1 of 1																																																																														
WELL I.D.: C3830		WELL NUMBER: N/A		REPORT NUMBER: 89		DATE: September 16, 2002 Monday																																																																														
CONTRACT NUMBER: 8248-55			START CARD NO: S00630		RIG MODEL/NO: SIMCO 5000 (Rig 106)																																																																															
PURPOSE: Daily Safety meeting. Borehole decommissioning and perk test.				REFERENCE: DFSNW-DOW-006, Rev. 0		LOCATION: TX Tank Farm, 200 West																																																																														
REFERENCE MEASURING POINT: Steel Plate				TOTAL SHIFT FOOTAGE: 16.26 ft. (decommissioning)																																																																																
CONSTRUCTION DESCRIPTION: N/A				BORING DEPTH: START: 117.45 ft END: 101.19 ft		START TIME: 0700 END TIME: 1630 CONTRACTOR TIME: 0.5 TOTAL TIME: 9.5																																																																														
CASING SIZE 7.0" OD	SET-AT DEPTH NA	TYPE CASING CS	DRIVE POINT DIMENSION Shoe, 7.5" OD	START DEPTH 117.45 ft	END DEPTH 96.11 ft.																																																																															
DOCUMENTED DOWNTIME Health physics – 1.0 hrs. WEATHER CONDITIONS (373-2716) Temperature – 64F; Wind – NW @5; Barometric pressure 29.15; Humidity – 52%.			CASING SUMMARY Bottom of 7" OD casing (start of shift) = 117.45 ft. Bottom of 7" OD casing (end of shift) = 96.11 ft. Casing (7 in OD) stick up (end of shift) = 5.35 ft. Total Casing (end of shift) = 101.46 ft. SAMPLE SUMMARY N/A		PERSONNEL: OPERATOR: KC Olson DL Curry/DE Morris WA LICENSE #: 1217 OTHER: D Skoglie K Johnson (Optr/PIC) K Hartelius (HPT) K. Flower/R. Sharpe K. Young/F. Hall																																																																															
TIME FROM TO		DESCRIPTION OF OPERATIONS/REMARKS																																																																																		
07:00 09:00		Conduct daily safety meeting. Complete equipment inspection with no deficiencies. A discussion was held regarding completion of the boring. 08:35 the Work Package is on location.																																																																																		
09:00		Set-up air samplers. Haul bentonite to rig from staging area (inside TX Tank Farm).																																																																																		
11:00		Back-pull casing (4 and 4.99 ft). Hydraulic pressure to back-pull is 1,900 psig. Tag DTB 116.95 ft bgs (122.3 – (3.35 + 2.0)) 10:50 hrs. Add bentonite (4. sks) through casing to 108.94 ft bgs (113.2 – [3.35 + 0.91]). Back-pull casing 5.0 ft. Casing @ 103.2 ft bgs. Add bentonite crumbles (1 sk) to a depth of 106.99 ft bgs (111.25 – (3.35 + 0.91)). Run tremie through casing shoe (110.0 – [3.35 + 3.2] = 103.45 ft bgs).																																																																																		
11:00 11:05		Add 2 gallon water to hydrate bentonite. Add sand (10 – 30) 2.6 gallons. Tag 112.4 – (3.35 + 3.15) = 105.9 ft bgs.																																																																																		
11:05		Lunch (11:05 – 11:35) Hydrate bentonite.																																																																																		
12:29		Tag DTB @ 105.87 ft bgs (112.37 – [3.35 + 3.15]). Add 4 gallons water and monitor test as follows:																																																																																		
12:29 14:08		<table border="1"> <thead> <tr> <th>Time</th> <th>Tape Measurement</th> <th>BGS Measurement</th> <th>Time</th> <th>Tape Measurement</th> <th>BGS Measurement</th> </tr> </thead> <tbody> <tr><td>12:29</td><td>110.04</td><td>103.54</td><td>12:30</td><td>110.05</td><td>103.55</td></tr> <tr><td>12:31</td><td>110.05</td><td>103.55</td><td>12:32</td><td>110.05</td><td>103.55</td></tr> <tr><td>12:33</td><td>110.06</td><td>103.56</td><td>12:34</td><td>110.06</td><td>103.56</td></tr> <tr><td>12:35</td><td>110.06</td><td>103.56</td><td>12:36</td><td>110.06</td><td>103.56</td></tr> <tr><td>12:37</td><td>110.06</td><td>103.56</td><td>12:38</td><td>110.06</td><td>103.56</td></tr> <tr><td>12:43</td><td>110.06</td><td>103.56</td><td>12:48</td><td>110.06</td><td>103.56</td></tr> <tr><td>12:53</td><td>110.06</td><td>103.56</td><td>12:58</td><td>110.06</td><td>103.56</td></tr> <tr><td>13:03</td><td>110.07</td><td>103.57</td><td>13:08</td><td>110.07</td><td>103.57</td></tr> <tr><td>13:13</td><td>110.08</td><td>103.58</td><td>13:18</td><td>110.08</td><td>103.58</td></tr> <tr><td>13:23</td><td>110.10</td><td>103.60</td><td>13:28</td><td>110.11</td><td>103.61</td></tr> <tr><td>13:38</td><td>110.13</td><td>103.63</td><td>13:48</td><td>110.15</td><td>103.65</td></tr> <tr><td>13:58</td><td>110.18</td><td>103.68</td><td>14:08</td><td>110.20</td><td>103.70</td></tr> </tbody> </table>					Time	Tape Measurement	BGS Measurement	Time	Tape Measurement	BGS Measurement	12:29	110.04	103.54	12:30	110.05	103.55	12:31	110.05	103.55	12:32	110.05	103.55	12:33	110.06	103.56	12:34	110.06	103.56	12:35	110.06	103.56	12:36	110.06	103.56	12:37	110.06	103.56	12:38	110.06	103.56	12:43	110.06	103.56	12:48	110.06	103.56	12:53	110.06	103.56	12:58	110.06	103.56	13:03	110.07	103.57	13:08	110.07	103.57	13:13	110.08	103.58	13:18	110.08	103.58	13:23	110.10	103.60	13:28	110.11	103.61	13:38	110.13	103.63	13:48	110.15	103.65	13:58	110.18	103.68	14:08	110.20	103.70
Time	Tape Measurement	BGS Measurement	Time	Tape Measurement	BGS Measurement																																																																															
12:29	110.04	103.54	12:30	110.05	103.55																																																																															
12:31	110.05	103.55	12:32	110.05	103.55																																																																															
12:33	110.06	103.56	12:34	110.06	103.56																																																																															
12:35	110.06	103.56	12:36	110.06	103.56																																																																															
12:37	110.06	103.56	12:38	110.06	103.56																																																																															
12:43	110.06	103.56	12:48	110.06	103.56																																																																															
12:53	110.06	103.56	12:58	110.06	103.56																																																																															
13:03	110.07	103.57	13:08	110.07	103.57																																																																															
13:13	110.08	103.58	13:18	110.08	103.58																																																																															
13:23	110.10	103.60	13:28	110.11	103.61																																																																															
13:38	110.13	103.63	13:48	110.15	103.65																																																																															
13:58	110.18	103.68	14:08	110.20	103.70																																																																															
14:08		Terminate test (Mr. Sydnor). Pull tremie out of boring. Back-pull casing (4 ft). Casing pulled @ 1,300 psig. Add 1 sk crumbles. Pull casing (2 ft). Casing @ 96.11 ft BGS (101.46 – [3.35 + 2.0]). Tag 109.13 – (3.35 + 2.61) = 103.17 ft BGS.																																																																																		
		Add bentonite crumbles (1 sk). Tag 107.15 – (3.35 + 2.61) = 101.19 ft BGS.																																																																																		
16:30		Secure Site due Health Physics (15:10 hrs.) Complete documentation and discuss upcoming operations.																																																																																		
REPORT BY: DE Skoglie TITLE: Field Team Lead SIGNATURE: 				REVIEWED BY: KD Reynolds TITLE: Project Manager SIGNATURE: 																																																																																
				DATE: 11-10-02																																																																																



		Duratek Federal Services, Inc., Northwest Operations				
DRILLING AND SAMPLING (PERCUSSION) DAILY WORK RECORD						Page 1 of 1
WELL I.D.: C3830		WELL NUMBER: N/A		REPORT NUMBER: 90		DATE: September 17, 2002 Tuesday
CONTRACT NUMBER: 8248-55			START CARD NO: S00630		RIG MODEL/NO: SIMCO 5000 (Rig 106)	
PURPOSE: Daily Safety meeting. Borehole decommissioning and moisture tensiometer installation.				REFERENCE: DFSNW-DOW-006, Rev. 0		LOCATION: TX Tank Farm, 200 West
REFERENCE MEASURING POINT: Steel Plate				TOTAL SHIFT FOOTAGE: 39.54 ft. (decommissioning)		
CONSTRUCTION DESCRIPTION: N/A						BORING DEPTH: START: 101.19 ft END: 61.65 ft
CASING SIZE 7.0" OD	SET-AT DEPTH NA	TYPE CASING CS	DRIVE POINT DIMENSION Shoe, 7.5" OD	START DEPTH 96.11 ft	END DEPTH 59.9 ft.	
DOCUMENTED DOWNTIME Minimal WEATHER CONDITIONS (373-2716) Temperature 57F; Wind SW 5-9; Humidity 77%.		CASING SUMMARY Bottom of 7" OD casing (start of shift) = 96.11 ft. Bottom of 7" OD casing (end of shift) = 59.90 ft. Casing (7 in OD) stick up (end of shift) = 2.2 ft. Total Casing (end of shift) = 65.45 ft. SAMPLE SUMMARY N/A				PERSONNEL: OPERATOR: KC Olson DL Curry/DE Morris WA LICENSE #: 1217 OTHER: D Skoglie K Johnson (Opnr/PIC) K Hartelius (HPT) K. Flower/R. Sharpe K. Young/F. Hall
TIME FROM TO		DESCRIPTION OF OPERATIONS/REMARKS				
07:00	09:30	Initial start-up delay, the PIC is in training. Conduct daily safety meeting. Complete equipment inspection with no deficiencies. A discussion was held regarding completion of the boring.				
09:30	09:52	Initial tag revealed a depth of 101.19 ft BGS. New S.U. on tremie (PVC) 101.2 ft BGS. Add sand 1 sk, a depth of 98.95 ft BGS was obtained. Top of landing plate is 2.75 ft. 105.05 bottom of boring to landing plate.				
09:52	10:24	The tensiometer is layed out and marked. Water is added to the tensiometer. The tensiometer is ran to bottom.				
10:24	10:53	Sand (5 gallon) and water (5 gallon) was tremmied through the casing shoe. A tag revealed a depth to bottom of 96.8 ft BGS (102.9 - [3.35 + 2.75]). Add 1/8 sk sand and retag @ 96.6 ft BGS (102.7 - [3.35 + 2.75]).				
10:53	11:30	Pull tremie out of boring. Pull casing (5.0 ft). Casing pulling @ 800 psig.				
11:30	12:40	Lunch CHG and Duratek Management onsite to BBQ for crew. The Rib Steaks were superb.				
12:40	13:42	Move the pulley to the rotary head saver sub (alignment is better). A tag revealed a depth of 96.25 ft BGS (101.5 - [3.35 + 1.9]). Casing @ 91.21 ft BGS. Add bentonite (2 sks). A tag determined a depth of 92.25 ft BGS (97.5 - [3.35 + 1.9]). Pull casing (2 - 5's). Casing depth is 81.01 ft BGS (86.46 - [3.35 + 2.1]).				
13:42	14:50	Add bentonite (4 sks) 13:47 hrs. Tag determined a depth of 83.95 ft BGS (89.4 - [3.35 + 2.1]). Pull casing (5.0 and 5.01 ft in length). Casing depth is 71.5 ft BGS 76.45 - (3.35 + 1.6). Tag revealed a depth of 83.85 ft BGS. Add 4 sks bentonite. Depth of bottom hole is 76.0 ft BGS (80.95 - [3.35 + 1.6]). Add 1 sk bentonite.				
14:50	15:15	No HPT helping survey out surveyors (15 minutes). Pull casing 4 ft, 2 ft, and 5.0 ft. Casing depth is 59.9 ft BGS (65.45 - [3.35 + 2.2]). A tag revealed a depth to bottom of 73.95 ft BGS (79.5 - [3.35 + 2.2]).				
15:15	15:35	Add bentonite 6 sks. A tag determined a depth of 61.65 ft BGS (67.2 - [3.35 + 2.2]).				
15:35	16:30	Secure site and exit TX Tank Farm. Conduct discussion regarding field operations.				
REPORT BY: DE Skoglie TITLE: Field Team Lead SIGNATURE: <u>David E. Skoglie</u>				REVIEWED BY: MG Gardner TITLE: Project Manager DATE: 10-9-02 SIGNATURE: <u>MG Gardner</u>		

		Duratek Federal Services, Inc., Northwest Operations						
DRILLING AND SAMPLING (PERCUSSION) DAILY WORK RECORD								Page 1 of 1
WELL I.D.: C3830		WELL NUMBER: N/A		REPORT NUMBER: 91		DATE: September 18, 2002 Wednesday		
CONTRACT NUMBER: 8248-55		START CARD NO: S00630		RIG MODEL/NO: SIMCO 5000 (Rig 106)				
PURPOSE: Daily Safety meeting. Borehole decommissioning and perk test.				REFERENCE: DFSNW-DOW-006, Rev. 0		LOCATION: TX Tank Farm, 200 West		
REFERENCE MEASURING POINT: Steel Plate				TOTAL SHIFT FOOTAGE: 19.05 ft. (decommissioning)				
CONSTRUCTION DESCRIPTION: N/A				BORING DEPTH:		START TIME: 0700		
CASING SIZE		SET-AT DEPTH	TYPE CASING	DRIVE POINT DIMENSION	START DEPTH	END DEPTH	END TIME: 1630	
7.0 " OD		NA	CS	Shoe, 7.5 " OD	59.90 ft	40.1 ft.	CONTRACTOR TIME: 0.5	
							TOTAL TIME: 9.5	
DOCUMENTED DOWNTIME Health physics – 1.0 hrs. WEATHER CONDITIONS (373-2716) 07:33 Temperature – 44F; Wind – E @ 3; Barometric pressure 29.29; Humidity – 53%.				CASING SUMMARY		PERSONNEL:		
				Bottom of 7 " OD casing (start of shift) = 59.9 ft.		OPERATOR: KC Olson		
				Bottom of 7 " OD casing (end of shift) = 40.1 ft.		DL Curry/DE Morris		
				Casing (7 in OD) stick up (end of shift) = 2.0 ft.		WA LICENSE #: 1217		
				Total Casing (end of shift) = 45.45 ft.		OTHER: D Skoglie		
				SAMPLE SUMMARY		K Johnson (Optr/PIC)		
				N/A		K Hartelius (HPT)		
						K. Flower/R. Sharpe		
						K. Young/F. Hall		
TIME		DESCRIPTION OF OPERATIONS/REMARKS						
FROM	TO							
07:00	08:25	Conduct daily and weekly safety meeting. Complete equipment inspection with no deficiencies. 07:32 the Work Package is on location.						
08:25	08:40	Back pull casing to 0.9 S.U. Casing @ 56.2 ft BGS. A tag revealed a depth of 61.7 ft BGS (65.95 – [3.35 + 0.9]) 08:37 hrs. Add bentonite pellets (2/3 bucket). Tag recorded a depth to bottom of 59.95 ft BGS.						
08:40	10:01	Run tremie to a depth of 57.45 ft BGS. Casing shoe @ 56.2 ft BGS. Add 2 gallons water. Hydrate 08:50 – 10:01 hrs.						
10:01	10:14	E-tape reading determined 0.8 feet water in bore-hole. Add 10 – 30 sand (1/2 bucket). A tag determined a depth of 59.05 ft BGS (65.0 – [3.35 + 2.6]).						
10:14		Add 4 gallons water and monitor test as follows:						
	11:57	Time	Tape Measurement	BGS Measurement	Time	Tape Measurement	BGS Measurement	
		10:16	62.96	57.01	10:17	62.97	57.02	
		10:18	62.98	57.03	10:19	62.98	57.03	
		10:20	62.98	57.03	10:21	62.99	57.04	
		10:22	62.99	57.04	10:23	62.99	57.04	
		10:24	62.99	57.04	10:25	63.0	57.05	
		10:26	63.0	57.05	10:27	63.0	57.05	
		10:32	63.02	57.07	10:37	63.04	57.09	
		10:42	63.05	57.10	10:47	63.06	57.11	
		10:52	63.08	57.13	10:57	63.10	57.15	
		11:02	63.12	57.17	11:07	63.17	57.17	
		11:12	63.15	57.20	11:17	63.17	57.22	
		11:27	63.18	57.23	11:37	63.21	57.26	
		11:47	63.25	57.30	11:57	63.26	57.31	
11:57	12:53	Terminate test (Mr. Syndor). Secure site. Lunch 12:23 – 12:53						
12:53	13:32	Pull tremie from boring. Backpull casing (5.0) 55.45 – (3.35 + 2.0) = 50.1 ft BGS. Tag revealed a depth to bottom measurement of 58.75 ft BGS (64.1 – [3.35 + 2.0]). Add 1 sk chips. Tag recorded a depth of 56.25 ft BGS (61.6 ft – [3.35 + 2.0]). Add 1/4 sk bentonite, a tag recorded 55.25 ft BGS (60.6 – [3.35 + 2.0]). Add 10 – 30 sand (5 gallon). A tag determined bottom @ 53 ft BGS (58.35 – [3.35 + 2.0]).						
13:32	14:25	Pre-mark length of tensiometer cable. Run tremie through casing shoe. Place tensiometer in boring. Slurry sand and water (2.5 gallons each). A tag determined a depth to 51.85 ft BGS (57.2 – [3.35 + 2.0]). Pull casing 5.0, casing @ 48.8 ft BGS (55.45 – [3.35 + 3.3]). Add sand and water slurry (2.5 gallons each). A tag showed a DTB of 51.15 ft BGS (57.8 – [3.35 + 3.3]).						
14:25	15:12	Add sand 2.3 gallons. A tag determined a DTB of 50.15 ft BGS (56.8 – [3.35 + 3.3]). Pull casing (5.0). Pulling pressure on the hydraulic jacks is 150 psig. Casing @ 40.1 ft BGS (45.45 – [3.35 + 2.0]). A tag showed a DTB of 49.95 ft BGS (55.3 – [3.35 + 2.0]).						
15:12	16:30	Add 4 sks bentonite. A DTB measurement determined 42.6 ft BGS (47.95 – [3.35 + 2.0]). Casing @ 40.1 ft BGS. Secure site.						
REPORT BY: DE Skoglie				REVIEWED BY: MG Gardner				
TITLE: Field Team Lead				TITLE: Project Manager				
SIGNATURE: 				SIGNATURE:  DATE: 10-9-02				

		Duratek Federal Services, Inc., Northwest Operations				
DRILLING AND SAMPLING (PERCUSSION) DAILY WORK RECORD						Page 1 of 1
WELL I.D.: C3830		WELL NUMBER: N/A		REPORT NUMBER: 92		DATE: September 19, 2002 Thursday
CONTRACT NUMBER: 8248-55			START CARD NO: S00630		RIG MODEL/NO: SIMCO 5000 (Rig 106)	
PURPOSE: Daily Safety meeting. Borehole decommissioning.				REFERENCE: DFSNW-DOW-006, Rev. 0		LOCATION: TX Tank Farm, 200 West
REFERENCE MEASURING POINT: Steel Plate				TOTAL SHIFT FOOTAGE: 42.6 ft. (decommissioning)		
CONSTRUCTION DESCRIPTION: N/A				BORING DEPTH: START: 42.6 ft END: 0.0 ft		START TIME: 0700 END TIME: 1630 CONTRACTOR TIME: 0.5 TOTAL TIME: 9.5
CASING SIZE 7.0" OD	SET-AT DEPTH NA	TYPE CASING CS	DRIVE POINT DIMENSION Shoe, 7.5" OD	START DEPTH 40.1 ft	END DEPTH 0.0 ft	
DOCUMENTED DOWNTIME Minimal WEATHER CONDITIONS (373-2716) Temperature 59F; Wind N 7; Humidity 74%; Barometric pressure 29.24.			CASING SUMMARY Bottom of 7" OD casing (start of shift) = 40.6 ft. Bottom of 7" OD casing (end of shift) = 0.0 ft. Casing (7 in OD) stick up (end of shift) = 0.0 ft. Total Casing (end of shift) = 0.0 ft.		PERSONNEL: OPERATOR: KC Olson DL Curry/DE Morris WA LICENSE #: 1217 OTHER: D Skoglie K Johnson (Optr/PIC) R. Ancelet (HPT) K. Flower/R. Sharpe K. Young/F. Hall	
TIME FROM TO		DESCRIPTION OF OPERATIONS/REMARKS				
07:00 07:50		Conduct daily safety meeting. Complete equipment inspection with no deficiencies.				
07:50 08:35		Pull casing 5.0 and 5.0. Casing depth is 29.9 ft BGS (35.45 – [3.35 + 2.2]). A tag revealed a depth to bottom measurement of 42.25 ft BGS (47.9 – [3.35 + 2.3]). Add 5 sks bentonite. A tag determined depth to be 32.25 ft BGS.				
08:35 09:10		Pull casing 5.01 and 5.0. Casing depth is 19.89 ft BGS (25.44 – [3.35 + 2.2]). A tag revealed a depth to bottom measurement of 32.2 ft BGS (37.75 – [3.35 + 2.2]). Add 5 sks bentonite. A tag determined depth to be 22.45 ft BGS (28.0 – [3.35 + 2.2]).				
09:10 10:10		Pull casing 5.0. Casing depth is 15.29 ft BGS (20.44 – [3.35 + 1.8]). Radiological contamination was found on this section of casing. The HPT stated 450 cts/minute (non-smearable). This section of casing was double sleeved and secured in TX Tank Farm.				
10:10 11:25		Pull casing 5.0. Casing depth is 9.99 ft BGS (15.44 – [3.35 + 2.1]). A tag revealed a depth to bottom measurement of 22.35 ft BGS (27.8 – [3.35 + 2.1]). Add 5 3/4 sks bentonite. A tag determined depth to be 10.6 ft BGS (15.25 – [3.35 + 1.3]). Add sand (10 – 30) 4 gallons. A tag determined depth to bottom @ 9.0 ft BGS (13.65 – [3.35 + 1.3]).				
11:25 11:47		Tensiometer placed in borehole. Placed (slurried) 5 gallon water through tremie and 5 gallons sand through casing. A tag depth to bottom is 7.45 ft BGS (12.0 – [3.35 + 1.2]). Add bentonite 1 gallon. A tag determined depth to bottom is 6.9 ft BGS (11.45 – [3.35 + 1.2]).				
11:47 12:20		Add 2.8 gallons sand. Tag sand @ 5.85 ft BGS. Tensiometer placed in borehole. Placed (slurried) 5 gallon water through tremie and 5 gallons sand through casing. A tag depth to bottom is 4.35 ft BGS (11.7 – [3.35 + 4.0]). Pull casing 1 ft. Add sand 3.3 gallons. A tag determined depth to bottom is 2.9 ft BGS (11.25 – [3.35 + 5.0]). Add bentonite 1.7 gallons. Depth to bottom is 1.15 ft BGS (10.5 – [3.35 + 5.0]). Pull casing, depth is 1.59 ft BGS (10.44 – [3.35 + 5.5]).				
12:20 13:50		Borehole is filled with natural material. Borehole is decommissioned/completed. BSE personnel worked through lunch to finish completion. The wind is expected to pick u.				
13:50 14:30		lunch				
14:30 16:30		Remove and disassemble remaining casing string (shoe and short sections). Area is secured.				
REPORT BY: DE Skoglie TITLE: Field Team Lead SIGNATURE: 				REVIEWED BY: MG Gardner TITLE: Project Manager DATE: 10-9-02 SIGNATURE: 		

		Duratek Federal Services, Inc., Northwest Operations						
DRILLING AND SAMPLING (PERCUSSION) DAILY WORK RECORD								Page 1 of 1
WELL I.D.: C3830		WELL NUMBER: N/A		REPORT NUMBER: 93		DATE: September 20, 2002 Friday		
CONTRACT NUMBER: 8248-55		START CARD NO: S00630		RIG MODEL/NO: SIMCO 5000 (Rig 106)				
PURPOSE: Daily Safety meeting. Equipment survey and demobilization.				REFERENCE: DFSNW-DOW-006, Rev. 0		LOCATION: TX Tank Farm, 200 West		
REFERENCE MEASURING POINT: Steel Plate				TOTAL SHIFT FOOTAGE: 0.0 ft.				
CONSTRUCTION DESCRIPTION: N/A				BORING DEPTH:		START TIME: 0700		
CASING SIZE		SET-AT DEPTH	TYPE CASING	DRIVE POINT DIMENSION	START DEPTH	END DEPTH	END TIME: 15:30	
7.0" OD		NA	CS	Shoe, 7.5" OD	0.0 ft	0.0 ft.	CONTRACTOR TIME: 0.5	
						TOTAL TIME: 8.5		
DOCUMENTED DOWNTIME				CASING SUMMARY		PERSONNEL:		
Operator/Health Physics – 4 hrs.				Bottom of 7" OD casing (start of shift) = 0.0 ft.		OPERATOR: KC Olson		
WEATHER CONDITIONS (373-2716)				Bottom of 7" OD casing (end of shift) = 0.0 ft.		DL Curry/DE Morris		
N/A				Casing (7 in OD) stick up (end of shift) = 0.0 ft.		WA LICENSE #: 1217		
				Total Casing = 0.0 ft.		OTHER: D Gostovich		
				SAMPLE SUMMARY		K Johnson (Optr/PIC)		
				N/A		R. Ancelet (HPT)		
TIME		DESCRIPTION OF OPERATIONS/REMARKS						
FROM	TO							
07:00	07:30	Conduct daily safety meeting. A discussion was held regarding anticipated activities. No operator coverage today, which means that the fork lift can not be operated.						
07:30	08:30	PIC arrives with work package @ 08:00 hrs.						
08:30		Contractor enters TX Tank Farm. The jacks were moved to the work platform. Support equipment was placed on pallets.						
	12:00	The TX Tank Farm gate was locked.						
12:00	12:30	Lunch						
12:30		BSE loaded miscellaneous on the flatbed and hauled to the yard. Equipment was cleaned and put away.						
	15:30	Documentation was completed. Area secured.						
REPORT BY: DE Gostovich				REVIEWED BY: MG Gardner				
TITLE: Field Team Lead				TITLE: Project Manager				
SIGNATURE: <i>David E. Shoglin for</i>				DATE: 10-9-02				
				SIGNATURE: <i>MG Gardner</i>				

		Duratek Federal Services, Inc., Northwest Operations						
DRILLING AND SAMPLING (PERCUSSION) DAILY WORK RECORD								Page 1 of 1
WELL I.D.: C3830		WELL NUMBER: N/A		REPORT NUMBER: 94		DATE: September 23, 2002 Monday		
CONTRACT NUMBER: 8248-55			START CARD NO: S00630			RIG MODEL/NO: SIMCO 5000 (Rig 106)		
PURPOSE: Daily Safety meeting. Equipment survey and demobilization.				REFERENCE: DFSNW-DOW-006, Rev. 0		LOCATION: TX Tank Farm, 200 West		
REFERENCE MEASURING POINT: Steel Plate				TOTAL SHIFT FOOTAGE: 0.0 ft.				
CONSTRUCTION DESCRIPTION: N/A				BORING DEPTH:		START TIME: 0700		
CASING SIZE		SET-AT DEPTH	TYPE CASING	DRIVE POINT DIMENSION	START DEPTH	END DEPTH	END TIME: 16:30	
7.0 " OD		NA	CS	Shoe, 7.5 " OD	0.0 ft	0.0 ft.	CONTRACTOR TIME: 0.5	
							TOTAL TIME: 9.5	
DOCUMENTED DOWNTIME N/A WEATHER CONDITIONS (373-2716) N/A				CASING SUMMARY		PERSONNEL:		
				Bottom of 7 " OD casing (start of shift) = 0.0 ft.		OPERATOR: KC Olson		
				Bottom of 7" OD casing (end of shift) = 0.0 ft.		DL Curry/DE Morris		
				Casing (7 in OD) stick up (end of shift) = 0.0 ft.		WA LICENSE #: 1217		
				Total Casing = 0.0 ft.		OTHER: D Gostovich		
				SAMPLE SUMMARY		K Johnson (Optr/PIC)		
				N/A		R. Sharp		
						R. Ancelet (HPT)		
						K. Hartelius		
TIME		DESCRIPTION OF OPERATIONS/REMARKS						
FROM	TO							
07:00	07:45	Conduct daily safety meeting. A discussion was held regarding anticipated activities.						
07:45		Contractor enters TX Tank Farm. The jacks were moved to the work platform. All pipe and support equipment was staged near the exit gate. The jacks were removed from the work platform.						
	10:00	The drill unit's mast was layed over and secured.						
10:00	11:30	The drill trailer was moved to the gate by the Teamster. Health Physics started the survey of the drill unit.						
11:30	12:20	Lunch						
12:20		The matting, plastic, and berm material was wrapped up and discarded (non-radiological waste).						
		The drill unit's survey was completed @ 15:30 hrs. The drill trailer was moved out of the TX Tank Farm.						
	15:45	Area secured. The TX Tank Farm gate was locked.						
15:45	16:30	BSE worked on the drill unit.						
REPORT BY: DE Gostovich				REVIEWED BY: MG Gardner				
TITLE: Field Team Lead				TITLE: Project Manager				
SIGNATURE: <i>David E. Shoglin Jr</i>				DATE: 10-9-02				
				SIGNATURE: <i>MG Gardner</i>				

		Duratek Federal Services, Inc., Northwest Operations						
DRILLING AND SAMPLING (PERCUSSION) DAILY WORK RECORD								Page 1 of 1
WELL I.D.: C3830		WELL NUMBER: N/A		REPORT NUMBER: 95		DATE: September 24, 2002 Tuesday		
CONTRACT NUMBER: 8248-55			START CARD NO: S00630			RIG MODEL/NO: SIMCO 5000 (Rig 106)		
PURPOSE: Daily Safety meeting. Equipment survey and demobilization.				REFERENCE: DFSNW-DOW-006, Rev. 0		LOCATION: TX Tank Farm, 200 West		
REFERENCE MEASURING POINT: Steel Plate				TOTAL SHIFT FOOTAGE: 0.0 ft.				
CONSTRUCTION DESCRIPTION: N/A				BORING DEPTH:		START TIME: 0700		
CASING SIZE		SET-AT DEPTH	TYPE CASING	DRIVE POINT DIMENSION	START DEPTH	END DEPTH	END TIME: 16:30	
7.0" OD		NA	CS	Shoe, 7.5" OD	0.0 ft	0.0 ft.	CONTRACTOR TIME: 0.5	
							TOTAL TIME: 9.5	
DOCUMENTED DOWNTIME N/A WEATHER CONDITIONS (373-2716) N/A				CASING SUMMARY		PERSONNEL: OPERATOR: KC Olson DL Curry/DE Morris WA LICENSE #: 1217 OTHER: D Gostovich K Johnson (Optr/PIC) R. Sharp R. Ancelet (HPT) K. Hartelius		
				Bottom of 7" OD casing (start of shift) = 0.0 ft.				
				Bottom of 7" OD casing (end of shift) = 0.0 ft.				
				Casing (7 in OD) stick up (end of shift) = 0.0 ft.				
				Total Casing = 0.0 ft.				
				SAMPLE SUMMARY				
				N/A				
TIME		DESCRIPTION OF OPERATIONS/REMARKS						
FROM	TO							
07:00	07:30	Conduct daily safety meeting. A discussion was held regarding anticipated activities.						
07:30	11:30	Contractor enters TX Tank Farm. Equipment is loaded on the flatbed and equipment trailer and hauled to the Duratek yard.						
11:30	12:20	Lunch						
12:20		Demobilized equipment from the TX Tank Farm. Items were hauled to Duratek's yard where items were cleaned and organized.						
	16:30	Area Secured.						
REPORT BY: DE Gostovich				REVIEWED BY: MG Gardner				
TITLE: Field Team Lead				TITLE: Project Manager				
SIGNATURE: 				DATE: 10-9-02				
				SIGNATURE: 				

		<h2 style="margin: 0;">Duratek Federal Services, Inc., Northwest Operations</h2>									
<h3 style="margin: 0;">DRILLING AND SAMPLING (PERCUSSION) DAILY WORK RECORD</h3>										Page 1 of 1	
WELL I.D.: C3830			WELL NUMBER: N/A			REPORT NUMBER: 96			DATE: September 25, 2002 Wednesday		
CONTRACT NUMBER: 8248-55				START CARD NO: S00630				RIG MODEL/NO: SIMCO 5000 (Rig 106)			
PURPOSE: Daily Safety meeting. Equipment survey and demobilization. Last Report.						REFERENCE: DFSNW-DOW-006, Rev. 0			LOCATION: TX Tank Farm, 200 West		
REFERENCE MEASURING POINT: Steel Plate						TOTAL SHIFT FOOTAGE: 0.0 ft.					
CONSTRUCTION DESCRIPTION: N/A						BORING DEPTH: START: 0.0 ft END: 0.0 ft			START TIME: 0700 END TIME: 16:30 CONTRACTOR TIME: 0.5 TOTAL TIME: 9.5		
CASING SIZE	SET-AT DEPTH	TYPE CASING	DRIVE POINT DIMENSION	START DEPTH	END DEPTH						
7.0" OD	NA	CS	Shoe, 7.5" OD	0.0 ft	0.0 ft.						
DOCUMENTED DOWNTIME N/A WEATHER CONDITIONS (373-2716) N/A				CASING SUMMARY			PERSONNEL: OPERATOR: KC Olson DL Curry/DE Morris WA LICENSE #: 1217 OTHER: D Gostovich K Johnson (Optr/PIC) R. Sharp R. Ancelet (HPT) K. Hartelius				
				Bottom of 7" OD casing (start of shift) = 0.0 ft.							
				Bottom of 7" OD casing (end of shift) = 0.0 ft.							
				Casing (7 in OD) stick up (end of shift) = 0.0 ft.							
				Total Casing = 0.0 ft.							
SAMPLE SUMMARY			N/A								
TIME		DESCRIPTION OF OPERATIONS/REMARKS									
FROM	TO										
07:00	07:30	Conduct daily safety meeting. A discussion was held regarding anticipated activities.									
07:30	10:30	Contractor enters TX Tank Farm. Equipment is loaded on the flatbed and equipment trailer and hauled to the Duratek yard. All equipment is removed from the TX Tank Farm.									
10:30	11:30	Haul materials/equipment to Duratek's yard.									
11:30	12:00	Lunch									
12:00		Items were hauled to Duratek's yard where items were cleaned and organized.									
	16:30	Area Secured.									
		N/A									
REPORT BY: DE Gostovich						REVIEWED BY: MG Gardner					
TITLE: Field Team Lead						TITLE: Project Manager					
SIGNATURE: <i>David E. Shoglin</i>						DATE: 10-9-02					
SIGNATURE: <i>[Signature]</i>						SIGNATURE: <i>[Signature]</i>					

This page intentionally left blank.

APPENDIX B
GEOLOGIC SAMPLE LOGS

This page intentionally left blank.

C3B30 TX-105

10/16/02

1)
1.35'

15-15.5' Backfill; uniform med-fine sand w/ occasional basalt pebble gravel moist; 7.5 yr 5/2 brown; no fizz; some impact bedding apparent in upper sample - drill method

15.5-16'

15.5-16' Backfill 7.5 yr 5/2 Brown; moist; uniform fine-med sand; rounded basalt pebble gravel in core catcher. No fizz

27.9-28.4'

2)
1.34'

27.9-28.4' Backfill; sand-fine-med w/ occasional subrounded-rounded basalt pebbles; CaCO_3 interspersed & rxn impact features; brown 7.5 yr 5/2

28.4-28.9'

28.4-28.9' Gravelly sand; fine-med sand; rounded basalt fine-med basalt pebble gravel; moist; unconsolidated 10 yr 5/2 grayish brown; CaCO_3 med.

3) 40.9-41.9	40.9-41.9	(40.9-41.9) Gravely Sand	101R512 grayish brown, moist	union, impact artifact, rounded	basalt + m. pebbles, mod. figs	figs	(41.4-41.9) Sand, backfill;	union, moist; uniform, some	coarser basalt sand, 101R512	dark grayish brown, occasional	basalt pebbles, + figs						
4) 41.4-41.9	41.4-41.9	41.4-41.9	41.4-41.9	41.4-41.9	41.4-41.9	41.4-41.9	41.4-41.9	41.4-41.9	41.4-41.9	41.4-41.9	41.4-41.9	41.4-41.9	41.4-41.9	41.4-41.9	41.4-41.9	41.4-41.9	41.4-41.9
5) 41.5-48.5	41.5-48.5	41.5-48.5	41.5-48.5	41.5-48.5	41.5-48.5	41.5-48.5	41.5-48.5	41.5-48.5	41.5-48.5	41.5-48.5	41.5-48.5	41.5-48.5	41.5-48.5	41.5-48.5	41.5-48.5	41.5-48.5	41.5-48.5

7) 57-58

57-58.5 1 Sand
f-m sand, uniform, dry
basal light gray, 1042 1/2
light gray, mod to strong
fz3
57.5-58.1 Sand; very fine
fine to med sand, clay
basal light to full spatic
mod rxn; 1042 1/2 light
gray

8) 58.3-59.3

58.3-58.8 1 Laminated
silt and f-m sand
slightly moist, 1042 1/2
grayish brown; some
spin as above; mod f33

58.8-59.3

(58.8-59.3) Uniformly
Sands at bottom of core taken
Laminated silt and fine sands
in contact w/ coarse sands
mod f3 at base; 1042 1/2 grayish
brown; slightly moist

9) 60.1-62.1

60.1-60.6 1 Sand, very
dry; 1042 1/2 light gray,
mostly mod sand, basal
light to grayish, uniform,
some fine silt; mod f33
100-100% 100%

60.6-61.1 Uniform med sand
dry; 1042 1/2 light gray; some
spin as above; mod rxn
100-100% 100%

10) 72-73

72-72.5 Sand: med-fine
gray; 1042 1/2 light gray
uniform; some reaction
basal sand, mod rxn
very dry


72.5-73 Sand, as above;
uniform; mod f33
very dry; 100-100%

13)	86.1-87.1	(86.1-86.6) Sand; podom. med. grain w/ some coarse basalt; increasing downward. Transition to higher basalt 73-100%, 60% gte fill sp.; some grain oxidation; uny. fine; slight bedding observed; mod-strong rxn; 104R 5/2 grayish brown.
		(86.6-87.1) silt. and on top of med. fine sand; sharp contact silt. thin; thick; sand 40% basalt 60% gte fill sp.; 104R 4/2 light brownish gray; mod-strong rxn.
14)	99-100	(99-99.5) fin. med. sand mod-strong rxn; laminated; 104R 1/2 11 brownish gray 20% mic. (99.5-100) Sand. F. med. sand; some lamination; uniform. dry; 100% B, 60% gte fill. sand; 104R 5/2 mod-strong

11)	77-78	(77-77.5) Sand Some silt unmixed in mid of sample; podom. med-f. in grain; v. dry; unconsolidated mod rxn; med-sand mainly basalt; 104R 1/2 light gray 77.5-78
		(77.5-78.5) Sand - some silt Predominantly med sand w/ some silt lamina; dry; 104R 1/2 11 brownish gray; 70-30% B, 70-80% gte fill mod. rxn. 77.5-78.5 (80.9-81.4) Sand mainly fine sand, mod consisting primarily of basalt, 70% gte fill 30% basalt - dry 104R 1/2 light gray; mod-strong rxn.
12)	80.9-81.9	(81.4-81.9) same as above mod rxn

year 100.36 + 2 m. Sample Sand-in contact
Sample W 1042 4/3 dark brown silt,
moist, high fissility; strong
old corals. Contact 100.42

(15) 100.3-101.3
 (100.3-100.8) Deep contact of stuff
 100.3 laminated with 100.4-101.3
 from grading to fine sand,
 med-stony rxn.

100.8  101.3

(100.8-101.3) laminated silt
f. sand, v.f. sandy, p. ill silt
ply nt of concretions;
shaly rxn; 10 yr 5/3 brown


10) 103-104 - (103-103.5)
 Silt on top of compact
 silt. 1042.5/34 mm
 Silt is laminated
 Silt consists of f-m
 sand, mod. string rxn

(103.5-104) Massm 517
Lampit 1045/3 brown
Shing 1045
1045

4-201-5-107 (H) 5th
107/108 (D) 5th
w/ sparse very fine sand
107/108 1/3 pale brown;
uniform strong ex.

(108.4 = 108.4) 5.14 massive
0.15 5.13 brach., im. born
Spring


10-113.5-114.5
 (113.5-114)
 Sp. in contact w/
 pink at 113.9"
 some vegetation
 bushes
 sparse vegetation
 → Cavity is matted
 compact, very strong on
 lower



(117-114-5) Mottled color of
 coarse basalt sand.
 V. strong red to black
 7.5 g 1/2 pint dr. gray

APPENDIX C
GEOPHYSICAL LOGS

This page intentionally left blank.



Pacific Northwest Geophysics

4200 West 19th Ave
Kennewick, WA 99338
(509) 735-3963

"No Job Is Too Large or Too Small"

September 17, 2002

Mr. Kent Reynolds
Duratek Federal Services, Inc.
345 Hills Street
Richland, WA 99352

Dear Mr. Reynolds,

Re: SUBCONTRACT NO. A00536, Task Order 18 Mod 2
TX-105 Tank Farm Borehole (C3830) Survey Data Processing

Enclosed are the deliverables for the Task Order 18 to subcontract A000536. The deliverables are HPGe spectral gamma and Neutron Moisture survey results for C3830-TX-105 and include:


- Moisture calculation from MathCad.
 - MathCad results identify: borehole ID, calibration date, coefficients, and casing correction. No density correction was applied.
 - Casing correction factor (multiplier) is 1.339.
 - Calibrations coefficients are $\%vf = 0.00004354CR^{2.222}$ (6-inch calibration model)
 - MathCad output file "Moist.dat" is ASCII. Tabular columns are: depth, moisture, raw count rate, and count rate uncertainty (1 sigma, percent).
- Radionuclide concentration from LgCalc.
 - All gamma photo peaks above MDL were identified to assure all radionuclides are included in the analysis results. Photo peak uncertainties less than 30% are above MDL levels. Radionuclide identification phase is in sub-directories "-RadID".
 - Casing correction information is shown on the Borehole Survey Log Header.
 - Calibration coefficients are: $\epsilon(E) = 1/(11.19E^{0.1068})$ as per ref. RLSG07000S01.0 (calib. date Oct. 29, 2001; report date Jun. 3, 2002)
 - Minimum Detection Levels are listed in the Log Analysis Summary Report.
- Final survey results in Microsoft Word ".doc" format. The results file contains:
 - Borehole Survey Log Header (Moisture & Gamma surveys merged as one form)
 - Log survey results plot. One page containing both Moisture and Gamma results.
 - Log Analysis Summary Report (Moisture & Gamma merged)

Thank You,

Randall Price

Moisture Calculation (Casing Corrected & NO Density Correction)

A := READPRN("0gross2.dat") d := A<0> cr := A<1> n1 := last(d) i := 0..n1 Hole ID: **C3830 TX-105**



Casing Attenuation (beyond calibration model) : $t := .590 + \frac{0}{2}$ Thickness (inches) t = 0.59
 $attn := 1.311 - .9560 \cdot t$ $attn = 0.747$ $f := \frac{1}{attn}$ f = 1.339 Casing Correction Factor


a6 := .00004354 $\alpha_6 := 2.222$
a8 := .00002198 $\alpha_8 := 2.470$
ax := .00001038 $\alpha_x := 2.762$

Calibration Coefficients: RLSM00.0 Jan 29, 2002

ax coefficients hole size = 13.375"

$crcor_i := cr_i \cdot f$ Casing Correction

$moist_i := a6 \cdot (crcor_i)^{\alpha_6}$ Compute moisture
Hole Size: 6.56 in (OD)



time := 15 Count times secs. $\sigma_i := \text{if}(cr_i > 0, \frac{100}{\sqrt{cr_i \cdot \text{time}}}, 0)$ Uncertainty (% , 1 sigma)

out<0> := d - $\frac{0}{12}$ out<1> := moist out<2> := cr out<3> := σ

WRITEPRN("moist.dat") := out


Moisture (% volume fraction)
Depth correction may be applied.

RLS Moisture & Spectral Gamma

Duratek Federal Services, NW Operations

Project: TX Drilling
Borehole: C3830

Log Date : September 2002
Depth Datum: Ground Level




RLS Moisture & Spectral Gamma

Duratek Federal Services, NW Operations

Project: TX Drilling
Borehole: C3830

Log Date : September 2002
Depth Datum: Ground Level



Borehole Survey Log Header

Duratek Federal Services, Inc.

Project: 241-TX-105 Drilling

Borehole: C3830

Log Types: HPGe Spectral-Gamma & Neutron-Moisture

Borehole Information

Well ID	C3830	Water Depth	None	ft	Total Depth	115	ft
Elevation Reference		Elevation	n/a	ft			
Depth Reference	Ground Level	Casing Stickup	4.75	ft			
Casing Diameter	5.81 in I.D.	Depth Interval	0 to 116.75	ft	Thickness	0.59	in
Casing Diameter		Depth Interval		ft	Thickness		in

Logging Information

Log Type	Neutron-Moisture Gauge	HPGe Spectral-Gamma
Logging Unit	RLS-1	RLS-1
Logging Engineer	J. Meisner	J. Meisner
Instrument ID	RLSM00.0	RLSG07000S01.0
Instrument Calibration Date	Jan. 29, 2002	Oct. 29, 2001
Survey Date	Sept. 9, 2002	Sept. 9-12, 2002
Depth Interval / Prefix	0 to 80 ft MC05	0 to 9.5 ft A734
	68 to 117.5 ft MC06	7 to 52 ft A735
		49 to 82 ft A736
		79 to 116.4 ft A737
		103.5 to 116 ft Repeat

Analysis Information

Company	Pacific Northwest Geophysics
Analyst	Randall Price
Date	September 16, 2002

Notes: The repeatability (precision) of the Moisture and Gamma surveys is good. No Co-60 was detected in the survey. U-238 was detected from 49 to 69 feet at concentrations less than the MDL of 10 pCi/g. Moisture for 7.0-inch O.D. borehole was computed using the 6.56-inch O.D. calibration model coefficients.

Log Analysis Summary Report

Duratek Federal Services, Inc.

Project: 241-TX-105 Drilling Well ID: C3830
 Log Type: Neutron-Moisture & HPGe Spectral Gamma Log Dates: Sept. 12, 2002

General Notes:

The log response transitions at the survey top (0 ft) and bottom (115 feet and below) are the result of changes in borehole conditions (i.e. air to surface soils and at bottom from drill stem into drive shoe and into open hole).

The moisture survey shows that the formation moisture content gradually increases from about 5 vf% (volume fraction percent) near the surface to 15 vf% at the bottom of the hole. Decreased moisture content down to 5 vf% and lower concentrations of natural thorium and uranium were encountered between 89 and 93 feet, indicating a change in sediments. The moisture survey is appropriate for identifying changes in the relative moisture content.

The gross gamma increase below 52 feet reflects the transition from backfill material around the tanks into undisturbed sediments below the tanks.

Environmental Corrections: The casing thickness correction (as shown on the Borehole Survey Log Header) was applied to the detector responses before computing the apparent moisture content and radionuclide concentration. No formation density correction was applied since it is assumed to be similar to calibration model densities (approx. 1.76 g/cc). No casing correction was applied to the Total Gamma due to Compton down-scatter interference.

Depth Reference: Zero depth of log survey is at ground level. An error of +0.25 ft in the moisture survey depth resulted from difference in ground surface reference (Driller was using the top of the floor plate [3-inch thick] instead of the plate bottom).

System Performance Verification: The gamma survey pre- and post-log verification was performed using "Coleman #1" mantles. The FWHM (full width at half maximum) resolution for the 583 keV gamma ray photo peak (^{232}Th) were all less than the maximum FWHM resolution of 3.15 keV for probe RLSG07000S01.0 except for the post survey spectra of data set A736 at FWHM=3.25 keV. The overlap sections between survey A736 and the neighboring surveys are excellent and concentrations of the natural radionuclides are within normal ranges. Spectra file A7371026 at 92 feet had broadening of the photo peaks that required manual processing. The logging operator indicated that amplifier gain changes had occurred. The calibration is not compromised and the HPGe surveys are valid.

The moisture survey pre- and post-log verification measurements (722 and 700 c/s respectively) were within the range of previous system performance checks.

Repeat Interval: The repeat intervals have excellent agreement with the main log. (Moisture repeat is 68-80 ft.) (Gamma repeat is 103.5-116 ft.)

Radionuclides:

- Cs-137 is present at the surface (0 to 11 feet) at a concentration up to 7.5 pCi/g at 1 ft.
- Co-60 was not detected in the survey.
- U-238 was detected at concentrations less than the MDL level of 10 pCi/g.

	Co-60	Cs-137	U-238
max. Concentration	None	7.5 pCi/g @ 1 ft	< MDL
max. Depth at MDL	n/a	11 ft	n/a
MDL	0.1 pCi/g	0.1 pCi/g	10 pCi/g


Spectral Gamma Ray and Moisture Log Survey

Duratek Federal Services, Inc.

Borehole: C3830


Project: Tank Farm Drilling - TX-105

Log Date: September 2002





Prepared by: Pacific Northwest Geophysics

BOREHOLE SURVEY DATA SHEET											
Project:	TX Farm Drilling			Well Name:			Well ID:	C3830			
Date:	09/12/02			Location:	TX Tank Farm, South of Tank TX-105						
Notes:											
5.0-4.75=.25 meas. Pt in hole w/ top of cablehead											
While moving on bottom, zeroed depth on accident. Used backup readout and bottom tag to reset.											
Tag bottom at 116.4+1.0+117.4											
BOREHOLE LOGGING INFORMATION											
Logger:	JAMES E. MEISNER			Logging Unit Configuration:	RLS1						
Depth Datum Reference:	Ground Surface			Instrument Calibration Configuration:	RLSG0700S00.0						
Total Well Depth (ft):	116.75	Source:	Driller	Water Level (ft):	Dry	Source:	Driller				
Source for Casing Parameters:	Measured with Calipers										
Casing Diameter (in.):	0.60	Wall Thickness (in.):	0.60	Type of Metal:	CARBON STEEL	Total Depth (ft):	116.75	Stickup (ft):	4.75		
Diameter (in.):	None	Wall Thickness (in.):	NA	Type of Metal:		Total Depth (ft):	NA	Stickup (ft):	NA		
Diameter (in.):	None	Wall Thickness (in.):	NA	Type of Metal:		Total Depth (ft):	NA	Stickup (ft):	NA		
Diameter (in.):	None	Wall Thickness (in.):	NA	Type of Metal:		Total Depth (ft):	NA	Stickup (ft):	NA		
File Name Prefix:	A737	Field Disk/Part:	A737	Return Error (in.):	1.000	High/Low at (ft):	LOW	Field Verifier ID:	COLEMAN 1		
Pre Log Verification:	Gross c/s:	2186.00	Background c/s:	1499.00	Th 583 keV photo peak FWHM:						
Post Log Verification:	Gross c/s:	2156.00	Background c/s:	1538.00	Th 583 keV photo peak FWHM:						
Log Interval:	Fix Speed (fpm):	na	Move-Stop-Acquire(s) (LT/RT):	150rt	LOGGING OPERATIONS WERE PERFORMED AND EQUIPMENT CLEANED AS PER PROCEDURES, 17.0 GEOPHYSICAL LOGGING, DURATEK FEDERAL SERVICES, INC.						
Depth Range:	Start (ft):	79.00	Stop (ft):	116.50						Incr (ft):	0.50
Log Interval:	Fix Speed (fpm):	na	Move-Stop-Acquire(s) (LT/RT):	150rt							
Depth Range:	Start (ft):	116.00	Stop (ft):	103.50						Incr (ft):	0.50
Log Interval:	Fix Speed (fpm):		Move-Stop-Acquire(s) (LT/RT):		Prepared by (print):						
Depth Range:	Start (ft):		Stop (ft):		Incr (ft):		JAMES E. MEISNER				
Log Interval:	Fix Speed (fpm):		Move-Stop-Acquire(s) (LT/RT):		Signature:						
Depth Range:	Start (ft):		Stop (ft):		Incr (ft):		Date:				
							9/12/02				

BOREHOLE SURVEY DATA SHEET											
Project:	TX Farm Drilling			Well Name:				Well ID:	C3830		
Date:	09/11/02			Location:	TX Tank Farm, South of Tank TX-105						
Notes:											
5.0-4.75=.25 meas. Pt in hole w/ top of cablehead											
BOREHOLE LOGGING INFORMATION											
Logger:	JAMES E. MEISNER			Logging Unit Configuration:	RLS1						
Depth Datum Reference:	Ground Surface			Instrument Calibration Configuration:	RLSG0700S00.0						
Total Well Depth (ft):	116.75	Source:	Driller	Water Level (ft):	Dry	Source:	Driller				
Source for Casing Parameters:	Measured with Calipers										
Casing Diameter (in.):	O.D = 7.0, I.D. = 5.81	Wall Thickness (in.):	0.60	Type of Metal:	CARBON STEEL	Total Depth (ft):	116.75	Stickup (ft):	4.75		
Diameter (in.):	None	Wall Thickness (in.):	NA	Type of Metal:		Total Depth (ft):	NA	Stickup (ft):	NA		
Diameter (in.):	None	Wall Thickness (in.):	NA	Type of Metal:		Total Depth (ft):	NA	Stickup (ft):	NA		
Diameter (in.):	None	Wall Thickness (in.):	NA	Type of Metal:		Total Depth (ft):	NA	Stickup (ft):	NA		
File Name Prefix:	A736	Field Disk/Part:	A736	Return Error (in.):	0.000	High/Low at (ft):	LOW	Field Verifier ID:	COLEMAN 1		
Pre Log Verification:	Gross c/s:	1960.00	Background c/s:	1287.00	Th 583 keV photo peak FWHM: na						
Post Log Verification:	Gross c/s:	2118.00	Background c/s:	1490.00	Th 583 keV photo peak FWHM:						
Log Interval:	Fix Speed (fpm):	na	Move-Stop-Acquire(s {LT/RT}):	150rt	LOGGING OPERATIONS WERE PERFORMED AND EQUIPMENT CLEANED AS PER PROCEDURES, 17.0 GEOPHYSICAL LOGGING, DURATEK FEDERAL SERVICES, INC.						
Depth Range:	Start (ft):	49.00	Stop (ft):	82.00						Incr (ft):	0.50
Log Interval:	Fix Speed (fpm):		Move-Stop-Acquire(s {LT/RT}):								
Depth Range:	Start (ft):		Stop (ft):							Incr (ft):	
Log Interval:	Fix Speed (fpm):		Move-Stop-Acquire(s {LT/RT}):		Prepared by (print): JAMES E. MEISNER						
Depth Range:	Start (ft):		Stop (ft):		Incr (ft):	Signature: 					
Log Interval:	Fix Speed (fpm):		Move-Stop-Acquire(s {LT/RT}):		Date: 9/11/02						
Depth Range:	Start (ft):		Stop (ft):		Incr (ft):						

BOREHOLE SURVEY DATA SHEET											
Project:	TX Farm Drilling		Well Name:			Well ID:	C3830				
Date:	09/10/02		Location:	TX Tank Farm, South of Tank TX-105							
Notes:											
5.0-4.75=.25 meas. Pt in hole w/ top of cablehead											
BOREHOLE LOGGING INFORMATION											
Logger:	JAMES E. MEISNER			Logging Unit Configuration:	RLS1						
Depth Datum Reference:	Ground Surface			Instrument Calibration Configuration:	RLSG0700S00.0						
Total Well Depth (ft):	116.75	Source:	Driller	Water Level (ft):	Dry	Source:	Driller				
Source for Casing Parameters:	Measured with Calipers										
Casing Diameter (in.):	O.D = 7.0, I.D. = 5.81	Wall Thickness (in.):	0.60	Type of Metal:	CARBON STEEL	Total Depth (ft):	116.75	Stickup (ft):	4.75		
Diameter (in.):	None	Wall Thickness (in.):	NA	Type of Metal:		Total Depth (ft):	NA	Stickup (ft):	NA		
Diameter (in.):	None	Wall Thickness (in.):	NA	Type of Metal:		Total Depth (ft):	NA	Stickup (ft):	NA		
Diameter (in.):	None	Wall Thickness (in.):	NA	Type of Metal:		Total Depth (ft):	NA	Stickup (ft):	NA		
File Name Prefix:	A735	Field Disk/Part:	A735	Return Error (in.):	0.000	High/Low at (ft):	LOW	Field Verifier ID:	COLEMAN 1		
Pre Log Verification:	Gross c/s:	2087.00	Background c/s:	1420.00	Th 583 keV photo peak FWHM:	na					
Post Log Verification:	Gross c/s:	2046.00	Background c/s:	1363.00	Th 583 keV photo peak FWHM:						
Log Interval:	Fix Speed (fpm):	na	Move-Stop-Acquire(s) (LT/RT):	150rt	LOGGING OPERATIONS WERE PERFORMED AND EQUIPMENT CLEANED AS PER PROCEDURES, 17.0 GEOPHYSICAL LOGGING, DURATEK FEDERAL SERVICES, INC.						
Depth Range	Start (ft):	7.00	Stop (ft):	52.00						Incr (ft):	0.50
Log Interval:	Fix Speed (fpm):		Move-Stop-Acquire(s) (LT/RT):								
Depth Range	Start (ft):		Stop (ft):		Incr (ft):		Prepared by (print):				
Log Interval:	Fix Speed (fpm):		Move-Stop-Acquire(s) (LT/RT):		JAMES E. MEISNER						
Depth Range	Start (ft):		Stop (ft):		Incr (ft):		Signature:				
Log Interval:	Fix Speed (fpm):		Move-Stop-Acquire(s) (LT/RT):		Date:						
Depth Range	Start (ft):		Stop (ft):		Incr (ft):		9/10/02				

BOREHOLE SURVEY DATA SHEET										
Project:	TX Farm Drilling		Well Name:			Well ID:	C3831			
Date:	09/09/02		Location:	TX Tank Farm, Tx105						
Notes:										
4.5 to TOC this Should have been 4.75 including the plate										
4.88-4.5=0.38 to top of CH(should have been 4.88-4.75=.13)										
Ground surface is defined by driller as top of floor plate and is 3" thick										
TD-117.20(inc. 3" correction)										
analyzed field log was corrected for this .25' error (3")										
BOREHOLE LOGGING INFORMATION										
Logger:	JAMES E. MEISNER			Logging Unit Configuration:	RLS1					
Depth Datum Reference:	Ground Surface			Instrument Calibration Configuration:	RLSM0.00 MOISTURE WA					
Total Well Depth (ft):	116.75		Source:	Driller	Water Level (ft):	Dry		Source:	Driller	
Source for Casing Parameters:	Measured with Calipers									
Casing Diameter (in.):	O.D = 7.0, I.D. = 5.81		Wall Thickness (in.):	0.59		Type of Metal:	CARBON STEEL		Total Depth (ft):	Stickup (ft):
									116.75	4.50
Diameter (in.):	None		Wall Thickness (in.):	NA		Type of Metal:			Total Depth (ft):	Stickup (ft):
									NA	NA
Diameter (in.):	None		Wall Thickness (in.):	NA		Type of Metal:			Total Depth (ft):	Stickup (ft):
									NA	NA
Diameter (in.):	None		Wall Thickness (in.):	NA		Type of Metal:			Total Depth (ft):	Stickup (ft):
									NA	NA
File Name Prefix:	MC05		Field Disk/Part:	MC05		Return Error (in.):	0.000		High/Low at (ft):	Field Verifier ID:
									LOW	COLEMAN 1
Pre Log Verification:	Gross c/s:		722.00		Background .c/s:	na		Th 583 keV photo peak FWHM:		
								na		
Post Log Verification:	Gross c/s:		700.00		Background .c/s:			Th 583 keV photo peak FWHM:		
Log Interval:	Fix Speed (fpm):		0.90		Move-Stop-Acquire(s {LT/RT}):		na			
Depth Range:	Start (ft):		0.00		Stop (ft):	80.00		Incr (ft): 0.25		
Log Interval:	Fix Speed (fpm):				Move-Stop-Acquire(s {LT/RT}):					
Depth Range:	Start (ft):		68.00		Stop (ft):	117.50		Incr (ft): 0.25		
Log Interval:	Fix Speed (fpm):				Move-Stop-Acquire(s {LT/RT}):					
Depth Range:	Start (ft):				Stop (ft):			Incr (ft):		
Log Interval:	Fix Speed (fpm):				Move-Stop-Acquire(s {LT/RT}):					
Depth Range:	Start (ft):		114.00		Stop (ft):	108.00		Incr (ft): 0.50		
LOGGING OPERATIONS WERE PERFORMED AND EQUIPMENT CLEANED AS PER PROCEDURES, 17.0 GEOPHYSICAL LOGGING, DURATEK FEDERAL SERVICES, INC.								Prepared by (print):		
								JAMES E. MEISNER		
								Signature:		
										
								Date:		
								9/9/02		

BOREHOLE SURVEY DATA SHEET												
Project:	TX Farm Drilling		Well Name:		Well ID:	C3830						
Date:	09/09/02		Location:	TX Tank Farm, South of Tank TX-105								
Notes:												
5.0-4.75=.25 meas. Pt in hole w/ top of cablehead												
BOREHOLE LOGGING INFORMATION												
Logger:	JAMES E. MEISNER			Logging Unit Configuration:	RLS1							
Depth Datum Reference:	Ground Surface			Instrument Calibration Configuration:	RLSG0700S00.0							
Total Well Depth (ft):	116.75	Source:	Driller	Water Level (ft):	Dry	Source:	Driller					
Source for Casing Parameters:	Measured with Calipers											
Casing Diameter (in.):	O.D = 7.0, I.D. = 5.81		Wall Thickness (in.):	0.60		Type of Metal:	CARBON STEEL		Total Depth (ft):	116.75		
									Stickup (ft):	4.75		
Diameter (in.):	None		Wall Thickness (in.):	NA		Type of Metal:			Total Depth (ft):	NA		
									Stickup (ft):	NA		
Diameter (in.):	None		Wall Thickness (in.):	NA		Type of Metal:			Total Depth (ft):	NA		
									Stickup (ft):	NA		
Diameter (in.):	None		Wall Thickness (in.):	NA		Type of Metal:			Total Depth (ft):	NA		
									Stickup (ft):	NA		
File Name Prefix:	A734		Field Disk/Part:	A734		Return Error (in.):	0.000		High/Low at (ft):	LOW		
									Field Verifier ID:	COLEMAN 1		
Pre Log Verification:	Gross c/s:		1825.00		Background c/s:	1254.00		Th 583 keV photo peak FWHM:		na		
Post Log Verification:	Gross c/s:				Background c/s:			Th 583 keV photo peak FWHM:				
Log Interval:	Fix Speed (fpm):	na		Move-Stop-Acquire(s {LT/RT}):	150rt		LOGGING OPERATIONS WERE PERFORMED AND EQUIPMENT CLEANED AS PER PROCEDURES, 17.0 GEOPHYSICAL LOGGING, DURATEK FEDERAL SERVICES, INC.					
Depth Range	Start (ft):	0.00		Stop (ft):	9.50					Incr (ft):	0.50	
Log Interval:	Fix Speed (fpm):			Move-Stop-Acquire(s {LT/RT}):								
Depth Range	Start (ft):			Stop (ft):						Incr (ft):		
Log Interval:	Fix Speed (fpm):			Move-Stop-Acquire(s {LT/RT}):			Prepared by (print):					
							JAMES E. MEISNER					
Depth Range	Start (ft):			Stop (ft):			Incr (ft):	Signature:				
												
Log Interval:	Fix Speed (fpm):			Move-Stop-Acquire(s {LT/RT}):			Date:					
									9/9/02			

APPENDIX D
CHAIN OF CUSTODY/SAMPLE ANALYSIS REQUESTS

This page intentionally left blank.

6268 CLEANING FACILITY
EQUIPMENT CHECK IN FORM

QUANTITY	ITEM	CUSTOMER	PROJECT
21	Complete Split Spoons	S. Harold	TX-Borehole

CUSTOMER INFORMATION:

The equipment that is being submitted for cleaning, to the best of my knowledge, meets the following criteria for acceptance into the 6268 cleaning facility.

- ☐ Is new equipment that has never been utilized for field sampling.
- ☒ The equipment has been utilized for field sampling inside of a radiologically controlled area, but has been "free released" by field radiological control technicians.
If so, survey number: _____ RCT signature: _____ Date: _____
- ☐ The equipment has been utilized for field sampling, but was not utilized a radiologically controlled area.

Customer: _____ Print Name: _____ Date: _____

RECEIPT INFORMATION

Receiver: K.J. - Young Print Name: K.J. - Young Date: 8/20/02

Duratek Federal Services		CHAIN OF CUSTODY/SAMPLE ANALYSIS REQUEST				C.O.C.# 102292	
Collector YOUNG, K.J.		Contact/Requestor SYDNOR, HAROLD		Tel. No. 372-9414 MSIN H0-22		Page 1 of 1 FAX	
SAF Number S02-083		Sample Origin T-Farm		Purchase Order/Charge Code			
Project Title TX Borehole (3830)		Logbook # DFSNW-SAWS-HSS		Ice Chest # SAWS-003		Temp.	
Shipped To (Lab) AG&G		Method of Shipment Gov Truck		Bill of Lading/Air Bill No.			
Protocol RCRA		Data Turnaround PER CONTRACT		Offsite Property No.			
Sample No.	Lab. ID	*	Date	Time	No/Type Container	Sample Analysis	Perservative
S02083-01		W	8/26/02	1030	(1) 125 P	IC Anions (EPA 300.0)	Cool to 4°C
S02083-01		W			(1) 500 P	ICP Metals - 6010A (TAL)	HNO3
S02083-01		W			(1) 1000 aG	Semi-VOA (8270)	Cool 4 deg. C
S02083-01		W			(1) 250 aGs	TOC (9060)	H2SO4/Cool to 4°C
S02083-01		W			(1) 1000 P	Total Alpha / Beta (Lab Specific), GEA	HNO3
S02083-01		W			(1) 1000 P	Tritium, (H3)	Cool to 4°C
S02083-01		W			(3) 40 aGs	VOA	HCL

POSSIBLE SAMPLE HAZARDS/REMARKS List all known wastes.				SPECIAL INSTRUCTIONS				Hold Time			
Relinquished By K.J. Young for				MSDS Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>							
Print		Sign		Date/Time		Received By		Print		Sign	
				8/27/02 1530		M. Valente		M. Valente		8/27/02 1530	
Relinquished By				Date/Time		Received By		Date/Time		Date/Time	
Relinquished By				Date/Time		Received By		Date/Time		Date/Time	
Relinquished By				Date/Time		Received By		Date/Time		Date/Time	
FINAL SAMPLE DISPOSITION				Disposal Method e.g. Return to customer, per lab procedure, used in process.				Disposed By			
								Date/Time			
								DI JS-010			

Duratek Federal Services		CHAIN OF CUSTODY/SAMPLE ANALYSIS REQUEST				C.O.C.# 10-73 Page 1 of 1			
Collector	K.J. Young	Contact/Requestor	Sydnor, Harold		Tel. No.	372-9414	MSIN	HO-22	FAX
SAF Number	502-083	Sample Origin	T-Farm		Purchase Order/Charge Code				
Project Title	TX Bone Hole (C38301)	Logbook #	DFSNW-SAWS-HSS		Ice Chest #	1 Drum			
Shipped To (Lab)	AG 26	Method of Shipment	Gov Truck		Bill of Lading/Air Bill No.				
Protocol	RCRA	Data Turnaround	Per contract		Offsite Property No.				
Sample No.	Lab. ID	Date	Time	No/Type Container	Sample Analysis	Actual	Depth	Preservative	
502083-02		8/10/02	1120	(1) S/S	Per contract	14.96	→ 16.31 ft	4°C	
502083-03		8/10/02	1448	(1) S/S	"	27.91	→ 29.25 ft	4°C	
				()					
				()					
				()					
				()					
				()					
				()					
				()					
				()					
				()					
				()					
POSSIBLE SAMPLE HAZARDS/REMARKS					MSDS	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>	SPECIAL INSTRUCTIONS		
List all known wastes.							Hold Time		
Relinquished By	Print	Sign	Date/Time	Received By	Print	Sign	Date/Time	Matrix *	
K.J. Young	per fax		8/10/02 1550	Henry Leary	Gov		8/10/02 1550	S = Soil DS = Drum Solids SE = Sediment DL = Drum Liquids SO = Solid T = Tissue SL = Sludge W1 = Wipe W = Water L = Liquid O = Oil V = Vegetation A = Air X = Other	
Relinquished By			Date/Time	Received By			Date/Time		
			Date/Time	Received By			Date/Time		
Relinquished By			Date/Time	Received By			Date/Time		
			Date/Time	Received By			Date/Time		
FINAL SAMPLE DISPOSITION					Disposal Method e.g. Return to customer, per lab procedure, used in process.				
					Disposed By				
					Date/Time				

DFNW-SS-010

Duratek Federal Services		CHAIN OF CUSTODY/SAMPLE ANALYSIS REQUEST				C.O.C.# 102-14	
Collector K.J. - Youngs		Contact/Requestor	Sample Origin	Tel. No.	MSIN	FAX	Page 1 of 1
SAF Number 502-083		SYDOR, HAROLD		372-9414		HO-22	
Project Title TX Bore Hole (C38301)		T-Farm		Purchase Order/Charge Code			
Shipped To (Lab) AG & G		Logbook # DFSNW-SAWS-HSS		Ice Chest # Drum # 1		Temp.	
Protocol RCRX		Method of Shipment Gov Truck		Bill of Lading/Air Bill No.			
Sample No.		Lab. ID	Date	Time	No/Type Container	Sample Analysis	Perservative
502083-04			8/21/02	0940	(1) S/S	Per contract	40.93 - 42.49
502083-05			8/21/02	1250	(1) S/S	"	46.20 - 47.50 - 67
					()		46.05 - 47.50
					()		
					()		
					()		
					()		
					()		
					()		
					()		
					()		
					()		
POSSIBLE SAMPLE HAZARDS/REMARKS		MSDS		Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>	SPECIAL INSTRUCTIONS		
List all known wastes.						Hold Time	
Relinquished By	Print	Sign	Date/Time	Received By	Print	Sign	Date/Time
K.J. - Youngs			8/21/02 1445	Jimmy McGore			8/21/02 1445
Relinquished By			Date/Time	Received By			Date/Time
			Date/Time	Received By			Date/Time
Relinquished By			Date/Time	Received By			Date/Time
			Date/Time	Received By			Date/Time
FINAL SAMPLE DISPOSITION		Disposal Method e.g. Return to customer, per lab procedure, used in process.		Disposed By		Date/Time	

DFNW-SS-010

Duratek Federal Services		CHAIN OF CUSTODY/SAMPLE ANALYSIS REQUEST				C.O.C # 10-295 Page 1 of 1	
Collector	K.J. Young	Contact/Requestor	Sycamore, Harlow	Tel. No.	372-9414	MSIN	HO-22
SAF Number	502-083	Sample Origin	T-Farm	Purchase Order/Charge Code			
Project Title	TX Bone Hole (C3830)	Logbook #	DFS NW-SAWS-HSS	Ice Chest #	Drum # 1 & 2	Temp.	
Shipped To (Lab)	AG & G	Method of Shipment	Gov Truck	Bill of Lading/Air Bill No.	N/A		
Protocol	RCRA	Data Turnaround	Per contract	Offsite Property No.	N/A		
Sample No.	Lab. ID	Date	Time	No/Type Container	Sample Analysis	Actual Depth	Perservative
502083-06		8/24/02	0818	(1) S/S	Per contract	47.50 to 49.00	4°C
502083-07		8/24/02	1142	(1) S/S	"	52.98 to 54.36	4°C
502083-08		8/24/02	1453	(1) S/S	"	56.99 to 58.37	4°C
				()			
				()			
				()			
				()			
				()			
				()			
				()			
				()			
				()			
POSSIBLE SAMPLE HAZARDS/REMARKS				MSDS	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>	SPECIAL INSTRUCTIONS	
List all known wastes.						Hold Time	
Relinquished By	Print	Sign	Date/Time	Received By	Print	Sign	Date/Time
K.J. Young			8/22/02 1600	Garry McGar			8/22/02 1600
Relinquished By			Date/Time	Received By			Date/Time
			Date/Time	Received By			Date/Time
Relinquished By			Date/Time	Received By			Date/Time
			Date/Time	Received By			Date/Time
FINAL SAMPLE DISPOSITION				Disposal Method e.g. Return to customer, per lab procedure, used in process.			
				Disposed By			
				Date/Time			
				DFNW-SS-010			

Duratek Federal Services		CHAIN OF CUSTODY/SAMPLE ANALYSIS REQUEST				C.O.C.# 102296 Page 1 of 1	
Collector	K.J. Young	Contact/Requestor	Sylvan, Harold	Tel. No.	372-9414	MSIN	HO-22
SAF Number	502-083	Sample Origin	T-Farm	Purchase Order/Charge Code			FAX
Project Title	TX Bone Hole (13830)	Logbook #	DFS NW-SAWS-HSS	Ice Chest #	Drum #1	Temp.	
Shipped To (Lab)	AG&G	Method of Shipment	Gov Truck	Bill of Lading/Air Bill No.			
Protocol	RCRA	Data Turnaround	Per contract	Offsite Property No.			
Sample No.	Lab. ID	Date	Time	No/Type Container	Sample Analysis	Perservative	
502083-09		8/23/02	1400	(1) SLS	Per contract	Actual Depth	40C
				()			
				()			
				()			
				()			
				()			
				()			
				()			
				()			
				()			
				()			
				()			
				()			
POSSIBLE SAMPLE HAZARDS/REMARKS List all known wastes.				MSDS	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>	SPECIAL INSTRUCTIONS	
Relinquished By	Print	Sign	Date/Time	Received By	Print	Sign	Date/Time
K.J. Young			8/23/02 1400	Michelle Valente			8/23/02 1400
Relinquished By			Date/Time	Received By			Date/Time
Relinquished By			Date/Time	Received By			Date/Time
Relinquished By			Date/Time	Received By			Date/Time
FINAL SAMPLE DISPOSITION				Disposal Method e.g. Return to customer, per lab procedure, used in process.		Disposed By	
						Date/Time	
						Date/Time	

DFNW-SS-010

[illegible]

Duratek FEDERAL SERVICES		CHAIN OF CUSTODY/SAMPLE ANALYSIS REQUEST				C.O.C # 102298					
Collector	K.J. Youngs	Contact/Requestor	SYDOR, HAROLD		Tel. No.	372-9414	MSIN	HO-22	FAX		
SAF Number	S02-083	Sample Origin	T-Farm		Purchase Order/Charge Code						
Project Title	TX Bore Hole (C3830)	Logbook #	DFS NW-SAWS-HSS		Ice Chest #	Dum #1 #2					
Shipped To (Lab)	AG & G	Method of Shipment	Gov Truck		Bill of Lading/Air Bill No.						
Protocol	RCRA	Data Turnaround	Per contract		Offsite Property No.						
Sample No.	Lab. ID	Date	Time	No/Type Container	Sample Analysis	Actual Depth ft	Perservative				
S02083-11		8/27/02	0810	(1) S/S	Per contract	71.95 - 73.30	40C				
S02083-12		8/27/02	1135	(1) S/S	"	76.98 - 78.35	40C				
				()							
				()							
				()							
				()							
				()							
				()							
				()							
				()							
				()							
				()							
				()							
POSSIBLE SAMPLE HAZARDS/REMARKS List all known wastes.				MSDS	Yes	No	SPECIAL INSTRUCTIONS				
Relinquished By	Print	Signature	Date/Time	Received By	Print	Signature	Date/Time	Matrix *			
K.J. Youngs		8/27/02	1530	M. Valente		8/27/02	1530	S	Soil	DS	Drum Solids
Relinquished By				Received By				SE	Sediment	DL	Drum Liquids
Relinquished By				Received By				SO	Solid	T	Tissue
Relinquished By				Received By				SL	Sludge	WI	Wipe
Relinquished By				Received By				W	Water	L	Liquid
Relinquished By				Received By				O	Oil	V	Vegetation
Relinquished By				Received By				A	Air	X	Other
FINAL SAMPLE DISPOSITION				Disposal Method e.g. Return to customer, per lab procedure, used in process.				Date/Time			
				Disposed By				Date/Time			

JW-SS-010

VIA

VALUEN
RBI SERVICES

CHAIN OF CUSTODY / SAMPLE ANALYSIS REQUEST

Page _____ of _____

Collector K.J. Young			Contact/Requestor Sydnor, Harold			Tel. No. 372-9414 MSIN HO-22 FAX		
SAF Number S02-083			Sample Origin T-Farm			Purchase Order/Charge Code		
Project Title TX Bore Hole (C3830)			Logbook # DFSNW-SAWS-HSS			Ice Chest # Drum #12 Temp.		
Shipped To (Lab) AG & G			Method of Shipment Gov Truck			Bill of Lading/Air Bill No.		
Protocol RCRA			Data Turnaround Per contract			Offsite Property No.		

Sample No.	Lab ID	Date	No/Type Container	Sample Analysis	Actual Depth	Perservative
S02083-13		8/28/02	(1) S/S	Per contract	80.91 -> 82.21	40°C
S02083-14		8/28/02	(1) S/S	" "	86.11 - 87.41	40°C
			()			
			()			
			()			
			()			
			()			
			()			
			()			
			()			
			()			
			()			
			()			
			()			
			()			
			()			
			()			
			()			

POSSIBLE SAMPLE HAZARDS/REMARKS		MSDS Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>		SPECIAL INSTRUCTIONS		Hold Time	
Relinquished By	Print	Received By	Sign	Print	Sign	Date/Time	Date/Time
K.J. Young	per fax	M. Valente	M. Valente			8/28/02	1530
Relinquished By		Received By				Date/Time	Date/Time
Relinquished By		Received By				Date/Time	Date/Time
Relinquished By		Received By				Date/Time	Date/Time

Matrix *	S	= Soil	SE	= Sediment	SO	= Solid	SL	= Sludge	W	= Water	O	= Oil	A	= Air	Matrix *	DS	= Drum Solids	DL	= Drum Liquids	T	= Tissue	WI	= Wipe	L	= Liquid	V	= Vegetation	X	= Other

FINAL SAMPLE DISPOSITION	Disposal Method e.g. Return to customer, per lab procedure, used in process.	Disposed By	Date/Time

DFNW-SS-010

[illegible]

[illegible]

[illegible]

APPENDIX E
FIELD DOCUMENTATION

This page intentionally left blank.



Duratek Federal Services, Inc.
Northwest Operations

TX Tank Farm Characterization Project Blow Count Form

PRELIMINARY DATA

Date: 08 20 02
Location: TX Tank Farm
Borehole Number: C3830

Operator: BSE
Personnel: K. OLSON
Rig Number: 106

Page 1 of 11
Hammer: ICE 40S

BOREHOLE SPECIFIC DATA

Starter Casing Size: 7 inch O.D. Constant: 3.35 ft/3.1 top of plate/plate .25 ft
Drive Casing Size/Type: 4.5 inch O.D. Starter Casing Depth: 0.0
Tip Size/Type: 7.5 X 17.75 inch Total Depth: 14.96
Joint Type: Welded N/A Conical: 4.75 inch I.D.
Threaded 4.5 Pinpile

DEPTH	BLOWS/FT	AVE. STROKE	DRIVING TIME	TIP DEPTH
0 1	3		08:20	
1 2	2			
2 3	2		N/A	N/A
3 4	2			
4 5	3			
5 6.19	3		08:42	6.19
6.19 7.19	8		09:40	
7.19 8.19	14			N/A
8.19 9.19	12		N/A	
9.19 10.19	10			
10.19 11.19	9		09:41	11.19
11.19 12.19	12		10:08	
12.19 13.19	10	N/A	N/A	N/A
13.19 14.19	8			
14.19 14.96	6		10:09	14.96
14.96 15.46	1	SD2083-02	10:57	N/A
15.46 15.96	1	N/A	N/A	

Prepared by: D.E. Skoglie Reviewed by: [Signature] 10-8-02



Duratek Federal Services, Inc.
Northwest Operations

TX Tank Farm Characterization Project Blow Count Form

PRELIMINARY DATA

Date: 08 20 02
Location: TX Tank Farm
Borehole Number: C3830

Operator: BSE
Personnel: K. OLSON
Rig Number: 106

Page 2 of 11
Hammer: ICE 40S

BOREHOLE SPECIFIC DATA

Starter Casing Size: 7 inch O.D. Constant: 3.35 ft/3.1 top of plate/plate .25 ft
Drive Casing Size/Type: 4.5 inch O.D. Starter Casing Depth: 14.96
Tip Size/Type: 7.5 X 17.75 inch Total Depth: 27.91
Joint Type: Welded N/A Conical: 4.75 inch I.D.
Threaded 4.5 Pinpile

DEPTH	BLOWS/FT	AVE. STROKE	DRIVING TIME	TIP DEPTH
15.96 16.31	1		10:58	14.96
14.96 15.96	4		12:50 - 12:51	
15.96 16.96	10		13:13	N/A
16.96 17.96	10		N/A	
17.96 18.96	10			
18.96 19.96	12			
19.96 20.94	13		13:14	20.94
20.94 21.94	14		13:35	N/A
21.94 22.94	14		N/A	
22.94 23.94	14	N/A		
23.94 24.94	14			
24.94 26.02	15		13:36	26.02
26.02 27.02	20		13:52	N/A
27.02 27.91	11		13:53	27.91
27.91 28.41	2	502083-03	N/A	N/A
28.41 28.91	2	N/A		

Prepared by: D.E. Skoglie Reviewed by: MLB 10-8-02



Duratek Federal Services, Inc.
Northwest Operations

TX Tank Farm Characterization Project Blow Count Form

PRELIMINARY DATA					
Date: <u>08 20-21 02</u>		Operator: <u>BSE</u>		Page <u>3</u> of <u>11</u>	
Location: <u>TX Tank Farm</u>		Personnel: <u>K. OLSON</u>			
Borehole Number: <u>C3830</u>		Rig Number: <u>106</u>		Hammer: ICE 40S	
BOREHOLE SPECIFIC DATA					
Starter Casing Size: <u>7 inch O.D.</u>		Constant: <u>3.35 ft/3.1 top of plate/plate .25 ft</u>			
Drive Casing Size/Type: <u>4.5 inch O.D.</u>		Starter Casing Depth: <u>27.91</u>			
Tip Size/Type: <u>7.5 X 17.75 inch</u>		Total Depth: <u>40.93</u>			
Joint Type: <u>Welded</u> <u>N/A</u>		Conical: <u>4.75 inch I.D.</u>			
		Threaded: <u>4.5 Pinpile</u>			
DEPTH	BLOWS/FT	AVE. STROKE	DRIVING TIME	TIP DEPTH	
28.91	29.25	1		14:29	
27.91	28.91	8		07:42	N/A
28.91	29.91	10		N/A	
29.91	30.95	10		07:43	30.95
30.95	31.95	10		08:04	
31.95	32.95	10			N/A
32.95	33.95	13		N/A	
33.95	34.95	15	N/A		
34.95	36.1	16		08:06	36.1
36.1	37.1	13		08:26	
37.1	38.1	15			N/A
38.1	39.1	14		N/A	
39.1	40.1	14			
40.1	40.93	10		08:27	40.93
40.93	41.43	1	502083-04	09:17	N/A
41.43	41.93	2	N/A		
Prepared by: <u>D.E. Skoglie</u> Reviewed by: <u>McLand</u> <u>10-8-02</u>					



Duratek Federal Services, Inc.
Northwest Operations

TX Tank Farm Characterization Project Blow Count Form

PRELIMINARY DATA

Date: 08 21-22 02
Location: TX Tank Farm
Borehole Number: C3830

Operator: BSE
Personnel: K. DISON
Rig Number: 106

Page 4 of 11
Hammer: ICE 40S

BOREHOLE SPECIFIC DATA

Starter Casing Size: 7 inch O.D.
Drive Casing Size/Type: 4.5 inch O.D.
Tip Size/Type: 7.5 X 17.75 inch
Joint Type: Welded N/A

Constant: 3.35 ft/3.1 top of plate/plate .25 ft
Starter Casing Depth: 40.93
Total Depth: 50.05
Conical: 4.75 inch I.D.
Threaded: 4.5 Pinpile

DEPTH	BLOWS/FT	AVE. STROKE	DRIVING TIME	TIP DEPTH
41.93 42.49	1		09:18	
40.93 41.93	6		10:42	N/A
41.93 42.93	9		N/A	
42.93 43.93	8	N/A	N/A	
43.93 44.93	9			
44.93 46.05	12		10:44	46.05
46.05 46.55	1	502083-05	12:29	
46.55 47.05	1		N/A	
47.05 47.5	1	N/A	12:30	
				N/A
47.5 48.0	1	502083-06	07:43	
48.0 48.5	2		N/A	
48.5 49.0	1		07:44	
46.05 47.05	7	N/A	08:50	
47.05 48.05	11		N/A	
48.05 49.05	13		N/A	
49.05 50.05	20			50.05

Prepared by: D.F. Skoglie

Reviewed by: MLB 10-08-02



Duratek Federal Services, Inc.
Northwest Operations

TX Tank Farm Characterization Project Blow Count Form

PRELIMINARY DATA

Date: 08 22-23 02 Operator: BSE Page 5 of 11
Location: TX Tank Farm Personnel: K. OLSON
Borehole Number: C3830 Rig Number: 106 Hammer: ICE 40S

BOREHOLE SPECIFIC DATA

Starter Casing Size: 7 inch O.D. Constant: 3.35 ft/3.1 top of plate/plate .25 ft
Drive Casing Size/Type: 4.5 inch O.D. Starter Casing Depth: 50.05
Tip Size/Type: 7.5 X 17.75 inch Total Depth: 56.99
Joint Type: Welded N/A Conical: 4.75 inch I.D.
Threaded 4.5 Pinpile

DEPTH	BLOWS/FT	AVE. STROKE	DRIVING TIME	TIP DEPTH
50.05 50.87	15		08:52	50.87
				N/A
50.87 51.87	15	N/A	09:08	
51.87 52.98	16		09:09	52.98
52.98 53.48	3	502083-07	11:11	
53.48 53.98	3		N/A	
53.98 54.36	2		11:12	N/A
52.98 53.98	11	N/A	13:24	
53.98 54.98	28		N/A	
54.98 55.98	34			
55.98 56.99	31		13:28	56.99
56.99 57.49	3	502083-08	14:25	
57.49 57.99	4		N/A	
57.99 58.37	2	N/A	14:26	N/A
58.29 58.79	2	502083-09	08:53	
58.79 59.29	2	N/A	N/A	

Prepared by: D.E. Skoglie Reviewed by: plaband 10-8-02



Duratek Federal Services, Inc.
Northwest Operations

TX Tank Farm Characterization Project Blow Count Form

PRELIMINARY DATA

Date: 08 23-26 02 Operator: BSE Page 6 of 11
Location: TX Tank Farm Personnel: K. OLSON
Borehole Number: C3830 Rig Number: 106 Hammer: ICE 40S

BOREHOLE SPECIFIC DATA

Starter Casing Size: 7 inch O.D. Constant: 3.35 ft/3.1 top of plate/plate .25 ft
Drive Casing Size/Type: 4.5 inch O.D. Starter Casing Depth: 56.99
Tip Size/Type: 7.5 X 17.75 inch Total Depth: 69.06
Joint Type: Welded N/A Conical: 4.75 inch I.D.
Threaded 4.5 Pinpile

DEPTH	BLOWS/FT	AVE. STROKE	DRIVING TIME	TIP DEPTH
59.29 59.7	2		08:53	
56.99 57.99	13		10:28	
57.99 58.99	15		N/A	N/A
58.99 59.99	12			
59.99 61.08	19		10:30	61.08
		N/A		
61.08 62.08	21		10:48	
62.08 63.08	30			N/A
63.08 64.08	39		N/A	
64.08 65.08	38			
65.08 66.08	38		10:52	66.06
66.06 66.56	2	502083-10	12:50	
66.56 67.06	2		N/A	
67.06 67.46	2		12:51	N/A
		N/A		
66.06 67.06	8		13:50	
67.06 68.06	27		N/A	
68.06 69.06	22			69.06

Prepared by: D.E. Skoglie Reviewed by: MLC/MLC 10-8-02



Duratek Federal Services, Inc.
Northwest Operations

TX Tank Farm Characterization Project Blow Count Form

PRELIMINARY DATA

Date: 08 26-27 02
Location: TX Tank Farm
Borehole Number: C3830

Operator: BSE
Personnel: K. OLSON
Rig Number: 106

Page 7 of 11
Hammer: ICE 40S

BOREHOLE SPECIFIC DATA

Starter Casing Size: 7 inch O.D. Constant: 3.35 ft/3.1 top of plate/plate .25 ft
Drive Casing Size/Type: 4.5 inch O.D. Starter Casing Depth: 69.06
Tip Size/Type: 7.5 X 17.75 inch Total Depth: 78.98
Joint Type: Welded N/A Conical: 4.75 inch I.D.
Threaded 4.5 Pinpile

DEPTH	BLOWS/FT	AVE. STROKE	DRIVING TIME	TIP DEPTH
69.06 70.06	23		N/A	N/A
70.06 71.06	25	N/A		
71.06 71.95	43		13:59	71.95
71.95 72.45	3	502083-11	07:37	
72.45 72.95	3		N/A	
72.95 73.3	1		07:38	
71.95 72.95	8		08:46	N/A
72.95 73.95	31	N/A		
73.95 74.95	35		N/A	
74.95 75.95	36			
75.95 76.98	38		08:52	76.98
76.98 77.48	3	502083-12	11:00	
77.48 77.98	4		N/A	
77.98 78.35	3		11:01	N/A
		N/A		
76.98 77.98	12		13:41	
77.98 78.98	22		N/A	78.98

Prepared by: D.E. Skoglie Reviewed by: M. Bland 10-8-02



Duratek Federal Services, Inc.
Northwest Operations

TX Tank Farm Characterization Project Blow Count Form

PRELIMINARY DATA

Date: 08-27-28-29-02 Operator: BSE Page 8 of 11
Location: TX Tank Farm Personnel: K. OLSON
Borehole Number: C3830 Rig Number: 106 Hammer: ICE 40S

BOREHOLE SPECIFIC DATA

Starter Casing Size: 7 inch O.D. Constant: 3.35 ft/3.1 top of plate/plate .25 ft
Drive Casing Size/Type: 4.5 inch O.D. Starter Casing Depth: 78.98
Tip Size/Type: 7.5 X 17.75 inch Total Depth: 89.06
Joint Type: Welded N/A Conical: 4.75 inch I.D.
Threaded 4.5 Pinpile

DEPTH	BLOWS/FT	AVE. STROKE	DRIVING TIME	TIP DEPTH
78.98 79.98	36		/	
79.98 80.91	38	N/A	13:46	80.91
80.91 81.41	4	502083-13	08:20	
81.41 81.91	4		/	
81.91 82.21	3		08:22	N/A
80.91 81.91	NOT			
81.91 82.91	RECORDED	N/A		
82.91 83.91	"			
83.91 84.91	"			
84.91 86.11	"			86.11
86.11 86.61	4	502083-14	N/A	
86.61 87.11	3			
87.11 87.41	3			N/A
86.11 87.06	26	N/A		
87.06 88.06	22			
88.06 89.06	21			89.06

Prepared by: D.E. Skoglie Reviewed by: [Signature] 10-8-02



Duratek Federal Services, Inc.
Northwest Operations

TX Tank Farm Characterization Project Blow Count Form

PRELIMINARY DATA

Date: 08 29 02 / 09 03 02 Operator: BSE Page 9 of 11
Location: TX Tank Farm Personnel: K. OLSON
Borehole Number: C3830 Rig Number: 106 Hammer: ICE 40S

BOREHOLE SPECIFIC DATA

Starter Casing Size: 7 inch O.D. Constant: 3.35 ft/3.1 top of plate/plate .25 ft
Drive Casing Size/Type: 4.5 inch O.D. Starter Casing Depth: 89.06
Tip Size/Type: 7.5 X 17.75 inch Total Depth: 99.97
Joint Type: Welded N/A Conical: 4.75 inch I.D.
Threaded 4.5 Pinpile

DEPTH	BLOWS/FT	AVE. STROKE	DRIVING TIME	TIP DEPTH
89.06 90.06	20			
90.06 91.06	19			
91.06 92.04	20			
92.04 93.04	24			
93.04 94.04	23			N/A
94.04 95.04	25	N/A	N/A	
95.04 96.04	26			
96.04 97.07	21			
97.07 98.11	24			
98.11 98.97	5			98.97
98.97 99.47	3	502083-15	08:44	
99.47 99.97	3		N/A	
99.97 100.36	2	N/A	08:45	
100.36 100.82	2	502083-16	12:13	N/A
100.82 101.32	2		N/A	
101.32 101.72	1	N/A	12:14	
98.97 99.97	9			99.97

Prepared by: D.E. Skoglie Reviewed by: McDonald 10-8-02



Duratek Federal Services, Inc.
Northwest Operations

TX Tank Farm Characterization Project Blow Count Form

PRELIMINARY DATA				
Date: <u>09-03-04 02</u>	Operator: <u>BSE</u>	Page <u>10</u> of <u>11</u>		
Location: <u>TX Tank Farm</u>	Personnel: <u>K. OLSON</u>			
Borehole Number: <u>C3830</u>	Rig Number: <u>106</u>	Hammer: ICE 40S		
BOREHOLE SPECIFIC DATA				
Starter Casing Size: <u>7 inch O.D.</u>	Constant: <u>3.35 ft/3.1 top of plate/plate .25 ft</u>			
Drive Casing Size/Type: <u>4.5 inch O.D.</u>	Starter Casing Depth: <u>99.97</u>			
Tip Size/Type: <u>7.5 X 17.75 inch</u>	Total Depth: <u>109.89</u>			
Joint Type: <u>Welded N/A</u>	Conical: <u>4.75 inch I.D.</u>			
	Threaded: <u>4.5 Pinpile</u>			
DEPTH	BLOWS/FT	AVE. STROKE	DRIVING TIME	TIP DEPTH
99.97 100.97	18			
100.97 101.97	17		N/A	N/A
101.97 102.99	20	N/A		102.99
102.99 103.49	2	S02083-17	07:58	
103.49 103.99	3		/	
103.99 104.44	2		07:59	
102.99 103.99	7			N/A
103.99 104.99	15			
104.99 105.99	17	N/A	N/A	
105.99 106.99	20			
106.99 107.89	22			107.89
107.89 108.39	2	S02083-18	12:28	
108.39 108.89	2		N/A	
108.89 109.19	2		12:29	N/A
107.89 108.89	12	N/A	N/A	
108.89 109.89	30			109.89
Prepared by: <u>D.E. Skoglie</u> Reviewed by: <u>[Signature] 10-8-02</u>				



Duratek Federal Services, Inc.
Northwest Operations

TX Tank Farm Characterization Project Blow Count Form

PRELIMINARY DATA

Date: 09 04 02
Location: TX Tank Farm
Borehole Number: C3830

Operator: BSE
Personnel: K. OLSON
Rig Number: 106

Page 11 of 11
Hammer: ICE 40S

BOREHOLE SPECIFIC DATA

Starter Casing Size: 7 inch O.D. Constant: 3.35 ft/3.1 top of plate/plate .25 ft
Drive Casing Size/Type: 4.5 inch O.D. Starter Casing Depth: 109.89
Tip Size/Type: 7.5 X 17.75 inch Total Depth: 116.75
Joint Type: Welded N/A Conical: 4.75 inch I.D.
Threaded 4.5 Pinpile

DEPTH	BLOWS/FT	AVE. STROKE	DRIVING TIME	TIP DEPTH
109.89 - 110.89	34			
110.89 - 111.89	24			
111.89 - 113.0	25	N/A	N/A	N/A
113.0 - 113.6	36			113.6
113.55 - 114.05	5	502083-19	09:12	
114.05 - 114.55	7		N/A	
114.55 - 115.0	6		09:13	
				N/A
113.6 - 114.0	13		12:30	
114.0 - 115.0	60			
115.0 - 116.0	78	N/A	N/A	
116.0 - 116.42	40			
116.42 - 116.75	54		12:47	116.75
			N/A	N/A

Prepared by: D.E. Skoglie

Reviewed by: [Signature] 10-8-02

This page intentionally left blank.

APPENDIX F
FIELD LOGBOOK ENTRIES

This page intentionally left blank.

Project TX-Borehole C3830
Continued from Page 34

Notebook No. DFSNW-SAWS-H55

08/20/02 - Start of Sampling job TX-105 (C3830) Borehole.
0700 - On Site, Attended prejob, starting TX-105 Borehole
first sample point 15-16 ft. K.J. Young Sampler.
0825 - started driving casing to first sample point.
1045 - Added sampler to drive string
1057 - drove sampler # S02083-02
1120 - collected sample, at 14.96 to 16.31 ft, No contamination
- Moisture present in soil at top of sampler, (soil shaken
out of air hole) 100% full
1240 - started driving casing to next sample point.
1415 - Added sampler to drive string
1430 - drove sampler # S02083-03
1448 - collected sample, from 27.91 - 29.25 ft, No contamination
no moisture, no soil present at top of sampler. 100%
1520 - left TX-Farm to ship samples to 3750 Lab
08/21/02
0640 - On Site, Attended prejob K.J. Young Sampler.
0742 - started driving casing to next sample depth. 41-42 ft
0853 - Added sampler to drive string
0918 - drove sampler # S02083-04
0940 - collected sample from 40.93 - 42.49 ft, No contamination
no moisture, 100% full, light colored soil in top of
sampler
1041 - Drove casing to next sample depth 46-47 ft
1110 - Added sampler to drive string.
1220 - Drove sampler to target depth of 46-47 ft # S02083-05
1250 - collected sample from 46.25 - 47.50 ft, No contamination
no moisture, 100% full, light colored soil in top of sampler
1310 - Added sampler to drive string.
1345 - left TX Farm to ship samples to 3720 building -
08/22/02
0650 On Site Attended prejob K.J. Young Sampler
0740 Drove sampler target depth 48-49 ft # S02083-06
0818 collected sample from 47.50 to 49.0 ft, No contamination
no moisture, 100% full, light colored fine soil in top of sampler
0911 - started driving casing to next sample depth 53-54 ft
Continued on Page

Read and Understood By

K.J. Young
Signed

8/22/02

Date

Signed

Date

Project TX Borehole 105 C3830
Continued from Page 35

Notebook No. DFSNW - SAWS - H55

1040 - Added sample to drive string 502083-07
1112 - Drove sampler target depth 53-54 ft.
~~1310~~ 1310 - BJT
1142 - Collected sample 52.98 to 54.36 ft No contamination
No moisture, 100% recovery
1310 - Drove casing to reach next target depth 57-58 ft
1405 - Added sample to drill string 502083-08
1422 - Drove sampler
1453 - Collected sample 56.99 - 58.37, No contamination
No Moisture 100% recovery
1520 - Added sample to drill 502083-09
1545 - Shipped samples to 3720 Lab.
8/23/02 -
0700 - Attended prejob K.J. Young Sampler.
on hold waiting for HPT coverage.
0840 - Drove sampler
0925 - Collected sample (502083-09) 58.29 - 59.70, No contamination
No moisture, 100% recovery, fine powder in air hole
0940 - Added casing and driving to next target depth of
66-67 ft.
1137 - Stopped driving case problem on drill rig.
1400 - left to ship sample to 3720 Lab
8/26/02 -
0715 - Attended prejob K.J. Young Sampler.
0740 - On hold waiting for drill rig repair.
1031 - Added casing and drove. Filled Equipment Blank 502083-01
1228 - Added sample to drive rod # 502083-10
Target depth of 66-67 ft.
1250 - Drove sampler.
1318 - Collected sample. 66.06 to 67.46, no contamination
no moisture, 100% recovery fine powder in air hole.
1356 - started driving casing for next target depth of
72-73 ft.
1510 - Added sample to drive rod, 502083-11.
1520 - left TX Farm to ship sample to TX-3720 Lab.
8/27/02
0650 - On Site Attended prejob K.J. Young (Sampler)

Continued on Page 37

Read and Understood By

K.J. Young
Signed

8/27/02

Date

Signed

Date

Project TX Borehole 105 C3830
Continued from Page 36

Notebook No. DPSNW-SAWS - H55

37

0732-	Drive Sample S02083-11 Target Depth 72-73 Ft
0810-	collected Sample. 71.95-73.30 Ft, No contamination no moisture, 100% full.
0816-	started Adding casing to reach next Sample point of 77-78 Ft
0920-	Drive casing
1038-	Added sampler to drill rod # S02083-12, Target depth of 77-78 Ft.
1100-	Drive sampler (#S02083-12)
1135-	collected Sample 76.98-78.35 Ft, No contamination No moisture, 100% recovery.
1250-	started driving casing for next Sample point 81-82 Ft
1440-	Added sampler to drive rod # S02083-13 ¹³⁷
1510-	left to ship samples to 3720 Lab.
8/28/02	
0645-	On Site Attended prejob. K.J. Young Sampler.
0720-	On hold waiting for HPT. 13
0819-	Drive Sample # S02083-16 Target depth 81-82 Ft.
0855-	collected Sample 80.91-82.12 ²¹ Actual depth No contamination No moisture 90% recovery
0910-	Added casing to reach next sample depth of 86-87 Ft
1323-	Added sampler to drive rod # S02083-14
1403-	Drive sampler Target depth of 86-87 Ft.
1440-	collected Sample. 86.11 to 87.41 Ft No contamination no moisture, 100% recovery Fine sand out of Air Hot
1520-	left to ship samples to 3720 Lab.
8/29/02	
710-	On Site Attended prejob / Safety meeting K.J. Young (Sampler)
850-	Added casing And driving to next sample depth of 99-100 Ft.
0922-	Added casing And driving.
1200-	Stopped driving casing, (lost HPT) No samples collected.
9/03/02	
700-	On Site waiting for pre job K.J. Young Sampler
805-	Added sampler to drill string.

Continued on Page 38

Read and Understood By

K.J. Young *[Signature]*
Signed

9/3/02
Date

Signed

Date

38

Project TX Borehole 105 C3830
Continued from Page 37Notebook No. DFSNW-SAWS-1155

Target depth of 99-100 ft SO2083-15
 0925 - collected sample 100% complete No Contamination / moisture
 1120 - Added sample to drill string SO2083-16 Target depth of 100-101 ft (back to back samples)
 1217 - Drove sampler.
 1306 - Collected sample 100.32-101.72 ft No contamination no moisture, 100% full (SO2083-16)
 1340 - left to ship samples to 3720 Lab.
 9/4/02
 0730 - attended project / Safety meeting K.J. Young sampler. casing was driven to next target depth of 103-104 ft on 9/3/02
 0745 - Added sampler to drill rod # SO2083-17
 0805 - drive sampler Target depth 103-104 ft
 0840 - collected sample 102.99 ft to 104.44 ft No contamination no moisture, no material through air hole 90% full.
 0903 - Added casing and driving to next sample depth 108 ft.
 1020 - Added sample to drive rod # SO2083-18
 1229 - Drive sampler Target depth of 108-109 ft.
 1311 - collected sample 107.89 - 109.19 ft No contamination No moisture, No soil in air hole 90% full.
 1340 - left TX Farm to ship samples to 3720 Lab.
 9/5/02 -
 0730 - on site attended project K.J. Young sampler
 0820 - Drive casing to next sample depth. Target depth of 119-120 ft.
 0905 - Added sample to drive rod # SO2083-19
 1000 - collected sample 113.55 to 115.00 ft
 No contamination, no moisture, 100% full
 1254 - Drive casing unable to reach next sample point of 119-120 ft
 This completes sampling of TX-105 and also completes sample of the TX project.

Continued on Page N/A

Read and Understood By

J. Young
Signed

9/5/02
Date

Signed

Date

APPENDIX G
EQUIPMENT CLEANING FORM


This page intentionally left blank.

6268 CLEANING FACILITY

EQUIPMENT CHECK OUT FORM

QUANTITY	ITEM	CUSTOMER	PROJECT	TPCN or WORK ORDER
21	Complete Split Spoons	S. Harold	Tx Borehole	

*All equipment has been cleaned per ES-SSPM-001 SP 2-5, "Laboratory Cleaning of RCRA/CERCLA Sampling Equipment.

Custodian Signature:  Print Name: K.S. Yang Date: 8/26/02
 Customer Signature: _____ Print Name: _____ Date: _____

This page intentionally left blank.

APPENDIX H

WASHINGTON STATE DEPARTMENT OF ECOLOGY DOCUMENTATION

This page intentionally left blank.



Notice of Intent to Construct a GEOTECHNICAL SOIL BORING

S 00632

This form must be received by the Department of Ecology 72 hours prior to construction of soil boring. Complete this form and mail to Department of Ecology, Water Resources Program, Well Drilling Unit, P.O. Box 47600, Olympia, WA 98504-7600. Instructions for filling out this form are printed on the back.

- Property Owner U.S. DEPARTMENT OF ENERGY Phone No. (509) 373 9630
Address (include city, state, zip) 825 JADWIN AVE., RICHLAND, WA. 99352
- Agent (if different from #1) DURATEK FEDERAL SERVICES NW Phone No. (509) 372 8029
Address (include city, state, zip) 345 Hills ST., RICHLAND, WA. 99352
- Project Name TX VADOSE ZONE PROJECT, BORING # C3830
- Well Location: NE 1/4 of the SW 1/4 Section 1 Township 12N Range 25 (EWM) (circle one)
Address (if known) HANFORD SITE, 200 WEST AREA, TX TANK WWM FARM
- Location of Well(s)

<input type="checkbox"/> Adams County	01-ERO	<input type="checkbox"/> Grays Harbor County	14-SWR	<input type="checkbox"/> Pierce County	27-SWR
<input type="checkbox"/> Asotin County	02-ERO	<input type="checkbox"/> Island County	15-NWR	<input type="checkbox"/> San Juan County	28-NWR
<input checked="" type="checkbox"/> Benton County	03-CRO	<input type="checkbox"/> Jefferson County	16-SWR	<input type="checkbox"/> Skagit County	29-NWR
<input type="checkbox"/> Chelan County	04-CRO	<input type="checkbox"/> King County	17-NWR	<input type="checkbox"/> Skamania County	30-SWR
<input type="checkbox"/> Clallam County	05-SWR	<input type="checkbox"/> Kitsap County	18-NWR	<input type="checkbox"/> Snohomish County	31-NWR
<input type="checkbox"/> Clark County	06-SWR	<input type="checkbox"/> Kittitas County	19-CRO	<input type="checkbox"/> Spokane County	32-ERO
<input type="checkbox"/> Columbia County	07-ERO	<input type="checkbox"/> Klickitat County	20-CRO	<input type="checkbox"/> Stevens County	33-ERO
<input type="checkbox"/> Cowlitz County	08-SWR	<input type="checkbox"/> Lewis County	21-SWR	<input type="checkbox"/> Thurston County	34-SWR
<input type="checkbox"/> Douglas County	09-CRO	<input type="checkbox"/> Lincoln County	22-ERO	<input type="checkbox"/> Wahkiakum County	35-SWR
<input type="checkbox"/> Ferry County	10-ERO	<input type="checkbox"/> Mason County	23-SWR	<input type="checkbox"/> Walla Walla County	36-ERO
<input type="checkbox"/> Franklin County	11-ERO	<input type="checkbox"/> Okanogan County	24-CRO	<input type="checkbox"/> Whatcom County	37-NWR
<input type="checkbox"/> Garfield County	12-ERO	<input type="checkbox"/> Pacific County	25-SWR	<input type="checkbox"/> Whitman County	38-ERO
<input type="checkbox"/> Grant County	13-ERO	<input type="checkbox"/> Pend Oreille County	26-ERO	<input type="checkbox"/> Yakima County	39-CRO
- Total number of borings to be constructed 1
- Approx soil boring construction date July 01, 2002
- Well Drilling Co Name BLUE STAR ENTERPRISES Phone No. (509) 946 9388
- Well Driller's Name MR. KELLY OLSON Driller's License No. 1217
- Contractor's L & I Registration No. BLUESEI 980CG
- Please fill out the portion below carefully. The return address label must contain the name and address of the person submitting this notification. This portion will be validated and returned to them as proof of notification. Send the entire form to Department of Ecology, Water Resources Program, Well Drilling Unit, P.O. Box 47600, Olympia, WA 98504-7600.

This notification number must be provided to your well driller:

S 00632

Submit by (return address)

Name MR. MARTIN G. GARDNER
Mailing Address 345 Hills ST.
City RICHLAND State WA Zip 99352

Agency Validation

Date _____



Duratek Federal Services, Inc.
Northwest Operations

345 Hills Street
Richland, Washington 99352
(509) 376-7055 - Phone
(509) 372-1435 - Fax

October 17, 2002

MGG-02-2423

Mr. Joe A. Caggiano
State of Washington
Department of Ecology
1315 West 4th Avenue
Kennewick, Washington 99336

Dear Mr. Caggiano:

WATER WELL REPORT

Attached is a Water Well Report for well C3830. Well C3830 is located in the 200 West Area (TX Tank Farm) at coordinates N136166.88, E 566795.41, and elevation 206.085.

Please reference Start Card numbers S00632 (Notice of Intent to Construct a Geotechnical Boring).

Should you have any questions, please contact me at (509) 372-8029.

Very truly yours,

A handwritten signature in dark ink, appearing to read "M. G. Gardner", with a stylized flourish at the end.

M. G. Gardner, Manager
Sampling and Well Services

jmt

Attachment

CHG - A. J. Knepp
H. A. Sydnor

FH - J. E. Auten

DFSNW - K. R. Reynolds
D. E. Skoglie
S. H. Worley
MGG File/LB
CHG/RC3011



WATER WELL REPORT

Original & 1st copy - Ecology, 2nd copy - owner, 3rd copy - driller

Construction/Decommission ("x" in circle)

☒ Construction

☐ Decommission ORIGINAL CONSTRUCTION Notice
of Intent Number S00632

PROPOSED USE: ☐ Domestic ☐ Industrial ☐ Municipal Sensors
☐ DeWater ☐ Irrigation ☐ Test Well ☒ Other Moisture

TYPE OF WORK: Owner's number of well (if more than one) C3830
☒ New Well ☐ Reconditioned Method: ☐ Dug ☐ Bored ☒ Driven
☐ Deepened ☐ Cable ☐ Rotary ☐ Jetted

DIMENSIONS: Diameter of well 7.5 inches, drilled 116.75 ft.
Depth of completed well 98.95 ft.

CONSTRUCTION DETAILS

Casing ☐ Welded ☐ Diam. from _____ ft. to _____ ft.
Installed: ☐ Liner installed ☐ Diam. from _____ ft. to _____ ft.
☒ Threaded 7.0" Diam. from 0 ft. to 116.75

Perforations: ☐ Yes ☒ No

Type of perforator used _____
SIZE of perfs _____ in. by _____ in. and no. of perfs _____ from _____ ft. to _____ ft.

Screens: ☐ Yes ☒ No ☐ K-Pac Location _____

Manufacturer's Name _____
Type _____ Model No. _____
Diam. _____ Slot Size _____ from _____ ft. to _____ ft.
Diam. _____ Slot Size _____ from _____ ft. to _____ ft.

Gravel/Filter packed: ☐ Yes ☒ No ☐ Size of gravel/sand _____
Materials placed from _____ ft. to _____ ft.

Surface Seal: ☐ Yes ☒ No To what depth? _____ ft

Materials used in seal _____

Did any strata contain unusable water? ☐ Yes ☐ No

Type of water? _____ Depth of strata _____

Method of sealing strata off _____

PUMP: Manufacturer's Name _____

Type: _____ H.P.

WATER LEVELS: Land-surface elevation above mean sea level _____ ft.

Static level _____ ft. below top of well Date _____

Artesian pressure _____ lbs. per square inch Date _____

Artesian water is controlled by _____
(cap, valve, etc.)

WELL TESTS: Drawdown is amount water level is lowered below static level.

Was a pump test made? ☐ Yes ☒ No If yes, by whom? _____

Yield: _____ gal./min. with _____ ft. drawdown after _____ hrs.

Yield: _____ gal./min. with _____ ft. drawdown after _____ hrs.

Yield: _____ gal./min. with _____ ft. drawdown after _____ hrs.

Recovery data (time taken as zero when pump turned off) (water level measured from well top to water level)

Time	Water Level	Time	Water Level	Time	Water Level
_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____

CURRENT

Notice of Intent No. S00632

Unique Ecology Well ID Tag No. N/A

Water Right Permit No. N/A

Property Owner Name U.S. Department of Energy

Well Street Address 825 Jadwin Avenue

City Richland County: Benton

Location NE 1/4- 1/4 SW 1/4 Sec. 1 Twn 12 R 25 EWM circle
or one
WWM

Lat/Long: N136166.88
(s, r still Lat Deg Lat Min/Sec
REQUIRED) E566795.41 EL: 206.085
Long Deg Long Min/Sec

Tax Parcel No. _____

CONSTRUCTION OR DECOMMISSION PROCEDURE

Formation: Describe by color, character, size of material and structure, and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of information. Indicate all water encountered.
(USE ADDITIONAL SHEETS IF NECESSARY.)

MATERIAL	FROM	TO
Construction Details:		
Driving Casing:		
Drive 7-in. O.D. casing/ shoe to total depth.	0	116.75
Sand/gravel	0	109.0
Caliche	109.0	116.75
Back fill/back pull	116.75	101.19
Casing Bentonite	96.25	55.25
	49.95	10.6
	7.45	6.9
	2.9	2.15
Install Tensiometer	101.19	96.25
Install Tensiometer	55.25	49.95
Install Tensiometer	10.6	7.45
Install Tensiometer	6.9	2.9
Natural fill added	2.15	0

Start Date 08/20/2002 Completed Date 09/19/2002

WELL CONSTRUCTION CERTIFICATION: I constructed and/or accept responsibility for construction of this well, and its compliance with all Washington well construction standards. Materials used and the information reported above are true to my best knowledge and belief.

☐ Driller ☒ Engineer ☐ Trainee Name (Print) D. E. Skoglie Drilling Company Duratek Federal Services, Inc.

Driller/Engineer/Trainee Signature David E Skoglie Address 345 Hills Street

Driller or Trainee License No. 1580 City, State, Zip Richland, WA 99352

If trainee, licensed driller's _____ Contractor's
Signature and License no. _____ Registration No. DURATFS990K5 Date 10/16/02


Ecology is an Equal Opportunity Employer. ECV 050-1-20 (Rev 4/01)


This page intentionally left blank.

APPENDIX I
VADOSE ZONE TENSIO METER PLACEMENT

This page intentionally left blank.

C3830 INSTRUMENTATION





Reynolds, Kent

From: "Gee, Glendon W" <glendon.gee@pnl.gov>
[GTSD_HQ.GTSD_HQ_GWIA."glendon.gee@pnl.gov"] on behalf of
GTSD_HQ.GTSD_HQ_GWIA."glendon.gee@pnl.gov"
Sent: Tuesday, September 10, 2002 4:07 PM
To: GTSD_HQ.GTSD_HQ_GWIA."Harold_A_Sydnor@rl.gov"; Reynolds, Kent; Skoglie,
Dave; Gardner, Marty
Subject: RE: Sensor Placement



Mime.822

Kent: These plans are okay for us. We have extra long cable for contingency purposes so all should be fine as far as cable length and the sensors are not constrained by the proposed placement depths in any way.

gwg

-----Original Message-----

From: Reynolds, Kent D
Sent: Tuesday, September 10, 2002 3:48 PM
To: Sydnor, Harold A; Gardner, Martin G (Marty); Skoglie, David E; Gee,
Glendon W
Cc: Knepp, Anthony J
Subject: Sensor Placement

Mr. Sydnor and I have reviewed the draft Moisture Logs generated in the field from C 3830 (TX-105). Several zones appear to be favorable for sensor placement and percolation testing.

For the sensor planned for approximately 100 ft BGS. Percolation test recommended for 104 to 106 ft BGS. Sample number S02083-17 was taken from 102.99 to 104.44 ft BGS and can provide laboratory derived data on lithology, moisture content, chemistry, etc. Moisture log data indicate the zone be at approximately 11% moisture content by volume. Lithology is assumed to be silt and fine to medium sand interbeds of the Cold Creek facies.

Sensor placement recommended to be 97.5 to 99 ft BGS Sample number S02083-15 was taken from 98.97 to 100.36 ft BGS and can provide laboratory derived data on lithology, moisture content, chemistry, etc. Moisture log data indicate the zone be at approximately 9% moisture content by volume. Lithology is assumed to be interbedded fine to medium sands and silts of the lower Hanford immediately above the Cold Creek.


Sensor planned at 50 ft. BGS

Percolation test recommended for 57 to 59 ft BGS. Sample numbers S02083-08 and 09 were taken from 56.99 to 59.7 ft BGS and can provide laboratory derived data on lithology, moisture content, chemistry, etc. Moisture log data indicate the zone be at approximately 8% moisture content by volume. Lithology is assumed to be medium to fine sands with some silt interbeds typical of Hanford sand facies.


Sensor placement recommended for 52-53.5 ft BGS. Sample number S02083-07 was taken from 52.98 to 54.36 ft BGS and can provide laboratory derived data on lithology, moisture content, chemistry, etc. Moisture log data indicate the zone be at approximately 8% moisture content by volume. Lithology is assumed to be medium to fine sands with some silt interbeds typical of Hanford sand facies.

Note: The samples from this probe hole are presently archived and are not planned to be opened until FY 03 at the PNNL 300 Area Laboratory. Therefore data pertaining to actual lithology and physical properties will not be available until some time into FY03.

Perc Test #1
(103.54 to 105.9 ft BGS)



Perc Test #2
(57.01 to 59.05 ft. BGS)



APPENDIX J
NOISE MONITORING

This page intentionally left blank.



Duratek

Federal Services

Date: May 16, 2002
Time: 07:00 am
Location: TX Farm

Inspectors: Jason Sweesy/Duratek Safety

TX-TY Borehole Drilling

Report # 02-005

Background: Borehole drilling and sampling for characterization and migration of plumes found underground.

Citation	Findings
<p>1. Completed real time noise survey of generator located to the north of the support area.</p>	<p>81 dB</p> <p>Generator</p> <p>Hearing Protection Boundry Line</p> <p>83 dB</p> <p>Approx. 3 Feet</p> <p>Exhaust Fan</p> <p>95 dB</p> <p>86 dB</p> <p>Support Trailers ~ 15 ft</p> <p>North</p>


COMMENTS:

General area monitoring was conducted with a Metrosonic dB-3100 Sound Analyzer (5711) calibrated with a Metrosonics acoustical calibrator (102 dB before and after; calibrated 12/20/01). Peak value was from the generator fan directly at the discharge. Informed client person In charge (PIC) of the results and analysis with recommendation to keep loitering around the postings to a minimum. According to the PIC the area outside of the boundaries is not occupied other than occasional foot traffic. The generator only runs when drilling operations are being conducted.

Analysis:

Hearing boundary postings are adequate for the site conditions. Minimal foot traffic with no personnel at the boundary greater than 4 hours. Should there be a need to be adjacent to the boundary for greater than 4 hours, a re-evaluation of the noise levels shall be conducted.

TX Tank Farm MAPR



OverAll Lav = 93.8dB

Over Range

Lpk

Lmax

Lav

Summary Report

Test Location.....TX Tank Farm
Employee Name....Kelly Olson
Employee Number...0029732
Department.....Blue Star Employee
Comment.....performed normal borehole drilling activities. Good range of work duties.

Metrosonics db-3100 SN 5711 V1.7
Report Printed 05/15/02 at 07:25
Exchange Rate...3 dB
Filter...A Wt.
Dose Criterion....85 dB
Response.....Slow

Calibrator Type.....Accustical SN..6114
Calibrator and Calibration Date..12/20/01

Pre-Test Calibration Time: 05/14/02 at 06:30
Pre-Test Calibration Range: 40.3dB to 140.3dB

Post Calibration 05/15/02 at 06:25

Test Began.....05/14/02 at 07:14
Test Length....0 Days 08:22
Test Ended...05/14/02 At 15:36

Lav.....93.8dB
Lav (80)...93.8dB
Lav (90)...93.1dB
SEL.....138.5dB

TWA.....94.0dB
TWA (80)..94.0dB
TWA (90)..93.3dB

Lmax...117.8dB on 05/14/02 at 15:21
Lpk.....141.0dB on 05/14/02 at 15:22

Time Over 115.0dB 0 Days 00:00:04

8 HR % Dose (80dB Cutoff).....804.09%
8 HR % Dose (90dB Cutoff).....687.61%

This page intentionally left blank.